

TENDER SCHEDULE

NAME OF WORK : Construction of 6 Seats Toilet at L.M. Colony in Kolappalur Town Panchayat.

Estimate Amount : Rs. 7,00,000

SL. NO.	QTY.		DESCRIPTION OF WORK	TNDSS NO.	RATE IN		UNIT
					Figure	WORDS	
1	56.00	M ³	Earth Work is All Soils Except hard rock requiring plasting and conveyance for formation of bund with leed of 0 mtr to 100 mtr deploying earth moving mechinry and tippers including benching, formation of bunds, breaking clods, Sectioning etc., complete (for Hard Rock, Mediem Rock, dense Medium Rock not required Blasting (SR SI NO.86)				One Cubic Metre
2	7.60	M ³	Plain Cement Concrete 1:4:8 Mix (one part cement, five part sand and ten part of aggrigate) using 40 mm size ISS HBG metal from approved quarry including cost and conveyance of all materials to site. loading and unloading charges and labour charges for mixing. Laying and curing etc. complete. Complying with std. specifications.				One Cubic Metre

3	13.00	M ³	Brick Work in Cement Mortar 1:5 Mix (one cement, five sand) using new best II class Bricks of size 9 x 4 1/2 x 3 from approved quarry including cost and conveyance of all materials to site. loading and unloading charges and labour charges for mixing, laying and curing etc. complete. complying with std. specifications				One Cubic Metre
4	9.00	M ³	Supply and fixing of Bison Door including cost and conveyance of all materials to site and all labour charges etc., complete as per stand specification.				One Cubic Metre
5			Centering for sides and soffits RCC slab (or) plane surface including strutting 3m height including cost and conveyance & all labour charges etc., complete				One Square Metre
	42.00	M ²	Square Column				
	41.00	M ²	Footings & Plinth Beam				
	35.91	M ²	Roof Slab				
6	1500.00	M ²	Supply and fabrication of steel including cost and conveyance of al materials to site and all labour charges etc., to complete as per std., specification.				One Square Metre
7	17.42	M ²	Rein forced cement concrete 1:1.5:3 mix using 20mm ISS HBG metal including cost and conveyance of all materials to site and all labour charges etc., to complete as per std., specification.				One Square Metre
8	45.60	Kg	Plastering with cm 1:3 mix using 10 mm thick metal including cost and conveyance and all labour charges etc., complete				One Square Metre

9	154.16	M ³	Plastering with cement mortal 1:5 mix using 12 mm thick including cost and conveyance of all materials to site and all labour charges etc., complete as per stand specification.				One Square Metre
10	106.80	M ²	Dadoing the walls with best approved quality colour glazed tiles of size 100 x 200 x 6mm set in CM 1:2 (One of cement and two of sand) 10mm thick and pointing with colour cement using 0.4kg per m2 neatly in all floors as directed etc., complete complying with standard specifications.				One Square Metre
11	30.00	M ²	Floor finishing with Ceramic tiles of size 30cm x 30cm x 6mm over the base plastering cement mortar 1:3 mix, 20mm thick pointing with using white cement 4kg/10sq.mt. including cost and conveyance of all materials and all labour charges.				One Square Metre
12	6.00	M ²	Supply and fixing in Position best quality of approved make Indian type Water closet of 10 litres capacity with all accessories such as P” trap or S trap confirming to IS with sand cushion and forming flooring around the closet using 40mm leveling course 1:4:8-100 mm thick and finishing the top to the required slope and including necessary internal connection and outlet connection and making the disturbed position to original condition without leakage etc. including labour charges.				One Square Metre
13	147.76	M ²	Painting two coats using approved colour with emulsion paint including coat and conveyance of all materials at site and all labour charges etc., complete.				One Square Metre

14	16.00	No	Painting two coats with best approved enamel paint for new Iron work including cost and conveyance etc., complete.				One number
15	17.00	M ²	Collection, supply and filling with well gravel including cost and conveyance of all materials and stacking them at road side to departmental gauge for pre-measurement including all labour charges for filling etc., complete as per standard specification.				One Square Metre
16	6.00	Ltr	Laying and jointing of RCC Jolly (0.60 X 0.45m) including cost and conveyance of all materials to site and all labour charges etc., complete as per stand specification.				One Liter
17	2000.00	Ltr	Supply and fixing 2000 ltr PVC Tank including cost and conveyance of all materials to site and all labour charges etc., complete as per stand specification.				
18	10.00	No	Wiring with 2x1.5(22/0.3) sqmm PVC insulated unsheathed SC Copper conductor of 1100 V grade in suitable PVC rigid pipe concealed on wall and ceiling with PVC accessories in flush with wall with hylum sheet of 3mm thick cover with TW Switch box and 5A F.T switch with painting of suitable colour with continuous earth wireconnection of 14 SWG wire for Conceled Light point/fan point (For Electronic regulator)[SD NO 23]				
19	10.00	No	Supply and fixing of WT bulk head fitting with guard (Philips / Bajaj / Crompton / K. Lite) suitable for 11W CFL lamp with CFL. (SD 83)				


20	20.00	M	Supply and run of 4 x 6 sq.mm.(56Nos/0.3mm.Dia) PVC insulated single core unsheathed copper conductor cable of 1100 V on 7/20 G.I. bearer wire for service connection mains (SD 68)				
21	4.00	M	Supply and Run of 4 x 4 sq.mm(84/0.3) PVC insulated Sc unsheathed Cu.Conductor of 1100V grade in 25mm dia G.I pipe ("B"class) suitable bend at both ends with necessary angle iron up right and end supports for mains.SD-73)				

Junior Engineer
Kugalur Town Panchayats(G),
Erode District

Assistant Executive E
Town Panchayats
Erode District

AMOUNT

[illegible]



Engineer,
ats,
t.