

TENDER SCHEDULE

NAME OF WORK : Construction of 8 Seats Community Toilet at Ward No 4, Vettuvanpudur in Periyakodiveri Town Panchayat (S.F.196/48)

Estimate Amount : Rs. 12,00,000.00

SL. NO.	QTY.		DESCRIPTION OF WORK	TNDSS NO.	RATE IN		UNIT	AMOUNT
					Figure	WORDS		
1	111.00	M ³	Earth work excavation and depositing on bank with initial lead of 10 meters and initial lift of 2 meters in hard stiff clay, stiff block cotton hard red earth, murrains, gravel stoney earth and earth mixed with small size boulders and hard gravel soil etc., complete as per standard specification				One Cubic Metre	
2	12.00	M ³	Plain Cement concrete 1:4:8 mix using 40mm HBG metal for foundation and flooring including cost and conveyance of all materials to site and all labour charges for mixing, laying and curing etc., complete as per standard specification				One Cubic Metre	
3			Supplying and erecting centering to sides and soffits including supports and strutting with necessary cross bracing for plain surface such as RCC slabs rectangular beams all beams lintels etc. Centering for soffits of RCC slabs plain surface including strutting upto 3 meter height using mild steel sheet of size 90cmx60cmx10 gauge with MS angles of size 25mmx2mmx3mm laid over silver oak (CW) joists of size 10cmx6cm spaced upto 90cm c/c and supported casurina props or 10cm to 13cm dia spaced at 0.750cm c/c complying with standard specification					

SL. NO.	QTY.		DESCRIPTION OF WORK	TNDSS NO.	RATE IN		UNIT	AMOUNT
					Figure	WORDS		
	42.00	M ²	A) Footing, side wall & Grade Beam				One Square Metre	
	31.00	M ²	B) For Coloumn				One Square Metre	
	47.00	M ²	C) For Roof				One Square Metre	
4	1500.00	kg	Supplying and fabrication placing in postion of M.S. (or) RTS rods for required size and length as directed by the departmental officers approved design including bending cutting tying and cost of binding wire cost and conveyance of all materials to site etc., complete as per standard specification				One Kilo Gramme	
5	17.00	M ³	Reinforced cement concrete 1:1/2:3 mix using 20mm ISS metal from the approved quarry including mixing, laying, consolidating, curing cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification				One Cubic Metre	
6	19.00	M ³	Collection, supply and filling with well gravel including cost and conveyance of all materials and stacking them at road side to departmental gauge for pre-measurement including all labour charges for filling etc., complete as per standard specification.				One Cubic Metre	

SL. NO.	QTY.		DESCRIPTION OF WORK	TNDSS NO.	RATE IN		UNIT	AMOUNT
					Figure	WORDS		
7	41.00	M ³	Brick work in cement mortar 1:5 mix using using best quality of country bricks of size 22cmx11cmx7cm) for foundation including curing cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification				One Cubic Metre	
8	116.00	M ²	Plastering with cement mortar 1:3 mix to 10mm thick including curing cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification				One Square Metre	
9	70.00	M ²	Plastering with cement mortar 1:3 mix to 20mm thick including curing cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification				One Square Metre	
10	372.00	M ²	Plastering with cement mortar 1:5 mix to 12mm thick including curing cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification				One Square Metre	
11	29.00	M ²	Laying with new C.C. Laminated tiles (Like Dora tiles Eurocon tiles etc),(anti skid) of 20mm thick of approved spl quality and set in Cement Mortar 1:3 (1 of cement and 3 of M-sand) 20mm. Thick using river sand and pointing with colour cement using at the rate of 0.40 kg/M2 and mixing with colour pigment at the rate of 0.3 Kg/M2 including finishing complete with Standard Specification and as directed by the Departmental Officers etc.,				One Square Metre	

SL. NO.	QTY.		DESCRIPTION OF WORK	TNDSS NO.	RATE IN		UNIT	AMOUNT
					Figure	WORDS		
12	94.00	M ²	Dadooring Wall glazed Tiles of 20cmx20cmx6cm of approved make and quality and colour set in cement mortar 1:2 mix and pointing with white cement heatly as dieced including cost and conveyance of all materials to site and all labour charges. etc. complete.				One Square Metre	
13	432.00	M ²	Exterior Emulsion paint Two coats with good quality of approved Emulsion paint including cost of all materials to site and all labour charges for mixing applying and proper curring etc., Complete as per Standard Specifications for 10 sqm				One Square Metre	
14	14.00	M ²	Supplying and fabrication and fixing in position of anodised natural colour matt fininsh sliding window in TWO track in all floors with following sizes. All the two shutters with slinging entering and made with UPVC (ultra Polyvinyl Chloride) section for outer frames as shown below with necessary accessories such rubber beading.clips, handle and fixing 5 mm thick clear sheet glass including all				One Square Metre	
15	8.00	Nos	Supply and fixing of RCC Jolly of Size 0.45 x 0.45 m inclduing cost and conveyance of all materials to site and all other labour charges etc., complete as per stanard specification				Each	
16	150.00	kg	Supply and fixing of MS Grill Gate for Entrance including cost and conveyance of all materials to site and all other labour charges etc., to complete as per std., specification.				One Kilo Gramme	

SL. NO.	QTY.		DESCRIPTION OF WORK	TNDSS NO.	RATE IN		UNIT	AMOUNT
					Figure	WORDS		
17	8.00	Nos	Supply and fixing in position of indian make colour water closet of size 58 cm (23inches) oriissa pan type with P or S trap and with sand cushion and etc., complete with necessary connection including cost and conveyance of all materials to site and all labour charges etc., complete as per statard specification				Each	
18	4.00	No	Supply and fixing of manhole cover including cost and conveyance of all materials to site and all other labour charges etc., to complete as per std., specification.				Each	
19	1.00	No	Supply and fixing of A.C. Pipe with cowl including cost and conveyance of all materials to site and all other labour charges etc., to complete as per std., specification.				Each	