

TENDER SCHEDULE

NAME OF WORK : Construction of 8 Seats Community Toilet Block at Ward No.01, Muthugoundanur in Jambai Town Panchayat

Estimate Amount : Rs. 12,00,000.00

SL. NO.	QTY.		DESCRIPTION OF WORK	TNDSS NO.	RATE IN		UNIT	AMOUNT
					Figure	WORDS		
1	100.00	M ³	Earth work excavation and depositing on bank with initial lead of 10 meters and initial lift of 2 meters in hard stiff clay, stiff block cotton hard red earth, murrains, gravel stoney earth and earth mixed with small size boulders and hard gravel soil etc., complete as per standard specification				One Cubic Metre	
2	11.00	M ³	Plain Cement concrete 1:5:10 mix using 40mm HBG metal for foundation and flooring including cost and conveyance of all materials to site and all labour charges for mixing, laying and curing etc., complete as per standard specification				One Cubic Metre	
3	115.00	M ²	Supplying and erecting centering to sides and soffits including supports and strutting with necessary cross bracing for plain surface such as RCC slabs rectangular beams all beams lintels etc. Centering for soffits of RCC slabs plain surface including strutting upto 3 meter height using mild steel sheet of size 90cmx60cmx10 gauge with MS angles of size 25mmx2mmx3mm laid over silver oak (CW) joists of size 10cmx6cm spaced upto 90cm c/c and supported casurina props or 10cm to 13cm dia spaced at 0.750cm c/c complying with standard specification				One Square Metre	

SL. NO.	QTY.		DESCRIPTION OF WORK	TNDSS NO.	RATE IN		UNIT	AMOUNT
					Figure	WORDS		
4	1750.00	kg	Supplying and fabrication placing in position of M.S. (or) RTS rods for required size and length as directed by the departmental officers approved design including bending cutting tying and cost of binding wire cost and conveyance of all materials to site etc., complete as per standard specification				One Kilo Gramme	
5	16.00	M ³	Reinforced cement concrete 1:1/2:3 mix using 20mm ISS metal from the approved quarry including mixing, laying, consolidating, curing cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification				One Cubic Metre	
6	12.00	M ³	Collection, supply and filling with well gravel including cost and conveyance of all materials and stacking them at road side to departmental gauge for pre-measurement including all labour charges for filling etc., complete as per standard specification.				One Cubic Metre	
7	28.00	M ³	Brick work in cement mortar 1:5 mix using using best quality of country bricks of size 22cmx11cmx7cm) for foundation including curing cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification				One Cubic Metre	
8	30.00	M ²	Plastering with cement mortar 1:3 mix to 10mm thick including curing cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification				One Square Metre	

SL. NO.	QTY.		DESCRIPTION OF WORK	TNDSS NO.	RATE IN		UNIT	AMOUNT
					Figure	WORDS		
9	45.00	M ²	Plastering with cement mortar 1:3 mix to 20mm thick including curing cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification				One Square Metre	
10	130.00	M ²	Plastering with cement mortar 1:5 mix to 12mm thick including curing cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification				One Square Metre	
11	25.00	M ²	Floor finishing with fully scratch ceramic tiles using best quality of fully vscratch ceramic tiles of size 30cm x 30cm x 6mm over the base plastering cement mortar 1:3 mix, 20mm thick pointing with using white cement 4kg/10sq.mt. inculing cost and conveyance of all materials and all labour charges. Etc. complete.				One Square Metre	
12	46.00	M ²	Dadooring Wall glazed Tiles of 20cmx20cmx6cm of approved make and quality and colour set in cement mortar 1:2 mix and pointing with white cement heatly as dieced including cost and conveyance of all materials to site and all labour charges. etc. complete.				One Square Metre	
13	16.00	M ²	White washing one coat with well burnt shell lime blue gum including all labour charges cost and conveyance of all materials to site etc., complete as per standard specification - 100m2				One Square Metre	
14	70.00	M ²	Exterior Emulsion paint Two coats with good quality of approved Emulsion paint including cost of all materials to site and all labour charges for mixing applying and proper curring etc., Complete as per Standard Specifications				One Square Metre	

SL. NO.	QTY.		DESCRIPTION OF WORK	TNDSS NO.	RATE IN		UNIT	AMOUNT
					Figure	WORDS		
15	12.00	M ²	Supply and fixing of bision shutter door of size 0.80 x 1.80 m including cost and conveyance of all materials to site and all labour charges etc., complete				One Square Metre	
16	8.00	Nos	Supply and fixing of RCC Jolly of Size 0.60 x 0.45 m inlcluding cost and conveyance of all materials to site and all other labour charges etc., complete as per stanard specification				One Number	
17	100.00	kg	Supply and fixing of MS Grill Gate for Entrance including cost and conveyance of all materials to site and all other labour charges etc., to complete as per std., specification.				One Kilo gram	
18	8.00	Nos	Supply and fixing in position of indian make colour water closet of size 58 cm (23inches) oriissa pan type with P or S trap and with sand cushion and etc., complete with necessary connection including cost and conveyance of all materials to site and all labour charges etc., complete as per statard specification				Number	
19	1.00	Nos	Geophysical survey charges for water resource point at Gandhi Nagar Proposed Toilet Area including cost and conveyance of all materials to site and all other labour charges etc., complete				Number	
20	180.00	M	Drilling of 150mm dia deep borewell including cost and conveyance of all materials to site and all other labour charges etc., complete				One Metre	
21	6.00	M	Supply and Fixing of 165mm Dia PVC causing pipe including cost and conveyance of all materials to site and all other labour charges etc., complete				One Metre	

SL. NO.	QTY.		DESCRIPTION OF WORK	TNDSS NO.	RATE IN		UNIT	AMOUNT
					Figure	WORDS		
22	2000.00	Lit	Supply and Fixing of 2000 Lit Capacity HDPE Tank including cost and coveyance of all charges etc., complete				One Litre	
23	1.00	Nos	Supply and delivery of 5HP Sub-mersible motor 50LPMx175M with out panel board and all accessories including cost and conveyance of all charges etc., complete(IS 8034 SI No7)				One Number	
24	1.00	Nos	Supply and delivery of 5HP Sub-mersible Motor 3 Phase panel board including cost and conveyance of all charges etc., complete				One Number	
25	210.00	M	Supply and deliver of 4.00 sq. mm cable including cost and conveyance of all materials to site and all other labour charges etc., complete				One Metre	
26	1.00	No	Towards Labour Charge for Errection of 5 HP Motor including cost and coveyance of all charges etc., complete				One Number	
27	100.00	M	Supply and delivery of 2" Dia PVC Pipe including cost and conveyance of all materials to site and all other labour charges etc., complete				One Metre	
28	100.00	M	Towards the cost of charges for Laying and Joining of PVC and GI Pipes with specials including cost and conveyance of all charges etc., complete				One Metre	
29	100.00	M ³	Refilling the excavated earth other than sand complying with std., specifications				One Cubic Metre	
30	5.00	M ²	Painting two coats Using best quality of Enamal paint including cost and conveyance of all materials to site and all other labour charges etc., complete				One Square Metre	