

TENDER SCHEDULE

Name of the Work: Conservation works in temple complex in Arulmigu Kalaththeeswarar Temple at Panappakkam Village, Nimili Taluk in Ranipet District.

Value Of Tender: Rs.3387302/-

Date of tender :7.6.2022

Cost Of EMD : Rs.27000/-

Period Of Completion : 4 Month

Sl. No.	Quantity		Description of item	Rate		Per	Amount
	In Figure	unit		In Figure	In Words		
1	447.00	m2	Labour charges for removing weathering course and pressed tiles from the sannathi roof and including removing all debris from site of work			1 Sqm	
2	86.00	m2	Labour charges for removing the ceramic tiles from walls including removing all debris from site of work			1 Sqm	
3	1440.00	Sqm	Cleaning the stone surfaces by water washing the stone elements like wall, pillar, uthiram, pothiyal, pavukal and etc., including cost of material and labour charges etc.,.			1 Sqm	
4	40.00	Sqm	Plastering with Lime mortar 1:1.5,12mm thick including cost and conveyance of all materials and labour charges,curing etc,complete complying with standard specifications.			1 Sqm	
5	103.00	Cum	Weathering course concrete with broken brick jelly 20mm size uniform gauge in pure slaked lime no sand to be added over RCC roof slab, the proportion being 32:12.5 by volume for required depth of giving required slope and thickness of roof, well beaten with wooden beater of approved pattern, keeping the surface constanthy wet by sprinkly lime jaggery water etc, complete as per standard specifications			1 Cum	

Signature of Executive Officer

No.of Correction/Overwriting:

Signature of Contractor

Sl. No.	Quantity		Description of item	Rate		Per	Amount
	In Figure	unit		In Figure	In Words		
6	445.00	m2	Finishing the top of roof with one course of machine pressed tiles 20cmx 20cmx20mm of approved quality laid in lime mortar 1:1.5,12mm thick mixed with water proofing compound 2% by weight of cement used and joints pointed neatly to full depth of tiles with same mortar mixed with red oxide and water proofing compound include curry etc, complete as per standard specifications.			1 Sqm	
7	1475.00	Sqm	Painting two coat with approved quality Emulsion Paint over the cement plastered wall surface, ceiling and other new surface over a priming coat including clearing preparing the surface curing in all floors with necessary plaster of paris wherever necessary including brushes etc., complete as per specification. The paint shall be get approved by the Executive Engineer before use on work			1 Sqm	
8			Scaffolding charges for Vimanans and gopurams with casurina posts coconut or plam trees wherever necessary for main, form work and providing with coconut keeth coverings, providing ladder arrangements, country wood plank for working, inspection etc, complete hire charges only for erection, maintainance and removing the same on completion of the work				
a	93	Sqm	Vimanam/Gopuram upto 15'0" height			1 Sqm	
b	281	Sqm	Vimanam/Gopuram upto 25'0" height			1 Sqm	

Signature of Executive Officer

No.of Correction/Overwriting:

Signature of Contractor

Sl. No.	Quantity		Description of item	Rate		Per	Amount
	In Figure	unit		In Figure	In Words		
9	92.00	Sqm	Scraping the decayed lime plaster from the surface of Vimanams and Gopurams, carefully including isolated bricks or brickwork without damaging the vari vargams, racking out the joints, cleaning the surface with water, including the working heights, hire charges for special tools, brushes complete for superficial area including all folds.			1 Sqm	
10	32.00	m2	Painting New wood work with two coats of synthetic enamel paint of approved quality and color over one coat of white primer in all floors The rate shall inclusive cost of all materials, brushes scaffolding charges etc, complete complying with standard specifications. the paint should be by the Executive Engineer before use on work.			1 Sqm	
11			Providing Vargapoochu over the corewalls of Vimanams / Gopurams, with lime Mortar 1:1.5 including shaping the mukhapathram, mahanasi, Koodu all ornamentals works to proper shape by embedding broken bricks of shaped/chiseled bricks, rough-plastering with Combination Mortar 1:1:4 and finishing with final ornamental plastering and nayam theervani including cost and conveyance of all materials, labour therefore, lifting of materials, all working in heights, curing with water etc, complete all extra for folding and clearing from the vimanams/gopurams superficial area.				
a	54.00	Sqm	For kalkaram of vimanam / gopuram shaping in vargams			1 Sqm	

Signature of Executive Officer

No.of Correction/Overwriting:

Signature of Contractor

Sl. No.	Quantity		Description of item	Rate		Per	Amount
	In Figure	unit		In Figure	In Words		
b	11.00	Sqm	Vimanam / gopuram of ht. Up to 15' excluding Kalkaram			1 Sqm	
c	82.00	Sqm	Vimanam / gopuram of ht. Up to 25' excluding Kalkaram			1 Sqm	
12			Providing new sudhai vigrahams in the vimanams and Rajagopurams with galvanised iron rod reinforcement of suitable dia with binding wires wherever necessary, shaping the core with broken bricks set in lime Mortor 1:1.5 finishing the same with lime Mortor 1:1.5 bringing to the correct shape (Lakshana) in conform with silpa sastra inclusive of special ornaments, wiapons, peedam etc., complete and providing C.M. Nayam theervai wherever necessary. inclusive of cost and conveyance of all materials, such as Lime broken bricks, and G.I. rods.binding wire labour for working in any heights, curing lifting of materials etc., complete including cement painting 2 coats over a priming coat (one vigraham is accountable with one head, 4 hands with weapons, ornamental costumes etc., as per prathima lakshans, Vigraham height is measurable from the crown top to the bottom of foot only If peetam is provided the rate with peetam may be adopted as datailed hereunder)				
a	23.00	Nos	Sudhai size above 1' 0" upto 2' 6"			1 Each	

Signature of Executive Officer

No.of Correction/Overwriting:

Signature of Contractor

Sl. No.	Quantity		Description of item	Rate		Per	Amount
	In Figure	unit		In Figure	In Words		
b	7.00	Nos	Sudhai size above 2' 6" upto 3' 6"			1 Each	
13	1180.00	Sqm	Labour charges for Pointing the Cut stone masonry work with lime Mortor 1:1.5 excluding cost and conveyance of cut stone but including all labour charges scaffolding, curing, finishing etc complete with standard specifications. The lime used should be sourced from Pollachi which is highly iron fortified and suitable for structural and masonry works.			1 Sqm	
			Total				

Signature of Executive Officer

No.of Correction/Overwriting:

Signature of Contractor