

MUTHUPET TOWN PANCHAYAT-THIRUVARUR DISTRICT
SOLID WASTE MANAGEMENT 2020-2021 SCHEME - BIO MINING

Estimate Amount : Rs. 52.040 Lakhs

Tender Date :

Issued to Thiru / Thirumathi _____

Challan No. _____ Date : _____

Executive Officer
Muthupet Town Panchayat

Tender Schedule for the Work of Removal of Legacy Garbage Waste Dumped at Prakash Nagar Solid Waste Management Dumbing Yard Site (S.F.No.129)and East Cost Bypass Road by Bio-Mining process in Muthupet Town Panchayat

Sl. No.	Quantity		Description of Works	MDSS/SSRB	Unit in Words	Rate in		Amount
						Figures	Words	
1	6505.00	M3	Revamping of existing dumped garbage in compost yard at Muthupet Town Panchayat, by Bio-mining process a) Excavating the existing mixed compacted garbage which underwent biological degradation in the land portion allocated/earmarked by Town Panchayat authority and spraying with microbial inoculum for sanitizing and stabilizing the excavated mass sieving them using Mechanical Sieving machine or any other equipment at the cost of the Bidder. b) Stabilization of the open land fill site c) Control of mal odour using Deodourising agent and stabilising the waste using Bio Culture for aerobic composting using industrial sprayer d) Eco friendly and nonpolluting process in order to reduce the impact of dumping site in the adjacent areas		One Cubic Metre			+

No. of Corrections: No. of Overwritings:

Signature of Contractor:

Sl. No.	Quantity		Description of Works	MDSS/SSRB	Unit in Words	Rate in		Amount
						Figures	Words	
			e) Excavating the soil which lost its stability due to garbage dumping with necessary dewatering works in the portion of the land earmarked					
			f) Segregate the excavated garbage in the land portion earmarked, into as many kinds and categories as possible at the cost of the Bidder including cost of any power or fuel Consumption.					
			g) Selling, diverting for recycling, marketing and recycling the excavated materials within SEVEN DAYS of segregation, without any accumulation in the storage facility at the project site					
			h) Creation and maintenance of infrastructure, facilities and amenities, for sieving, the excavated garbage, storing the segregated materials before selling/taking out them from the project site					
			i) Deployment of necessary manpower, materials, equipment's, tools and construction of plants and sheds and creation of facilities for handling, separating, segregating, storing and weighing facilities for the operation of the plant and using only covered body vehicles for the transportation of materials					