

## Item Rate BoQ

Tender Inviting Authority: **President Kodungiam Panchayat.**

Extension of Distribution Pipe line and FHTC's 252 Nos at South AD colony Vallakundapuram H/o Kodingiyam panchayat in Udumalpet Block.

Contract no :

<b>Bidder Name :</b>						
<b><u>PRICE SCHEDULE</u></b>						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )						
<b>NUMBER</b>	<b>TEXT #</b>	<b>NUMBER #</b>	<b>TEXT #</b>	<b>NUMBER #</b>	<b>NUMBER #</b>	<b>TEXT #</b>
SI. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	BASIC RATE In <b>Words</b> To be entered by the <b>Bidder</b> Rs. P	<b>TOTAL AMOUNT In Words</b>
1	2	3	4	5	6	7
1.00	Supply and delivery of PVC Saddle Piece 90 x 20 mm	252.00	Each			
2.00	Supply & Delivery of G.M Ferrule as per IS 1239/ Part II					

3.00	15mm (1/2")-(Suitable for 20 mm PVC OD HSC Main)	252.00	Each			
4.00	PVC 90 Degree Compression elbow as per IS 10124/1982 Part II					
5.00	20mm (1/2")-(Suitable for 20 mm PVC OD HSC Main)	504.00	Each			
6.00	PVC Male Threaded Adaptor as per IS 10124/1982 Part II					
7.00	20mm (1/2")-(Suitable for 20 mm PVC OD HSC Main)	504.00	Each			

8.00	PVC PIPE 20mm dia (10 KSC)					
9.00	20mm (1/2")	1512.00	Mts			
10.00	15mm (1/2")-(Brass tap Suitable for 20 mm PVC OD HSC Main)	252.00	Each			
11.00	Brass Flow Control valve 15 mm dia	252.00	Each			
12.00	15mm GI Pipe	504.00	Mts			

13.00	15mm GI Coupling	252.00	Each			
14.00	15mm GI Elbow	504.00	Each			
15.00	Earthwork excavation and depositing on bank for foundation, with an initial lead of 10m and initial lift of 2m including shoring, strutting and bailing water wherever necessary and all other incidental works etc., complete in all classes of Strata (6m*0.6m*1.05m)	952.56	M <sup>3</sup>			
16.00	Labour for drilling, cutting, Threading and Fixing Ferrules in distribution pipes.	252.00	Each			
17.00	supply and delivery of MS Wall Clamp and fixing in walls/floor in open space with required screws and drilling holes etc complete.	252.00	Each			

18.00	Lowering PVC pipes , specials , fittings and all accessories to trench and laying to proper grade and alignment in trench and open space and as directed by the TWAD Officers	1512.00	Mts			
19.00	Labour for refilling excavated earth work in pipe line trenches (6m*0.6m*1.05m)	952.56	M <sup>3</sup>			
20.00	Shellac	252.00	Each			
21.00	Pre cast post with Platform including painting	252.00	Each			
22.00	Provision for Logo Tiles	252.00	Each			

23.00	Earth work excavation in all types of strata for laying of pipes with the standard trench width as per Bd .Circular No. 28/ AE10/ P&D/ 2001/ dt. 01.10.2001 and JCE (P&D)/ Lr.No. LM/ AE10/ P & D/ 2001/ dt.22.11.2001	1.00	Mts			
24.00	Supply of unplasticised PVC rigid pipes as per BIS 4985/2000 with ISI Marking to site of works					
25.00	a. 90 mm OD PVC Pipe 4 KSC	1.00	Mts			
26.00	Lowering and laying the PVC Pipes and specials to trench , laying to proper grade and alignment, Jointing with PVC coupler and specials fixing with Solvent cement paste etc					
27.00	a. 90 mm OD PVC Pipe 4 KSC	1.00	Mts			

28.00	Refilling with excavated soil complying with standard specification in layers of 15 cm thick well rammed and consolidated after pipes and specials are laid and tested.					
29.00	a. 90 mm OD PVC Pipe 4 KSC	1.00	Mts			
30.00	Rate per l m run					
31.00	Supply,delivery, laying and jointing of 90mm OD PVC 4Ksc pipe including earth work excavation in all strata soil, refilling and hydraulic testing, adopting standard specification and as directed by TWAD Board Officer.	0.25	Km			
32.00	Supply of PVC specials as per BIS 10124/1988 Part 1 to 13 & BIS 7834/1975 with ISI Marks to site of works					

33.00	90mm PVC Bend page 12 ,sl.no-3	6.00	Each			
34.00	90mm X 80mm PVC Threaded coupler page 10 SOR		Each			
35.00	90mm PVC Tee IS 7834/1987 page 10	3.00	Each			
36.00	90mm End cap page 12 sl.no 11	1.00	Each			
37.00	Provision for 80 mm Water meter	1.00	Each			

38.00	Water meter Dirt BOX	1.00	Each			
39.00	Water meter erection charges	1.00	Each			
40.00	Provision for pit for Water meter 90X75cm	1.00	Each			