

Name of work : Construction of Compound wall (South Side & West side) in Devaswom High School at Thirparappu in Vilavancode Taluk of Kanyakumari District in Tamil Nadu							
Issued to							
Estimate Amount - Rs.17,70,000/-					E.M.D. - Rs.17,700/-		
Agreement Amount - Rs.16,81,772/-							
Data of Tender : 01.06.2022					Period of Completion : 3 Months		
Sl. No.	Qty		Description	Unit in figures and words	Rate in		Total
					figures	words	
1	155.00	Cum	Earth work excavation for foundation in all classes of soils and sub soils and todepth as may be directed except in hard rock, requiring blasting, including infinal leads and lifts and re-filling the sides of foundation, with excavated earth in 150mm layers well watered rammed and consolidated, including depositing surplus earth within the godown or inside compound in places shown with initial leads and lifts, clearing and levelling the site, shoring shuttering baling out water wherever necessary etc., complete complying with standard specification.	1 Cum (One Cubic Meter only)			

Signature of Contractor

No of Correction:
No of Overwritings:

Joint Commissioner / Executive Officer

Sl. No.	Qty		Description	Unit in figures and words	Rate in		Total
					figures	words	
2	13.00	Cum	Cement concrete 1:5:10 (one cement five sand Ten aggregate) using 40mm gauge hard granite broken stone jelly for foundation including cost and conveyance of all materials labour for mixing,l aying, compacting, curing, dewatering, side shuttering, wherever necessary including curing etc.,complete complying with standard specification and as directed.	1 Cum (One Cubic Meter only)			
3	135.00	Cum	Random Rubble Masonry in CM 1:5 (one of cement and five of sand) using new rough stone and bond stone for foundation and basement including simultaneous flush pointing, curing etc complete.	1 Cum (One Cubic Meter only)			

Signature of Contractor

No of Correction:
No of Overwritings:

Joint Commissioner / Executive Officer

Sl. No.	Qty		Description	Unit in figures and words	Rate in		Total
					figures	words	
4	43.00	Sqm	Providing form work for centering the soffits of all reinforcement cement concrete surfaces including Secondarytying to the required height with M.S.Sheets of 90 x 60cm x 10 gauge stiffened with welded M.S angle of size 25x25x3mm laid over silver oak joints of size 10cm x 6.50cm spaced at about 90cm centre to centre and supported by casurina props of 10cm to 13 cm dia spaced at 75cm centre to centre complying with standard specification and as directed.	1 Sqm (One Square Meter only)			
5	10.00	Cum	R.C.Concrete 1:1 1/2:3 (one cement,One and half course sand and Three broken stone) using 20mm 'size of hard broken granite stone for all RCC works using machine for mixing concrete excluding cost of steel, fabrication of reinforcement, centering, Secondarytying and shuttering and placing the grills in position etc., complete complying with standard specification	1 Cum (One Cubic Meter only)			

Sl. No.	Qty		Description	Unit in figures and words	Rate in		Total
					figures	words	
6	1002.00	Kg	Supplying and fabricating and placing in position M.S.grills for reinforcement for all RCC works, including cost of rods, straightening, bending, cracking tying grills,with 18 gauge galvanized binding wire and placing the grills in position etc., complete and as directed.	1 Kg (One Kilo gram only)			
7	57.50	Cum	Brick work in cement mortar 1:5 using country bricks of size 8 3/4" x 4 1/4" x 2 3/4",including cost and conveyance of all materials into the site and all labour charges etc complete with standard specification as directed by the department officer	1 Cum (One Cubic Meter only)			
8	781.00	Sqm	Plastering with CM 1:5 (one cement and five sand) 12 mm thick including scaffolding finishing curing etc., including cost and conveyance of all materials into the site and all labour charges etc complete complying with standard specification and as directed.	1 Sqm (One Square Meter only)			

Sl. No.	Qty		Description	Unit in figures and words	Rate in		Total
					figures	words	
9	896.00	Sqm	Cement painting two coat to the walls after cleaning and preparing the surface ,including cost and conveyance of all materials into the site and all labour charges etc complete with standard specification as directed by the department officers etc,.	1 Sqm (One Square Meter only)			
			Total				
Total Value of work as per basic rate Rs. _____ ()							
Add GST @ 12% (CGST @ 6% + SGST @ 6%) Rs. _____ ()							
Total Value of Tender Rs. _____ ()							

Signature of Contractor

No of Correction:
No of Overwritings:

Joint Commissioner / Executive Officer