

Item Rate BoQ

Tender Inviting Authority: Commissioner, Thoothukudi City Municipal Corporation

Name of Work :Construction of SWD at P&T Colony 11th East in West Zone (Ward-16)

Contract No:14/22-23/AEE(W)

Name of the Bidder/ Bidding Firm / Company :							
<u>PRICE SCHEDULE</u>							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBE	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Earth work excavation for foundation in Hard stiff clay, stiff black cotton, hard red earth, shales murram, gravel,stone earth and earth mixed with small size boulders SS.20B and Sand, silt or other loose soil, wet sand,or silt not under water, light black cotton soil, sandy loam ordinary soil and to full depth as may be directed except in hardrock requiring blasting inclusive of shoring shuttering and baling out water and cleaning and levelling the site etc.,	85.00	1M3 (One cubic metre)			0.00	INR Zero Only

2	Plain Cement Concrete 1:4:8 (one cement four fine aggregates and eight coarse aggregates) using 40mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges and all incidental charges such as water providing etc., complete as per standard specification	15.00	1M3 (One cubic metre)			0.00	INR Zero Only
3	Centering for soffits of RCC slabs of plane surface like lintels, beams ,etc.,including strutting 3m high using mild steel sheets of size 90cm X 60cm X and B.G 10 stiffened with M.S angles of size 25mm X 25mm X 3mm laid over silver Oak (C.W) joists of size 10cm X 6.5cm (spaced at about 90cm c/c)and supported dy casurina props of 10cm to 13cm dia (spaced of 75cm C/C) complying with standard specification and directed	250.00	1M2 (One square metre)			0.00	INR Zero Only
4	Plain Cement Concrete 1:2:4 (one cement, two fine aggregates and four coarse aggregates) using 20mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges etc., complete as per standard specification	32.00	1M3 (One cubic metre)			0.00	INR Zero Only
5	Plastering with cement mortar (1:4) 20mm thick in all floors including cost and conveyance of all materials to site and labour charges etc, complete complying with standard specifications	82.00	1M2 (One square metre)			0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					