

EDAIKAZHINADU TOWN PANCHAYAT

Date of Tender :
 Schedule Amount :
 Chellan No. :
 & Date
 Issued to Thiru/Tmt .

TENDER SCHEDULE – TYPE "A"**SCHEDULE OF RATES APPROXIMATE QUANTITIES**

- a) The quantities here given those the lump sum tender cost of work is based but they are subject to alterations omissions deductions as provided for in the conditions of this contract and do shown actual quantities of work top done to unit rates noted below are those covering payment extras of reductions omissions for according to the conditions of contract as set for in the preliminary specifications of the TNBPR and other conditions of contract specification of this contract.
- b) It is to be expressed immder stood that rent works is to be taken net (not withstanding any or practice to the contrary) according to the actual quantities in Balance finished according to the drawings or as may be provided from time by the Town Panchayat Engineer and the cost calculated by measurement or weight of the respective any additional charges for any necessary connected to the work. The rates quoted in site and complete in every respect.

Name of the Scheme : **O&M -(2021-2022)**

Estimate Amount Rs,15.00Lakhs

Name Of Work :Repair and Maintanance for OHT tank (1) Ward No. 3 Muthaliyarkuppam Primary school, (2) Ward No.7, Vilambur Karumariyamman Kovil near (3) Ward No.8 Kadapakkam OHT (4) Ward No.10 Alambaraikuppam Uthukattamman Tank (5) Ward No.17 Kappivakkam Primary School, (6) Ward No.18 Sembulipuram Primary School (7) Kottaikkadu Kasipattai Salai PDS Shop (8)Ward No.15 Karumbakkam Merku OHT (9) Ward No. 6 Vilambur Vinayagar Koil near OHT in Edaikalinadu Town Panchayat.

Sl.	Quantity	Description of Works	MDSS/	Unit in	Rate in		Remarks
No.			SSRB	Words	Figures	Words	

No. of Corrections:No. of Overwritings:

Signature of Contractor:

Name of the Scheme : **O&M -(2021-2022)**

Estimate Amount Rs,15.00Lakhs

Name Of Work :Repair and Maintanance for OHT tank (1) Ward No. 3 Muthaliyarkuppam Primary school, (2) Ward No.7, Vilambur Karumariyamman Kovil near (3) Ward No.8 Kadapakkam OHT (4) Ward No.10 Alambaraikuppam Uthukattamman Tank (5) Ward No.17 Kappivakkam Primary School, (6) Ward No.18 Sembulipuram Primary School (7) Kottaikkadu Kasipattai Salai PDS Shop (8)Ward No.15 Karumbakkam Merku OHT (9) Ward No. 6 Vilambur Vinayagar Koil near OHT in Edaikalinadu Town Panchayat.

Sl.	Quantity		Description of Works	MDSS/	Unit in	Rate in		Remarks
No.				SSRB	Words	Figures	Words	
1			Providing two legged scaffolding using 15cm dia blue-gum posts of 4.0m overall length (3M HT + 0.5M projection + 0.5m into ground) the distance between two rows being 1.25m and the spacing of postsbeling 2.0m and the spacing of postsbeling 2.0m in both the rows with two horizontal posts with 0.5m overlap on either sideand braces at 2m c/cincludng longitudinal and transverse middle braces to step up and providing aplatform with					
a	76.00	M ²	First level @ 0.00 to 3.00 m above G.L		1M2 (one square metre)			
b	76.00	M ²	Second level @ 3.00 to 5.50 m above G.L		1M2 (one square metre)			
c	76.00	M ²	Third level @ 5.50 to 8.00 m above G.L		1M2 (one square metre)			
d	76.00	M ²	Fourth level @ 8.00 to 10.50 m above G.L		1M2 (one square metre)			
			For 0.30 L Ltr - 5 Nos					
a	74.00	M ²	First level @ 0.00 to 3.00 m above G.L		1M2 (one square metre)			

No. of Corrections:No. of Overwritings:

Signature of Contractor:

Name of the Scheme : **O&M -(2021-2022)**

Estimate Amount Rs,15.00Lakhs

Name Of Work :Repair and Maintanance for OHT tank (1) Ward No. 3 Muthaliyarkuppam Primary school, (2) Ward No.7, Vilambur Karumariyamman Kovil near (3) Ward No.8 Kadapakkam OHT (4) Ward No.10 Alambaraikuppam Uthukattamman Tank (5) Ward No.17 Kappivakkam Primary School, (6) Ward No.18 Sembulipuram Primary School (7) Kottaikkadu Kasipattai Salai PDS Shop (8)Ward No.15 Karumbakkam Merku OHT (9) Ward No. 6 Vilambur Vinayagar Koil near OHT in Edaikalinadu Town Panchayat.

Sl.	Quantity		Description of Works	MDSS/	Unit in	Rate in		Remarks
No.				SSRB	Words	Figures	Words	
b	74.00	M ²	Second level @ 3.00 to 5.50 m above G.L		1M2 (one square metre)			
c	74.00	M ²	Third level @ 5.50 to 8.00 m above G.L		1M2 (one square metre)			
d	74.00	M ²	Fourth level @ 8.00 to 10.50 m above G.L		1M2 (one square metre)			
2	26.98	M ³	Earth work excavation for foundation in Hard stiff clay, stiff black cotton, hard red earth, shales murram, gravel, stoney earth and earth mixed with small size boulders SS.20B and completed depositing the surplus excavated soil with in the compound in places shown by the departmental officers with intial lead etc.,complete width upto 2.00m		1 m3 (One Cubic Metre)			
3	4.46	M ³	Cement Concrete 1:4:8 (One cement, four fine aggregate and eight course aggregate) mix using 40mm HBG ISS metal from approved quarry including cost and conveyance of all materials to site and labour charges, including dewatering if found necessary and lai		1 m3 (One Cubic Metre)			

No. of Corrections:No. of Overwritings:

Signature of Contractor:

Name of the Scheme : **O&M -(2021-2022)**

Estimate Amount Rs,15.00Lakhs

Name Of Work :Repair and Maintanance for OHT tank (1) Ward No. 3 Muthaliyarkuppam Primary school, (2) Ward No.7, Vilambur Karumariyamman Kovil near (3) Ward No.8 Kadapakkam OHT (4) Ward No.10 Alambaraikuppam Uthukattamman Tank (5) Ward No.17 Kappivakkam Primary School, (6) Ward No.18 Sembulipuram Primary School (7) Kottaikkadu Kasipattai Salai PDS Shop (8)Ward No.15 Karumbakkam Merku OHT (9) Ward No. 6 Vilambur Vinayagar Koil near OHT in Edaikalinadu Town Panchayat.

Sl.	Quantity		Description of Works	MDSS/	Unit in	Rate in		Remarks
No.				SSRB	Words	Figures	Words	
4	110.40	M ²	Supplying and erecting centering to sides and soffits including supports and strutting with necessary cross bracing for plain surface such as CC slabs rectangular beams all beams lintels etc., centering for soffits upto 3 meter height using mild steel sheet of size 90 cm x 60 cm x 10 mm gauge with MS angles of size 25mm x 25mm x 3mm laid		1M2 (one square metre)			
5	6.66	M ³	Brick work CM 1:5 mix using good quality ground molded champer bricks including including cost and conveyance of material and all other labour charges etc completed		1 m3 (One Cubic Metre)			
6	21.70	M ³	Plain Cement Concrete 1:2:4 (One cement,two fine aggregate and four course aggregate) mix using 20mm HBG ISS metal from approved quarry including cost and conveyance of all materials to site and labour charges, including dewatering if found necessary and		1 m3 (One Cubic Metre)			
7	47.80	M ²	Plastering with C.M.1:5 (One cement and five sand) mix using 12 mm thick including cost and conveyance of all materials and labour charges etc., complete complying with standard specifications as directed by the departmental		1M2 (one square metre)			

No. of Corrections:No. of Overwritings:

Signature of Contractor:

Name of the Scheme : **O&M -(2021-2022)**

Estimate Amount Rs,15.00Lakhs

Name Of Work :Repair and Maintanance for OHT tank (1) Ward No. 3 Muthaliyarkuppam Primary school, (2) Ward No.7, Vilambur Karumariyamman Kovil near (3) Ward No.8 Kadapakkam OHT (4) Ward No.10 Alambaraikuppam Uthukattamman Tank (5) Ward No.17 Kappivakkam Primary School, (6) Ward No.18 Sembulipuram Primary School (7) Kottaikkadu Kasipattai Salai PDS Shop (8)Ward No.15 Karumbakkam Merku OHT (9) Ward No. 6 Vilambur Vinayagar Koil near OHT in Edaikalinadu Town Panchayat.

Sl.	Quantity		Description of Works	MDSS/	Unit in	Rate in		Remarks
No.				SSRB	Words	Figures	Words	
8	50.00	No	Supplying and Fabrication of approved filterbed inside of the bed including cost of materials and all other labor charges Etc. Complete.		1No. (one number)			
9	312.00	M ²	Plastering with C.M.1:3 (One cement and five sand) mix using 20 mm thick including cost and conveyance of all materials and labour charges etc., complete complying with standard specifications as directed by the departmental		1M2 (one square metre)			
10	75.00	M	Supply and delivery of 65mm dia B Class GI Pipe including cost and conveyance of all materials and all other labour charges etc. complete (TWAD SoR 2021-22, P.No.30)		1M (one metre)			
11	6.00	No	Supply and delivery of 65mm dia Gate Valve including cost and conveyance of all materials and all other labour charges etc. complete (TWAD SoR 2021-22, P.No.30)		1No. (one number)			
12	6.00	No	65 mm dia G.M Non return Vale Supply and delivery of 50mm dia Non Return Valve including cost and conveyance of all materials and all other labour charges etc. complete (TWAD SoR 2021-22, P.No.30)		1No. (one number)			

No. of Corrections:No. of Overwritings:

Signature of Contractor:

Name of the Scheme : **O&M -(2021-2022)**

Estimate Amount Rs,15.00Lakhs

Name Of Work :Repair and Maintanance for OHT tank (1) Ward No. 3 Muthaliyarkuppam Primary school, (2) Ward No.7, Vilambur Karumariyamman Kovil near (3) Ward No.8 Kadapakkam OHT (4) Ward No.10 Alambaraikuppam Uthukattamman Tank (5) Ward No.17 Kappivakkam Primary School, (6) Ward No.18 Sembulipuram Primary School (7) Kottaikkadu Kasipattai Salai PDS Shop (8)Ward No.15 Karumbakkam Merku OHT (9) Ward No. 6 Vilambur Vinayagar Koil near OHT in Edaikalinadu Town Panchayat.

Sl.	Quantity		Description of Works	MDSS/	Unit in	Rate in		Remarks
No.				SSRB	Words	Figures	Words	
13	5.00	No	50 mm dia G.M Gate Vale Supply and delivery of 50mm dia Non Return Valve including cost and conveyance of all materials and all other labour charges etc. complete (TWAD SoR 2021-22, P.No.30)		1No. (one number)			
14	1930.00	M ²	Painting two coats with ready mixed Plastic Emulsion Paint S.I.358 Plastic emulison paint of approved quality and colour over a priming coat, including thorough scraping, clean removal of dirt, etc complete and including necessary plaster of		1M2 (one square metre)			
15	332.00	M ²	Painting two coats with ready mixed enamel paint of approved quality and colour over a Existing priming coat For New Iron Grill works, including cost and conveyance of all materials etc.and all lobour charges etc.complete as per Standard		1M2 (one square metre)			

No. of Corrections:No. of Overwritings:

Signature of Contractor: