

Item Rate BoQ

Tender Inviting Authority: Commissioner, Thoothukudi City Municipal Corporation

Name of Work : Replacement of Existing PVC into HDPE pipe Krishnarajapuram to S.S Manikapuram .

File No: 26/22-23/AEE(N)

Name of the Bidder/ Bidding Firm /	
---	--

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Supply and Delivery of 250mm HDPE Pipe (PN8) the rate includes all cost and conveyence of materials and labour charges etc., complete	300.00	1 Mtr (One Metre)			0.00	INR Zero Only
2	Supplying and fixing of 250mm CI sluice valve set the rate includes all cost and conveyence of materials and labour charges etc., complete	1.00	1 Nos (One Number)			0.00	INR Zero Only
3	Supply and Delivery of Ductile Iron Class PN10 1 m length of Flanged Pipes AS PER IS 8329/2000 the rate includes all cost and conveyence of materials and labour charges etc., complete (1.5m Length pipe)						
3.01	250mm Pipe	2.00	1 Nos (One Number)			0.00	INR Zero Only
4	Supply and Delivery of CI all Flange Specials the rate includes all cost and conveyence of materials and labour charges etc., complete	361.00	1kg(One kilo Gram)			0.00	INR Zero Only

5	Jointing HDPE Pipes and Specials by butt fusion welding / electro fusion welding joints using fusion equipment as per ISO 21307-2011 and as per IS 7634 (part-2) : 2012 including cost of hire charges for butt fusion equipment power supply arrangements etc., complete as per directed by TWAD Board Officers.						
5.01	250 mm HDPE Pipes	50.00	1 Nos (One Number)			0.00	INR Zero Only
6	Earth work excavation and depositing on bank with an initial lead of 10mtr and lift of 2mtr in narrow trench have a bed width 1.25m and below for laying pipes for water supply in sand silt or other loose soil sandy loam and ordinary soil SS 20B	265.00	1M3 (One Cubic metre)			0.00	INR Zero Only
7	Lowering HDPE pipes and specials to trench and laying to proper grade and alignment and as directed by the Corporation Officers						
7.01	250 mm HDPE Pipes	300.00	1 Mtr (One Metre)			0.00	INR Zero Only
8	Jointing the C.I/ D.I Double flanged pipes and specials with rubber insertion to with IS-638(1979) and M.S. bolts and nuts of IS 1364-1 (2002), including cost of jointing materials suchas bolt and nuts Rubber insertion and labour charges etc., complete						
8.01	300mm Pipe	2.00	1 Nos (One Number)			0.00	INR Zero Only
8.02	250mm Pipe	4.00	1 Nos (One Number)			0.00	INR Zero Only

9	Jointing the C.I/ D.I-S/S pipes and specials with neat cement or cement mortar and spun yarn including caulking the joints, curing. (including cost of jointing materials), including cost of jointing materials suchas bolt and nuts Rubber insertion and labour charges etc., complete						
9.01	300mm Pipe	4.00	1 Nos (One Number)			0.00	INR Zero Only
10	Refilling with excavated earth from pipe line work,excavation filling in layers of not exceeding 15 cm thick well rammed watered and consolidation etc., complete as per specification	250.00	1M3 (One Cubic metre)			0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					