

SALEM CITY MUNICIPAL CORPORATION

TENDER SCHEDULE

Name of Contractor :

EMD Details **Rs.8,300/-**

Tender Date **15.06.2022**

Name of Work **Construction of Storm Water Drain and Cuvert at Mullai Nagar Main Road and Paver Block Flooring at Mullai Nagar Sai Baba Kovil Near in Division No: 23 of Suramangalam Ward Office. 3**

Est. No. **E3/NNT / Est No:498/ D /2021-2022**

Estimate Cost **Rs. 8,30,000/-**

1. The Quantities here given are those upon the lump sum tender cost of work is based, but they are subject to alterations, omissions, deductions or additions as provided for the conditions of the contract and do not necessarily show the actual quantities of work to be done. The unit rates are those governing payment for extracts or deductions for omissions according to the contract, as set forth in the preliminary specifications of the (Madras Detailed Standard Specifications) Tamil Nadu building practice and other conditions or specifications of the contract.

2. It is to be expressly understood that the measured work is to be taken nett (not with standing any custom or practice to the contrary) according to the actual quantities when in place and finished according to the drawing or as may be ordered from time to time by the Corporation Engineer and the cost calculated by measurement of weight, of the respective prices, with out additional charge for any necessary contingent works connected herewith. The Rates quoted are for works in 'situ' and complete in every respect.

3. The work must be completed with in Days/Month from the date of receipt of acceptance of this tender.

Item	Probable Quantity		Description of Work	Rate		Unit in	Amount in
	No	Figures	Units	Words	Figures	Words	Figure
1	45.00	m3	Earth work excavation for foundation in ordinary soil, light black cotton sandy loam and dry silt including shoring, strutting, baling or pumping out water wherever necessary and refilling the sides of foundation with excavated earth in layers of 15cm thick and depositing the surplus earth at places as directed by the departmental officers with initial lead and lift			m3	
2	4.00	m3	Plain cement concrete 1:4:8 mix (One cement four sand and eight aggregate) using 40mm size ISS gauge HBBG metal including mixing, laying, consolidating, curing, cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification			m3	
3			Supplying and erecting centering to sides and soffits including supports and strutting for drainage sides and culvert body wall sides using M.S Sheets of size 90cm x 60cm and B.G 10stifened with welded mild steel angles of size 25mm x 25mm x 3mm for boarding laid over(silver oak joists) of size 10cm x 6.50cm spread at about 90cm including all labour charges and cost and conveyance of all materials to site etc. complete Complying with Standard Specification				

	8.00	m2	a). Drain works Below 1m Height			m2	
	63.00	m2	a). Drain works Above 1m Height			m2	
	20.50	m2	b). Slab & Beam			m2	
4	18.00	m3	Plain cement concrete 1:2:4 mix (One cement two sand and four aggregate) using 20mm size ISS gauge HBBG metal including mixing, laying, consolidating, curing, cost and conveyance of all materials to site and all labour charges etc., complete as per standard specification			m3	

5	5.50	m3	<p>Providing and laying in position, Standardised Concrete Mix M-20 Grade in accordance with IS:456-2000, using 20mm and down graded hard broken granite stone jelly for all RCC items of works with minimum cement content of 325 kg/m³ and maximum water cement ratio of 0.55, including admixture (plasticiser / super plasticiser) in recommended proportions as per IS:9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability with about (5 cu.m.) 7730 kg. of 20mm machine crushed stone jelly and with about (3.3 cu.m.) 5156 kg. of 10-12mm machine crushed stone jelly and with about (4.79 cu.m.) 7670 kg. of sand, but excluding cost of reinforcement grill and fabricating charges, centering and shuttering and also including laying, vibrating with mechanical vibrators, finishing, curing, etc. and providing fixtures like fan clamps in the RCC floor/ roof slabs wherever necessary without claiming extra, etc., complete complying with standard specification and as directed by the departmental officers. The coarse and fine aggregates to be used should comply with the requirements of IS Standards. (No separate payment will be made by the Department for the excess usage of materials).</p>			m3	
---	------	----	--	--	--	----	--

6	550.00	Kg	Supply and fabrication and placing in position of TMT steel rods to required size and length as directed by the departmental officers including cost of binding wire, cutting, bending and tying with proper position etc., including cost and conveyance of all materials to site and all labour charges etc., complete Complying with Standard Specification			Kg	
7	14.50	m2	Plastering with cement mortar 1:3 mix, 20mm thick including cost and conveyance of all materials to site, loading and unloading charges and labour charges for mixing, laying and curing etc. complete . complying with std. specifications			m2	
8	30.00	m3	Conveyance of Excavated Excess Earth away from the site to 2km including loading and transportation charges etc., complete as per standard Specification.			m3	
9	89.00	m3	Supplying and filling the basement with Good Earth filling in layers of not more than 15cm thick well rammed watered and compacted - etc., complete complying with standard specification.			m3	

10	442.00	m3	Supplying and laying Rubberised interlocking Paver block M40 grade Providing and laying of 83mm thick high strength type conforming IS 15658-2006 of rubberized interlocking paver lock in size of minimum compressive strength of 40N/mm2 in uniform shape of approved make to be laid in flurring bone pattern with stone dust cushion below the uniform shap of approved non skitting surface in the top and the rate including levelling the base preparation of pavers as sub base, stone dust cushion 150mm thick laying out of pavement cut the pieces to fix the edge vibring the pavers,sweeping tranporting loading unloading of laying paver block as per standard specification,.			m3	
----	--------	----	---	--	--	----	--