

## Item Rate BoQ

Tender Inviting Authority: **Block Development Officer, Udumalpet Block.**

Drilling of new Borewell supply and erection of pumpset and Pumping Main Pipe Line at Thippiparai in Amaravathinagar H/o. Andiyagoundanur Panchayat.

Contract no :

Bidder Name :						
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )</div>						
NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs.    P	BASIC RATE In Words To be entered by the Bidder Rs.    P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1.00	Towards Geo physical survey charges	1.00	Job			
2.00	Drilling of 180 mm dia bore well in overburden soil including labour charges for insertation of casing pipes.	12.00	Running Meter			

3.00	Supply of 180 mm $\Phi$ PVC casing pipe including all.	12.00	Running Meter			
4.00	Drilling of 150 mm dia bore well in hard rock area by using drilling rig including transportation of rig and support vehicle etc., Completed.	325.00	Running Meter			
5.00	Supply of 10 HP Submersible pumpset 50 LPM X 275 mtr / head including vat.	1.00	Each			
6.00	Supply of 10 HP star / Delta - Automatic Panel Board, ISI make including vat.	1.00	Each			
7.00	Supply of 4 Sq.mm 3 core flat cable	520.00	Running Meter			

8.00	Supply of 50 mm dia UPVC column pipe	249.00	Running Meter			
9.00	Supply of 75 mm dia 6 Ksc PVc pipe	1782.00	Running Meter			
10.00	Supply of 1000lit capacity HDPE tank	5.00	Each			
11.00	Fabrication and supply of M.S.KIOSK of size 0.75 m x 0.45 x 0.75 made up of M.S. angle of size 50 mm x 50 mm x 4 mm alround coverd with 16 gange of size 25 mm x 3 mm including cutting, welding, Grinding, loading to front page arrangements.	1.00	Each			
12.00	supply of 100 Amps fuse units	3.00	Each			

13.00	supply of 100 Amps main switch	1.00	Each			
14.00	Earth work excavation and depositing on bank within an initial lead of 10 mtr and lift of 2 mts in all soils	1782.00	Running Meter			
15.00	Laying and jointing of 75 mm 6 ksc PVC pipes and specials.	1782.00	Running Meter			
16.00	Refilling the excavated earth work for pipe line trench	1782.00	Running Meter			
17.00	Labour charges for erection of 10 HP submersible Pumpset	1.00	Job			

18.00	Construction of bed for HDPE Tank with all civil materials and labour charges etc. completed.	5.00	Each			
19.00	Construction of bed for Restraining the M.S. Kiosk with all civil materials and labour charges etc. completed.	1.00	Each			