

AMMAPETTAI TOWN PANCHAYAT
TENDER SCHEDULE

Name of the work : Renovation of community Toilet at Thanjai Nagai salai

EST.AMOUNT Rs 5,50,000/-

TENDER DATE:

TENDER DEPOSIT:

Sl. No	Quantity		Description of Work	TNDSS or TNBP No	Rate in Rupees		Units in Figures & Words	Amount in Rupees
					FIGURES	WORDS		
1	18.00	M ³	Earth work open excavation and depositing on bank with in the initial lead of 10m and a lift of 2m in hard stiff clay, stiff block cotton, hard red earth, shales, murram, gravel, stoney earth and earth mixed with small size boulders etc., as per SS 20 A. TNDSS NO: 23 & 24 VI (S2) VI,VII 9,10 with standard specifications.				1M ³ (One Cubic Metre)	
2	3.00	M ³	Supply delivery and filling of River Sand in layer of not more than 15 cm thick including watering with all layers and consolidation complying with standard specification including cost and conveyence of sand to Site and all labour charges and all other incidental charges etc,. complete as per Standard Specification				1M ³ (One Cubic Metre)	

Sl. No	Quantity		Description of Work	TNDSS or TNBP No	Rate in Rupees		Units in Figures & Words	Amount in Rupees
					FIGURES	WORDS		
3	3.00	M ³	Plain Cement concrete of mix 1:4:8 (One cement four sand eight aggregates) using 40mm gauge hard broken including cost conveyance of all materials to site including labour charges, transporting and placing in position including shoring, strutting forming protective bunds, cofferdams bailing out of water labour for mixing compacting, finishing and curing, working at depths, tools and plants and incidental charges such as sheeting, shoring and bracing and their subsequent removal etc., complete as per standard specification.				1M ³ (One Cubic Metre)	
4	2.00	M ³	VRCC 1:1½:3 (One cement one point five sand and three aggregates) mix using 20mm gauge hard granite broken stone jelly in all RCC works connected to the work excluding shuttering , Centering and cost of Reinforcement grills but including curing ,fini				1M ² (One Square Metre)	

Sl. No	Quantity		Description of Work	TNDSS or TNBP No	Rate in Rupees		Units in Figures & Words	Amount in Rupees
					FIGURES	WORDS		
5	8.00	M ²	Supplying & Erecting of steel centering for sides & soffits including necessary supports & strutting upto 3.29m height for plane surfaces in all floors with all cross bracings using mild steel sheets of size 90 x 60cm & 10 gauge stiffened, welded w				1M ² (One Square Metre)	
6	150.00	kg	Supplying and Fabrication of Steel and placing in position MS / Ribbed tor steel Grills for RCC works as per design given including cost of steel and GI binding wire in Floors etc.,. Complete complying with standard specification in force and as directed				1Kg (One Kilo Grame)	
7	6.00	M ³	Brick work in Cement Mortar in 1:5 (One cement and Five Sand) using best quality of Country bricks of size 8 ³ / ₄ x 4 ¹ / ₄ x 2 ³ / ₄ including all cost of materials and labour charges including Curing charges etc., complete as per Standard Specificationand as dire				1M ³ (One Cubic Metre)	

Sl. No	Quantity		Description of Work	TNDSS or TNBP No	Rate in Rupees		Units in Figures & Words	Amount in Rupees
					FIGURES	WORDS		
8	30.00	M ²	Special Ceiling plastering with cement mortar 1:3(one cement and three sand) mix 10mm thick including cost of all materials and all labour charges etc., complete complying with standard specifications.				1M ² (One Square Metre)	
9	20.00	M ²	Plastering the surface of walls with cement mortar 1:5(One cement and five sand) 12 mm thick in all floors including cost of all materials and all labour charges etc etc., complete complying with standard specifications.				1M ² (One Square Metre)	
10	36.00	M ²	Paving the flooring with ceramic tiles of following types of approved colour and quality laid in cement mortar 1:3 (one cement and three sand) 20mm thick in all floors and the top pointed with the same coloured cement etc., complete in all floors.				1M ² (One Square Metre)	
11	26.00	M ²	Dadoing walls with the following types tiles of suitable size of approved quality and colour set in cement mortar 1:2 (one cement ,two sand); 10mm and pointing with colour cement neatly etc., complete in all floors.				1M ² (One Square Metre)	

Sl. No	Quantity		Description of Work	TNDSS or TNBP No	Rate in Rupees		Units in Figures & Words	Amount in Rupees
					FIGURES	WORDS		
12	19.00	M ²	Supplying and fabrication and fixing in position of anodised natural colour matt finish sliding Door in all floors with following sizes. All the two shutters with slinging entering and made with UPVC (ultra Polyvinyl Chloride) section for outer frame				1M ² (One Square Metre)	
13	335.00	M ²	Painting two coats of newly plastered wall surface with ready mixed plastic emulsion paint of first class quality and of approved colour over a priming coat including thorough scrapping, clean removal of dirt, and including necessary plaster of paris, put				1M ² (One Square Metre)	
14	30.00	RM	Supply and run of 2 of 1.5 sqmm (22/0.3) PVC insulated SC unsheathed Cu.Conductor of 1100V Grade in rigid pipe concealed in wall and ceiling with continuous earth wire connection of 14SWG TC wire and making good of the concealed portion with suitable color				1RM(One Running Metre)	
15	10.00	Nos	Wiring with 2x1.5 sqmm (22/0.3) PVC insulated SC.unsheathed Cu. Conductor of 1100 V grade in suitable PVC rigid pipe on wall and ceiling with PVC accessories and with TW switch box and 5A F.T. switch with painting of suitable Colourfor open PVC light poi				1No(Each)	

Sl. No	Quantity		Description of Work	TNDSS or TNBP No	Rate in Rupees		Units in Figures & Words	Amount in Rupees
					FIGURES	WORDS		
16	6.00	Nos	Supply and fixing of single box type 4'40 W flu fitting complete with copper choke and condensor with TW round blocks on wall or ceiling with flu tube with PVC unsheathed Copper leads from terminals to the fitting. SD 89				1No(Each)	
17	4.00	Nos	Supply and fixing of WT bulk head fitting with guard (Philips / Bajaj / Crompton / K. Lite) suitable for incandescent lamp with 60 W bulb. SD 84				1No(Each)	
18	1.00	No	Supply and fixing of 32 Amps DPIC Switch of 500 V with metal clad with fuse and neutral (Side Handle) on suitable TW Board , with earth connection only SD 142				1No(Each)	
19	1.00	No	Supply and fixing of TNEB meter Board suitable for 32A Single Phase service connection with 32A Fuse unit (500V) 32A neutral link and earth link (1" x 1/8" Copper flat) on TW plank of size 375mm x 300mm x 19mm with supporting TW reepers of 1" thick an eit				1No(Each)	

Sl. No	Quantity		Description of Work	TNDSS or TNBP No	Rate in Rupees		Units in Figures & Words	Amount in Rupees
					FIGURES	WORDS		
20	7.00	RM	Supplying and fixing PVC rain water down fall pipes of 4kgf/cm ² variety of the following sizes excluding cost of PVC specials but including charges for fixing them in position with nessary shoes, bends, clamps, TW plugs, screws, nails etc., complete.				1RM(One Running Metre)	
21	6.00	Nos	Supplying and fixing in position white glazed Indian water closet of size 580 X 440mm of Orissa type of approved quality with 'P' or 'S' trap with sand cushion and forming flooring alround the closet using 40mm broken brick jelly lime concrete 1:2:5 ; 10				1No(Each)	
22	2.00	NOs	Supplying and fixing in position best quality approved make white glazed earthenware wash hand basin of size 550 X 400 mm with a pair of cast iron brackets, including cost of 15mm dia brass chromium plated piller tap, 32 mm dia C.P. waste coupling, 32 mm				1No(Each)	
23			Supply and delivery of Water Supply Pipes and Specials including cost and conveyance of all materials and labour charges etc.,					
a	30.00	RM	20 mm Pvc pipe				1RM(One Running Metre)	

Sl. No	Quantity		Description of Work	TNDSS or TNBP No	Rate in Rupees		Units in Figures & Words	Amount in Rupees
					FIGURES	WORDS		
b	24.00	RM	25 mm Pvc pipe				1RM(One Running Metre)	
c	10.00	RM	110 MM Pvc Pipe				1RM(One Running Metre)	
d	12.00	RM	20 mm GI Pipe				1RM(One Running Metre)	
e	10.00	Nos	Tap				1No(Each)	
f	2.00	Nos	Floor Trap with stainless Steel Grating 100mm x 75mm				1No(Each)	
24	1.00	No	Supply and fixing of 1000 litre capacity HDPE Tank of approved quality including cost and conveyance of all materials and all labour charges and other incidental charges to site etc., complete as per standard specification.				1No(Each)	
25	2.00	Nos	Supplying and fixing in position Indian make bewelled edge mirror of approved quality and colour of size 600 X 450mm with necessary plastic back, PVC frame with bottom stand with brass screws,rawal plugs etc., complete complying with standard specificat				1No(Each)	

Sl. No	Quantity		Description of Work	TNDSS or TNBP No	Rate in Rupees		Units in Figures & Words	Amount in Rupees
					FIGURES	WORDS		
26	4.00	Nos	Supplying and fixing best approved quality C.P / Al anodised Towel rail 600mm. long and 20mm dia with brackets of same material including cost of teakwood plugs and C.P.Screws etc., complete complying with standard specifications				1No(Each)	
27	4.00	Nos	Supplying and fixing best approved quality C.P. soap tray of size 150mm X 100mm including cost of teakwood plugs, brass screws etc., complete complying with standard specifications.				1No(Each)	

(Approved Items 1 to 27 only)

Note:

(1) Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the Other rates and prices in the Bill of /Quantity (refer: ITB clause 13.2 and GCC Clause 43.3)

(2) Unit rates and prices shall be quoted by the bidder in Indian Rupee (ITB Clause 14.1)

(3) Where there is a discrepancy between the rate in figures and words, the rates in words will govern (ITB Clause 27s.1(a))

(4) Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity, the unit rate quoted shall govern (ITB Clause 27.1(b)).