

## TENDER SCHEDULE - B.

Tender Date : 09 - 06 - 2022

Koliyanur Block

Name of Scheme : 15th CFC (DPt , Tied ) 2021-22

Estimate Amount RS: 16 ,00,000 /-

Name of Work: Construction of Cement Concrete Drainage with 2 nos Culvert at Poothamedu Mariyamman Koil street, School street in Thennamadevi Panchayat.

Name of Contractor :

Name of Contractor :					
S.No	Quantity	Description of works	Unit	Rate in	
				in Figures	in words
Drainage					
1	151.80	Earth work excavation and depositing on bank with in initial lead of 10 mand initial lift of 2m in hard stiff clay, stiff black cotton soil, hard red earth,earth mixed with small sized boulders and hard gravelly soil as per SS 20B	M3		
2	30.36	CC 1:4:8 mix using 40mm ISS HBG metal including all other labour charges etc	M3		
3	528.75	Supplaying and erection centering for sides and sofficts inculding cost and conveyance cost of all labour charges etc complete BGL	M2		
4	66.00	Cement concrete 1:2:4 mix using 20mm ISS metal including cost and conveyance of all materials to site and all labour charges for mixing, laying and curing etc complete for 10 cum.	M3		
5	79.20	Plastering in Cement Mortor 1 : 3 mix to 20 mm thick including cost and conveyance of all materials to site and all labour charges for mixing, laying and curing etc complete	M2		
6	6.88	Supplaying and erection centering for sides and sofficts inculding cost and conveyance cost of all labour charges etc complete AGL	M2		
7	0.24	Supplying and Fabrication of steel including cost and conveyance to site and other all labour charges	MT		

8	2.00	Reinforced Cement concrete 1: 1.5 : 3 mix using 20 mm ISS Hbg metal including cost and conveyance of all materials to site and all labour charges for mixing, laying and curing etc complete for 10 cum.	M3		
Culvert					
9	97.02	Earth work excavation and depositing on bank with in initial lead of 10 mand initial lift of 2m in hard stiff clay, stiff black cotton soil, hard red earth,earth mixed with small sized boulders and hard gravelly soil as per SS 20B	M3		
10	5.88	CC 1:4:8 mix using 40mm ISS HBG metal including all other labour charges etc	M3		
11	54.83	Supplaying and erection centering for sides and sofficts inculding cost and conveyance cost of all labour charges etc complete BGL	M2		
12	22.69	Supplaying and erection centering for sides and sofficts inculding cost and conveyance cost of all labour charges etc complete AGL	M2		
13	26.16	Cement concrete 1:3:6 mix using 40mm ISS metal including cost and conveyance of all materials to site and all labour charges for mixing, laying and curing etc complete for 10 cum.	M3		
14	3.58	Cement concrete 1:2:4 mix using 20mm ISS metal including cost and conveyance of all materials to site and all labour charges for mixing, laying and curing etc complete for 10 cum.	M3		
15	2.69	Reinforced Cement concrete 1: 1.5 : 3 mix using 20 mm ISS Hbg metal including cost and conveyance of all materials to site and all labour charges for mixing, laying and curing etc complete for 10 cum.	M3		
16	0.30	Supplying and Fabrication of steel including cost and conveyance to site and other all labour charges	MT		
17	2.45	Provision for Bitumen Pad	M2		

Signature of Contractor

No of Corrections

No of Overwrittings