

TENDER SCHEDULE - B.

Tender Date : 09 - 06 - 2022

Koliyanur Block

Name of Scheme : 15th CFC (DPT , Tied) 2021-22

Estimate Amount RS: 11 ,00,000 /-

Name of Work: Construction of Cement Concrete Drainage at Colony Mettu street in Thennamadevi Panchayat.

Name of Contractor :

S.No	Quantity	Description of works	Unit	Rate in	
				in Figures	in words
Drainage					
1	168.71	Earth work excavation and depositing on bank with in initial lead of 10 mand initial lift of 2m in hard stiff clay, stiff black cotton soil, hard red earth,	M3		
2	28.12	CC 1:4:8 mix using 40mm ISS HBG metal including all other labour charges etc	M3		
3	587.70	Supplaying and erection centering for sides and sofficts inculding cost and conveyance cost of all labour charges etc complete BGL	M2		
4	73.35	Cement concrete 1:2:4 mix using 20mm ISS metal including cost and conveyance of all materials to site and all labour charges	M3		
5	73.35	Plastering in Cement Mortor 1 : 3 mix to 20 mm thick	M2		
6	11.66	Supplaying and erection centering for sides and sofficts inculding cost and conveyance cost of all labour charges etc complete AGL	M2		
7	0.47	Supplying and Fabrication of steel including cost and conveyance to site and other all labour charges	MT		
8	3.42	Reinforced Cement concrete 1: 1.5 : 3 mix using 20 mm ISS Hbg metal including cost and conveyance of all materials to site and all labour charges	M3		

Signature of Contractor

No of Corrections

No of Overwrittings