

SCHEDULE - B.

Name of work : Sinthipattu Road 0/0-1/247 in Melmalayanur block in Villupuram District

S.No	Proable Quantity	Description of works	TNBP No	Rate in words	Rate in Figures	Unit in Figures	Total Amount
		Sinthipattu Road 0/0-1/247 in Melmalayanur block in Villupuram District					
1	561.60	Clearing the scrub jungles including all labour charges for all labour charges etc complete.				Sqm	
2	187.20	Earthwork excavation in all classes of soils except hard rock requiring blasting and depositing on bank with all leads and lifts as per SS20A including cost of all labour materials, tools, equipments and all incidental charges and sheeting, shoring and br				Cum	
3	31.20	Laying US GRAVEL including cost and conveyance and stacking at site to departmental gauge for taking pre measurements by departmental officers and including labour charges for spreading the gravel as per standard specification etc. complete.(Shoulder)				Cum	
4	205.31	Providing and laying Water Bound Macadam Grading - III(63mm to11.20mm)IRC HBG of 75mm consolidated thickness consisting of clean, crushed aggregates mechanically interlocked by rolling and bonding together with screening binding material of 0.24 cum for 10 sqm (the material passing 425 microns sieve shall have liquid limit and plasticity index not more than 20 & 6% repectively) and finished in accordance with the requirements of the specification and thickness as per approved plans or as directed by the Engineer as per clause 405 of MORD revision I(Mix -in - place method) Rate for 10sqm				Cum	
5	3900.00	Applying TACK COAT over WBM surface at 4Kg / 10 sq.m including labour for spraying, hire charges for bitumen sprayer etc. Comp.				Sqm	

6	3900.00	Providing and laying Premix carpet with seal coat type 'A' for 20 mm consolidated thickness 0.18cum of 13.20 mm and 0.09 cum of 11.20 mm with 14.60 kg of 60/70 grade bitumen for pre mixing for 10 sqm for premix carpet and 0.09 cum of 6.70 mm IRC size HBG				Sqm	
7	1.00	Provision for KM Stones.				No	
8	8.00	Provision for HM Stones.(0.75 X 0.23 X 1)				No	
9	1.00	Provision for Name board Charges				No	
10	1.00	Provision for labour welfare fund 1.00%				NO	
11	1.00	Provision For GST 12.00%				No	
12	1.00	Provision for Photographic Charges				No	

Signature of Contractor

No of Corrections