

SCHEDULE - A

Name of Works : OPERATION AND MAINTENANCE OF THE CWSS TO GOUNDAMPALAYAM, VADAVALLI & VEERAKERALAM OF COIMBATORE CORPORATION IN COIMBATORE DISTRICT FOR A PERIOD OF 9 MONTHS FROM 01.7.2022 TO 31.03.2023

Sl. No.	Description of Work	Quantity	Unit	Rate (Both in figures and words)		Amount (in Rs.)
1	Operation and maintenance of pumping station by providing required manpower as to the level acceptable to the Board and to satisfy the IE rules whenever applicable and to perform themandatory duties specified in the schedule operationg and patrolling the sump, pumping mains, Air vlaves, scour valves, sluice valves in the pipe line and all mechanieries including watech and ward at night undre the control of following placeess the required maintenance staff, electricanm, maintenance Asst. Etc should be engaged at appropriate place as directed by the TWAD Board officer. For the period from 1.7.2022 to 31.3.2023 inclusive of service charges of 10% to contractors	5995.130	1 MLD	827.76	Rupees Eight hundred and twenty seven and paise seventy six Only	4962528.81
					Sub Total I	4962528.81
2	Attending Leaks in the pipelines of this CWSS for the following items, as per the standard procedure including earthwork excavation, dewatering, removing, relaying, jointing, civil works, cost of materials and all other incidental charges, etc complete within the stipulated time limit as specified in Clause 2.6.4 of General conditions of Contract - Part II.					
2.1	600 mm PSC (by providing cement joint for leaks)	1.000	Nos	20671.00	Rupees Twenty thousand six hundred and seventy one only	20671.00

Sl. No.	Description of Work	Quantity	Unit	Rate (Both in figures and words)		Amount (in Rs.)
2.2	Attending Bursts in the pipelines of this CWSS for the following items, as per the standard procedure including earthwork excavation, dewatering, removing, relaying, jointing, civil works, cost of materials and all incidental charges, etc complete within the stipulated time limit as specified in Clause 2.6.4 of General conditions of Contract - Part II.					
2.3	600 mm PSC (by dismantling the burst pipe ,removing , replacing with 600 mm MS pipe for 5m ,providing necessary MS machine ends without inside lining and outside coating but one coat of anti-rust paint to suit 600mm dia. PSC pipe using 6 mm thick plates to required dimension with minium weight of 643.12 Kg , fixing, providing cement joint for strengthening with hardcrete including cost of all materials, labour, etc., complete)	1.000	Nos	140000.00	Rupees one Lakh and Fourty thousand only	140000.00
2.4	700 mm PSC (by dismantling the burst pipe ,removing , replacing with 600 mm MS pipe for 5m ,providing necessary MS machine ends without inside lining and outside coating but one coat of anti-rust paint to suit700mm dia. PSC pipe using 7 mm thick plates to required dimension with minium weight of 809.94 Kg , fixing, providing cement joint for strengthening with hardcrete including cost of all materials, labour, etc., complete)	1.000	Nos	160055.00	Rupees one Lakh and Sixty thousand and fifty five nine only	160055.00
					Sub Total-II	320726.00
3	Supply of rewinding materials suitable for 50 HP Marathon make induction motor unit II at Goundampalayam booster station Under AM of CWSS to GV for the year 2021-22	1.000		42016.00	Rupees Fourty two thousand and sixteen only	42016.00

Sl. No.	Description of Work	Quantity	Unit	Rate (Both in figures and words)		Amount (in Rs.)
3.1	Charges rewinding and re erection of 40 HP Marathon make induction motor unit II at Goundampalayam booster station Under AM of CWSS to GV for the year 2021-22	1.000		23258.00	Rupees Twenty three thousand two hundred and fifty eight only	23258.00
					Sub Total-III	65274.00
					Grand Total	4962528.81

Rupees Fourty nine Lakhs Sixty two thousand five hundred and twenty eight and paise eighty one only

I/We, hereby agree to execute the
above item of work at % excess over / less then the value mentioned above.

1. The percentage filled by the contractor both in figures and words by using two decimal only .
2. If there is any discrepancy in percentage quoted in words and in figures, the lowest of the two will be considered.
3. If no percentage is quoted, the workers value will be taken as quoted price
4. If the contractor failed to score out the word either excess or less. The word less alone will be taken into consideration.