

Validate

Print

Help

**Item Rate BoQ**Tender Inviting Authority: **EXECUTIVE OFFICER, TOWN PANCHAYAT NARANAMMALPURAM TIRUNELVELI DISTRICT**Name of Work: **Providing interlock cement concrete rubberized paver block Road @Ward No 5,Ward No 8 ,Ward No 9 and Ward No 13 Streets in Naranammalpuram Town Panchayat**

Contract No:

Name of the Bidder/ Bidding Firm / Company :							
<b>PRICE SCHEDULE</b>							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	6	13	53	55
1	Earthwork excavation in all classes of soil including all labour charges etc. complete as per S.S.20B	119.25	m3			0	INR Zero Only
2	Plain Cement Concrete 1:4:8 (one cement, four sand and eight hard broken stone jelly) using 40mm jelly for wearing coat including laying, compacting, finishing and curing, etc., complete as per standard specificatins and as directed by the departmental officers.	39.75	m3			0	INR Zero Only
3	Supplying and erecting centering for sides and soffits of drainage side walls and lane walls with necessary C.W.Scantlings, silver oak planks, casurina poles 10 to 13 and labour charges etc, complete with standard specifications	795.00	m2			0	INR Zero Only
4	Plain Cement Concrete 1:2:4 Mix (one part cement, two part sand and four part of aggrigate) using 20mm size ISS HBG metal machine crushed from approved quarry including cost and conveyance of all materials to site, loading and unloading charges and labour charges for mixing, laying and curing etc., complete as per TNDSS NO: 28 & VI (S2) VI (S5A) VII standard specifications as directed by Engineer incharge.	79.50	m3			0	INR Zero Only

5	Providing and laying ,spreading and compacting graded stone aggregate to wet mix macadam (WMM ) Grade I specification including premixing the material with water at OMC in mechanical mix plant carriage to mixed material by tipper to site laying in uniform layers with paver in sub base / base course on well prepared surface and compacting with vibratory roller to achive the desired density complete as per clasue 404 of MORTH specifications.	609.30	m3				0 INR Zero Only
6	Supplying and fixing of HI type of interlocking colour paved block of size 250x125x80mm thick minimum compressive strngth 40 N / mm2 in uniform shape of approved make to be laid in herring bone pattern with approved non sticking surface in top. The rate inclusive of providing loading unloading and laying as per standard specifications	6093.00	m2				0 INR Zero Only
<b>Total in Figures</b>						<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>		<b>INR Zero Only</b>					