

VELUR TOWN PANCHAYAT - NAMAKKAL DISTRICT SCHEDULE - A

Est. No. :

Package- I Value Rs.20.00 Lakh

EMD.Amount (1%) : Rs.40,000/-

Tender Date & Time: 16.06.2022 & 3:30 pm

Sold to : Thiru.

Challan No.

Date:

Schedule of rates and approximate quantities to accompany the tender for the work of

Replacing of existing damaged pumping main from south end at Cauvery River Bridge in Velur Town Panchayat

a)	The quantities have given are those upon which the lump-sum tender cost at the work is caused but they are subject to alterations, omissions, deductions or additions as provided for in the conditions of the contract and do not necessarily show the actual
b)	It is to be expressively understood that the measured work it is to be taken out (Not withstanding any customarily practice to the contrary according to the actual quantities when the place and finished accordingly to the Drawings or as may be ordered tim
c)	The material required for the works must be supplied by the contractor and of the approved quality

Bidder's Signature

VELUR TOWN PANCHAYAT - NAMAKKAL DISTRICT
15TH SFC (2020-21 1st Installment) Tied Grant 2021-2022
TENDER SCHEDULE - (PACKAGE -I)

Replacing of existing damaged pumping main from south end at Cauvery River Bridge in Velur Town Panchayat

Package- I Value Rs.20.00 Lakh

Sl. No.	Probable quantity.	Description of work etc.,	MORTH SSRB	Rate in Rupees		UNIT	AMOUNT (In Rupees)
				In Figures	In Words		
1	460.00 M	Supply, erection, testing and commissioning of following MS "C" Class Heavy Duty Pipe as per IS 1239 to withstand a developing pressure of 10 kg. / sq.cm including necessary fittings like MS flange of table "E", elbows, reducers, gaskets, bolt, nuts with washers & joints as per standard method of arc welding, including one coat metal primer and two coat Post Office Red painting including conveyance, all incidental charges, necessary scaffolding and re-doing the dismantled portions to its original condition wherever found necessary, etc., complete as per standard specification and as directed by the Departmental Officers. Make: JINDAL / EQUIVALENT. (PWD SOR Page No.86. Sl. No. 351)	PWD SOR 2021-22 Sl. No.351(c)			1M (One metre)	
2	460.00 M	Cutting and dismantling the existing damaged 150mm MS pipe line from its position, loading the same in vehicle, transport upto Panchayat store and unloading etc complete as directed by the Departmental Engineer,	Special			1M (One metre)	

Bidder's Signature

3	250.00 M	Barricading work (Where, there is less traffic areas and broader roads etc.) for laying of pipe line using casurina poles at 1.50m center to center (8cm to 10cm dia and 1.80m height) vertical with horizontal poles in three rows including painting the vertical poles in the road facing sides with ready mix paint, tying the vertical and horizontal poles with coir rope including fixing charges and fixing 75mm dia reflectors including earth work excavation for fixing vertical posts and finally removing and stacking the materials safely for further use etc., complete and as directed by TWAD Board officers. TWAD SOR 2021-22 Item No. 43	TWAD SOR 2021-22 Sl. No.43(i)			1M (One metre)	
4	153.00 Nos	Fabrication, supply and fixing of Support clamps including MS flats, bolt and nut and cost of all materials and labour charges etc complete. TWAD SOR 2021-22 Item No. 5. 1b	TWAD SOR 2021-22 Sl. No.5.1(b)-24			1 No (One Number)	

Bidder's Signature