## MAMALLAPURAM TOWN PANCHAYAT

Date of Tender :
Schedule Amount:
Chellan No. :
& Date
Issued to Thiru/Tmt.

## **TENDER SCHEDULE - TYPE "A"**

## **SCHEDULE OF RATES APPROXIMATE QUANTITIES**

E.O.

- a) The quantities here given those the lump sum tender cost of work is based but they are subject to alterations omissions deductions as provided for in the conditions of this contract and do shown actual quantities of work top done to unit rates noted below are those covering payment extras of reductions omissions for according to the conditions of contract as set for in the preliminary specifications of the TNBPR and other conditions of contract specification of this contract.
- b) It is to be expressed immder stood that rent works is to be taken net (not withstanding any or practice to the contrary) according to the actual quantities in Balance finished according to the drawings or as may be provided from time by the Town Panchayat Engineer and the cost calculated by measurement or weight of the respective any additional charges for any necessary connected to the work. The rates quoted in site and complete in every respect.

Name of the Scheme: CAPITAL GRAND FUND-2022-23

Estimate Amount RS .92,00,000/-Earnest Money Deposit Rs. :Rs.92000/-

Name Of Work:

Name of Work: Providing Paver Block to Existing Earthern Road at MGR Nagar Poonjery Cross Streets in Mamallapuram Town Panchayat.

SI.	Quantity	Description of Works	MDSS/	Unit in	Rate in		Remarks
No.			SSRB	Words	Figures	Words	

No. of Corrections:

No. of Overwritings:

Signature of Contractor:

Estimate Amount RS .92,00,000/-Earnest Money Deposit Rs. :Rs.92000/-

Name Of Work: Providing Paver Block to Existing Earthern Road at MGR Nagar Poonjery Cross Streets in Mamallapuram Town Panchayat.

SI.	Quantity	Description of Works	MDSS/	Unit in		Rate in	Remarks
No.			SSRB	Words	Figures	Words	1
1		Earth work excavation for foundation and depositing on bank with in the initial lead of 10m and a lift of 2m in hard stiff clay, stiff block cotton, hard red earth, shales, murram, gravel, stoney earth and earth mixed with small size boulders etc.,as per SS 20 A. TNDSS NO: 23 & 24 VI (S2) VI,VII 9,10 with standard specifications.		1M <sup>3</sup> <sup>(</sup> One Cubic Metre)			
2	60.00 M <sup>3</sup>	Plain Cement Concrete 1:4:8 Mix (one part cement, four part M.sand and Eight part of aggrigate) using 40 mm size ISS HBG metal from approved quarry including cost and conveyance of all materials to site. Loading and unloading charges and labour charges for mixing. Laying and curing etc., complete as per TNDSS NO: 28 & VI (S2) VI (S5A) VII standard specifications as directed by Engineer incharge.		1M <sup>3</sup> <sup>(</sup> One Cubic Metre)			

Estimate Amount RS .92,00,000/-Earnest Money Deposit Rs. :Rs.92000/-

Name Of Work: Providing Paver Block to Existing Earthern Road at MGR Nagar Poonjery Cross Streets in Mamallapuram Town Panchayat.

SI.	Quantity	Description of Works	MDSS/	Unit in		Rate in	Remarks
No.			SSRB	Words	Figures	Words	1
3	2400.00 M <sup>2</sup>	Centering for soffits of CC slabs of plane surface like lintels, beams, etc., including strutting 3m high using mild steel sheets of size 90cm x 60cm x and BG 10 stiffened with MS angles of size 25mm x 25mm x 3mm laid over silver oak joists of size 10cm x 6.5 cm spaced at about 90 cm c/c and supported by consurina props of 10 cm to 13cm dia spaced of 75cm c/c complying with standard specifications and as directed by the departmentsl officers etc., complete		1M <sup>2</sup> (One Square Metre)			
4	240.00 M <sup>2</sup>	Plain Cement Concrete 1:2:4 Mix (one part cement, two part sand and four part of aggrigate) using 20mm size ISS HBG metal machine crushed from approved quarry including cost and conveyance of all materials to site, loading and unloading charges and labour charges for mixing, laying and curing etc., complete as per TNDSS NO: 28 & VI (S2) VI (S5A) VII standard specifications as directed by Engineer incharge.		1M <sup>3</sup> <sup>(</sup> One Cubic Metre)			

No. of Corrections:

Estimate Amount RS .92,00,000/-Earnest Money Deposit Rs. :Rs.92000/-

Name Of Work: Providing Paver Block to Existing Earthern Road at MGR Nagar Poonjery Cross Streets in Mamallapuram Town Panchayat.

SI.	Quantity	Description of Works	MDSS/	Unit in		Rate in	Remarks
No.			SSRB	Words	Figures	Words	
5		Construction of Granular Sub-base by providing close graded material, mixing in a machanical plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to acheive the desired density, Complete as per clause 401.		1M <sup>3</sup> <sup>(</sup> One Cubic Metre)			
6	600.00 M <sub>2</sub>	Providing and laying, spreading and compacting graded stone aggregate to Wet mix macadam (WMM) soecification including premixing the material with water at OMC in mechanical mix plant carriage to mixed material by tipper to site laying in uniform layers with paver in sub base / base course on well prepared surface and compacting with vibratory roller to achive the desired density complete as per clasue 406 of MORTH specifications.		1M <sup>3</sup> <sup>(</sup> One Cubic Metre)			

Estimate Amount RS .92,00,000/-Earnest Money Deposit Rs. :Rs.92000/-

Name Of Work: Providing Paver Block to Existing Earthern Road at MGR Nagar Poonjery Cross Streets in Mamallapuram Town Panchayat.

SI.	Quantity	Description of Works	MDSS/	Unit in		Rate in	Remarks
No.			SSRB	Words	Figures	Words	1
7	4000.00 M <sup>2</sup>	Supplying and laying Precast Designer Paver Block confirming to IS 1568-2006 specification manufacturing and laying standard of M50 grade 83mm thick (table clauses 5 and 9.14) suitable for bus terminals industrial complexes road on expensive soils etc., including the cost of paver block of size 225mm x 12.50 mm x 80mm and conveyance of materials to work site mentioned in the tender schedule cost of loading and unloading handling during over Stone dust of 100mm thick (excluding the cost of sand) conveyance paver block cutter to site and hire charges of vibrators and block cutter operator and labour for leveling the sand to paver block etc., complete ISI 15658-2006.		1M <sup>2</sup> (One Square Metre)			