

NAME OF WORK: CONSTRUCTION OF COMMUNITY HALL TO MYLAMBADI PANCHAYAT (36 HAMLET) AT BHAVANI TALUK IN ERODE DISTRICT.

a) The Quantities given here are those upon which the lump sum tender cost of the work is based, but they are subject to alternations, omissions, deductions or addition as provided for in the condition of this contract and do not necessarily show the actual quantities of work to be done. The unit rates excluding GST Amount, quoted below are those governing payment for extras or deductions or omissions according to the condition of the contract, as 1 Set (One Set) forth in the preliminary specification of the standard specifications for roads and bridges with the MORTH specifications and other condition of specifications of the contract.

b) It is expressly understood that the measured work is to be taken net (Not withstanding any custom or practice to the contrary) according to the actual quantities. When in places and finished according to the drawings, or as may be ordered from time to time by the Collector and the cost calculated by measurement or weight at the respective prices, without any additional charges for any necessary or contingent works concerned therewith. The rates quoted excluding GST Amount are for the finished works in situ and complete in every respect.

SCHEDULE - A

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
1	91.00	Cu.m	Earth work excavation for foundation (for narrow excavation) in all soils and sub-soils and to full depth as may be directed except in rock requiring blasting inclusive of shoring shuttering, bailing out water wherever necessary and depositing the surplus earth within the compound in places shown by the departmental officers with an initial lead of 10 mts and initial lift of 2 mts. and clearing and levelling the site, etc., complete complying with standard specification.	23 & 24 VI (S2)	Rs.	214.55	Rupees Two Hundred Fourteen and Fifty Five Paise Only	1 Cum (One Cubic metre)	19524.00
2	36.00	Cu.m	Earth work open excavation in all soils and sub-soils and to full depth as may be directed except in rock requiring blasting inclusive of shoring shuttering, bailing out water wherever necessary and depositing the excavated earth with a lead of 10 mts. within the compound in places shown by the departmental officers and clearing and levelling the site, etc., complete complying with standard specification.	23 & 24 VI (S2)	Rs.	101.70	Rupees One Hundred One and Seventy Paise Only	1 Cum (One Cubic metre)	3661.00
3	12.50	Cu.m	Cement Concrete 1:4:8 (One Cement, Four M.Sand and Eight hard broken stone jelly) using 40 mm gauge hard broken granite stone jelly for foundation including dewatering wherever necessary and laid in layers of not more than 15 cm thick well rammed, consolidated and curing etc. complete complying with standard specification	28 V & VI (s2)(S5A) VII	Rs.	4667.10	Rupees Four Thousand Six Hundred Sixty Seven and Ten Paise Only	1 Cum (One Cubic metre)	58339.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
4	15.00	Cu.m	Flooring Concrete 1:4:8 (One cement, Four M.Sand and Eight hard broken stone) using 40 mm gauge hard broken jelly for flooring including laying, consolidating, finishing, rendering the top surface rough to receive the floor, curing, etc. complete complying with standard specification. (The rate is inclusive of necessary planking for panelling wherever necessary and as directed by the departmental officers.	39 & 39C V, VI(S)	Rs.	4667.10	Rupees Four Thousand Six Hundred Sixty Seven and Ten Paise Only	1 Cum (One Cubic metre)	70007.00
5	1.50	Cu.m	Plain Cement Concrete 1:2:4 (one cement, two M.Sand and four hard broken stone jelly) using 20mm jelly for wearing coat including laying, compacting, finishing and curing, etc., complete as per standard specifications and as directed by the departmental officers.		Rs.	6011.40	Rupees Six Thousand Eleven and Forty Paise Only	1 Cum (One Cubic metre)	9017.00
6	14.00	Cu.m	Supplying and filling in foundation, basement, etc with filling M.Sand in layers of not more than 15 cm thick well watered, rammed and consolidated etc. complete complying with standard specification and as directed by the departmental officers.		Rs.	1622.60	Rupees One Thousand Six Hundred Twenty Two and Sixty Paise Only	1 Cum (One Cubic metre)	22716.00
7	37.00	Cu.m	Refilling with excavated earth other than M.Sand with an initial head load of 100 mts. and depositing the earth as shown by the departmental officers in layers of not more than 15 cm thick well rammed, watered and consolidated etc. complete complying with standard specification.	24, 25 VI (S2)	Rs.	33.60	Rupees Thirty Three and Sixty Paise Only	1 Cum (One Cubic metre)	1243.00
8	53.00	Cu.m	Supplying and filling in foundation, basement, etc with conveyed Well gravel in layers of not more than 15 cm thick well watered, rammed and consolidated etc. complete complying with standard specification and as directed by the departmental officers.	24, 25		251.00	Rupees Two Hundred Fifty One Only)	1 Cum (One Cubic metre)	13303.00
9	3.00	Cu.m	Supplying and filling 40mm gauge HBGS stone jelly for dispersion trench including loading conveying and unloading and as directed by the departmental officers etc. complete complying with standard specification.	24 & 25 V,VI, S2	Rs.	1293.70	Rupees One Thousand Two Hundred Ninety Three and Seventy Paise Only	1 Cum (One Cubic metre)	3881.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
10	129.00	Sq.m	Supplying and erecting steel centering including necessary supports for plane surfaces for Reinforced Cement Concrete works such as column footings, column pedestals, plinth beams, grade beams, staircase steps, etc. which require only nominal strutting using mild steel sheets of size 90cm x 60cm and 10 BG stiffened with welded mild steel angles of size 25mm x 25mm x 3 mm for boarding, laid over silver oak joists of size 10cm x 6.5cm spaced at about 75cm centre to centre or at suitable intervals etc. complete in all floors complying with standard specification. (Payment for centering shall be given after the concrete is laid).	30 V, VII (S3)		747.60	Rupees Seven Hundred Forty Seven and Sixty Paise Only	1 Sqm (One Squire metre)	96440.00
11			Supplying and erecting centering for sides and soffits including necessary supports and strutting upto 3.29 M height for plane surfaces as detailed below in all floors with all cross bracings using Mild Steel sheets of size 90 x 60 cm and 10 BG stiffened with welded Mild Steel angle of size 25mm x 25mm x 3 mm for boarding laid over silver oak joists of size 10cm x 6.50 cm spaced at abote 90 cm centre to centre and supported by casurina props of 10cm to 13 cm dia spaced at not more than 75 cm centre to centre etc. complete complying with the standard specificaliton. (Payment for centering shall be given after the concrete is laid).						
a	394.00	Sq.m	For plane surfaces such as RCC floor slab, roof slab, beams, lintels, bed blocks, landing slab, waist slab, portico slabs and beams, etc.	30 V, VII (S3), VII	Rs.	840.30	Rupees Eight Hundred Forty and Thirty Paise Only	1 Sqm (One Squire metre)	331078.00
b	165.00	Sq.m	For plane surfaces such as rectangular or square RCC columns, sunshades, top and bottom slab of RCC boxing, etc.	30 V, VII (S3), VII	Rs.	1008.40	Rupees One Thousand Eight and Forty Paise Only	1 Sqm (One Squire metre)	166386.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
12			Cement Concrete 1:1-1/2:3 (One Cement, One and a half M.Sand and Three hard broken stone jelly) using 20 mm gauge hard broken granite stone jelly for all RCC items of works excluding cost of reinforcement grill and fabricating charges centering and shuttering but including laying, vibrating with mechanical vibrators, finishing, curing, etc. and providing fixtures like fan clamps in the RCC floor / roof slabs wherever necessary and bearing surfaces of walls, beams etc. shall be finished smooth with Cement Mortar 1:3 (One Cement and Three M.Sand) and kraft paper laid over it without claiming extra, etc., complete complying with standard specification and as directed by the departmental officers						
a	41.00	Cu.m	For foundation & basement	30 & 46J V, VI (S3) VII		8005.54	Rupees Eight Thousand Five and Fifty Four Paise Only	1 Cum (One Cubic metre)	328227.00
b	43.00	Cu.m	In Ground floor	30 & 46J V, VI (S3) VII	Rs.	8108.84	Rupees Eight Thousand One Hundred Eight and Eighty Four Paise Only	1 Cum (One Cubic metre)	348680.00
c	17.00	Cu.m	In First floor	30 & 46J V, VI (S3) VII	Rs.	8312.34	Rupees Eight Thousand Three Hundred Twelve and Thirty Four Paise Only	1 Cum (One Cubic metre)	141310.00
13			Cement Concrete 1:3:6 (One Cement, Three M.Sand and Six broken stone jelly) using 40mm size hard broken stone jelly for dummy columns, excluding cost of centering shuttering reinforcement grills and fabrication charges but including curing etc. complete. (Reinforced Cement Concrete 1:2:4 for slab to be extended upto top of splashing with pressed tiles and future extension rods to be embedded in CC 1:3:6 (One Cement, Three M.Sand and Six hard broken stone jelly). Dummy columns should be at least 1 metre height)						
a	0.50	Cu.m	In First floor	30 s V,VI, (S5) VII & 13		5301.08	Rupees Five Thousand Three Hundred One and Eight Paise Only	1 Cum (One Cubic metre)	2651.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
b	0.50	Cu.m	In Second floor	30 s V,VI, (S5) VII & 13	Rs.	5504.58	Rupees Five Thousand Five Hundred Four and Fifty Eight Paise Only	1 Cum (One Cubic metre)	2752.00
14	95.00	Qtl	Supplying, fabricating and placing in position Mild Steel / Ribbed Tor Steel grills for all RCC works as per design given including cost of steel and G.I. binding wire in all floors etc. complete complying with standard specification. (Contractor has to make his own arrangements for the supply of steel and binding wire)	39 & 39C V, VI(S)	Rs.	7849.74	Rupees Seven Thousand Eight Hundred Forty Nine and Seventy Four Paise Only	1 Qtl (One Quintal)	745725.00
15			Manufacturing, supplying and fixing Precast Reinforced Cement Concrete slabs of following thickness in RCC 1:2:4 (one cement, two M.Sand and four aggregates), using following HBGS jelly excluding cost of reinforcement steel in position but including cost of moulding charges, casting of slab, finishing, curing and fixing in position in all floors etc., complete complying with standard specification and as directed.						
a	5.00	Sq.m	25mm Thick slab	Special		227.10	Rupees Two Hundred Twenty Seven and Ten Paise Only	1 Sqm (One Squire metre)	1136.00
b	21.00	Sq.m	50mm Thick slab	Special	Rs.	466.40	Rupees Four Hundred Sixty Six and Forty Paise Only	1 Sqm (One Squire metre)	9794.00
16			Brick work using using Country Bricks of size 8-3/4" x 4-1/4" X2-3/4" in Cement Mortar 1:6 (One cement and six M.Sand) including curing neat finishing, etc., complete complying with standard specifiction.						
a	14.50	Cu.m	For foundation & basement	31&Similar to 31C V, VI (S5) VII		5360.00	Rupees Five Thousand Three Hundred Sixty Only)	1 Cum (One Cubic metre)	77720.00
b	40.00	Cu.m	In Ground floor	31&Similar to 31C V, VI (S5) VII	Rs.	5428.00	Rupees Five Thousand Four Hundred Twenty Eight Only)	1 Cum (One Cubic metre)	217120.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
c	33.50	Cu.m	In First floor	31&Similar to 31C V, VI (S5) VII	Rs.	5565.20	Rupees Five Thousand Five Hundred Sixty Five and Twenty Paise Only	1 Cum (One Cubic metre)	186434.00
d	2.50	Cu.m	In Second floor	31&Similar to 31C V, VI (S5) VII	Rs.	5702.40	Rupees Five Thousand Seven Hundred Two and Forty Paise Only	1 Cum (One Cubic metre)	14256.00
17			Brick work using using Country Bricks of size 8-3/4" x 4-1/4" X2-3/4" in Cement Mortar 1:3 (One cement and three M.Sand) including curing neat finishing, etc., complete complying with standard specification.						
a	7.00	Cu.m	For foundation & basement	31&Similar to 31C V, VI (S5) VII		5723.60	Rupees Five Thousand Seven Hundred Twenty Three and Sixty Paise Only	1 Cum (One Cubic metre)	40065.00
18			Brick partition walls using best quality using Country Bricks of size 8-3/4" x 4-1/4" X2-3/4" in Cement Mortar 1:3 (One Cement and Three M.Sand) using hoop iron reinforcement if found necessary including curing etc. complete and as directed by the departmental officers. (Hoop iron reinforcement will be measured and paid for separately).						
a	5.00	Sq.m	For foundation & basement	31&Similar to 31C V, VI (S5) VII	Rs.	704.25	Rupees Seven Hundred Four and Twenty Five Paise Only	1 Sqm (One Squire metre)	3521.00
b	15.00	Sq.m	In Ground floor	31&Similar to 31C V, VI (S5) VII	Rs.	711.60	Rupees Seven Hundred Eleven and Sixty Paise Only	1 Sqm (One Squire metre)	10674.00
c	15.00	Sq.m	In First floor	31&Similar to 31C V, VI (S5) VII	Rs.	726.45	Rupees Seven Hundred Twenty Six and Forty Five Paise Only	1 Sqm (One Squire metre)	10897.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
19	1.00	Cu.m	Weathering course in brick jelly lime concrete using broken brick jelly of size 20mm uniform gauge in pure slaked lime (no M.Sand to be used) to the proportion of brick jelly to lime being 32:12.5 by volume and laid over the RCC roof slab in a single layer of required slope and finished by beating the concrete with wooden beaters of approved pattern, keeping the surface constantly wet by sprinkling lime jaggery water, etc., complete as per standard specification and as directed by the departmental officers.	30G V, VI, S5		3853.10	Rupees Three Thousand Eight Hundred Fifty Three and Ten Paise Only	1 Cum (One Cubic metre)	3853.00
20	8.00	Sq.m	Finishing the top of roof with one course of machine pressed tiles of size 230mm x 230mm x 20mm of approved quality set in Cement Mortar 1:3 (One Cement and Three M.Sand) 12mm thick mixed with water proofing compound conforming to ISS at 2% by weight of cement used and the joints pointed neatly to full depth of tiles with the same cement mortar mixed with red oxide and water proofing compound including curing etc., complete complying with standard specification and as directed by the departmental officers	Special	Rs.	1080.80	Rupees One Thousand Eighty and Eighty Paise Only	1 Sqm (One Squire metre)	8646.00
21			Flooring with following ceramic tiles of size 305 x 305 x 6 mm laid over 20 mm thick cement mortar 1:3 (One Cement and Three M.Sand) base mortar over the existing slab / floor including cutting the tiles to the required size with special cutter wherever necessary, laying in position and pointing with white cement mixed with colouring pigment at the rate of 0.3 Kg. / sq.m. etc., complete complying with standard specification. (The make and brand of the tiles should be got approved by Executive Engineer before use on works)						
a	147.00	Sq.m	Plain Ceramic Tiles of size 305 x 305 x 6mm	Special		788.00	Rupees Seven Hundred Eighty Eight Only)	1 Sqm (One Squire metre)	115836.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
22			Dadoing walls with following best approved quality, white / colour glazed tiles of following sizes set in Cement Mortar 1:2 (One Cement and Two M.Sand) 10mm thick and pointing the joints with white cement mixed with colouring pigments at the rate of 0.40 Kg. / sq.m. neatly in all floors, curing, etc., complying with standard specification and as directed by the departmental officers.						
a	23.00	Sq.m	Cost of Colour glazed tiles of size 150mm X150mm X 6mm size	Special		1216.20	Rupees One Thousand Two Hundred Sixteen and Twenty Paise Only	1 Sqm (One Squire metre)	27973.00
23			Providing granolithic floor finish of the following thickness with plain cement concrete 1:2:4 (One Cement, Two M.Sand and Four aggregate) using 10 to 12mm gauge hard broken stone jelly including laying, finishing and the top rubbed smooth with power trowl, thread lining, curing etc. complete complying with standard specification and as directed by the departmental officers. (The rate is inclusive of necessary planking for panelling wherever necessary and as directed by the departmental officers).						
a	149.00	Sq.m	For 25 mm thick	Special		151.20	Rupees One Hundred Fifty One and Twenty Paise Only	1 Sqm (One Squire metre)	22529.00
24			Supplying and fixing in position best approved of BIS quality PVC rain water down fall pipes having a pressure of 4 kg. / sq.cm including cost of necessary PVC shoe, PVC bend, cast iron gratings of required diameter and special clamps, brass screws, nails, etc., and fixing of cast iron gratings at junction of parapet and the RCC roof slab including finishing neatly etc., complete. The rate shall be inclusive of cast of removable cast iron grating. The PVC pipe shall be fixed in wall with special type of "U" clamp at the centre of the pipe line in addition to those for more than 3.0 metre pipe length, etc., complete complying with standard specification.						
a	35.00	Rm	110 mm dia PVC Pipe	Special	Rs.	532.70	Rupees Five Hundred Thirty Two and Seventy Paise Only	1 RM (One Running metre)	18645.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
25	250.00	Kg	Supplying & fixing mild steel grills for opening, corridor sides, ladder entrance gate and Name board angles, windows, ventilators, etc., including priming coat etc., complete complying with standard specification and as directed.	30 V, VI	Rs.	90.20	Rupees Ninety and Twenty Paise Only	1 Kg (One Kilo gram)	22550.00
26	5.00	Rm	Supplying and Fixing MS Ladder width 45cm using 50x50x6mm MS Angle including priming coat etc., complete complying with standard specification and as directed.	30 V, VI	Rs.	1273.80	Rupees One Thousand Two Hundred Seventy Three and Eighty Paise Only	1 RM (One Running metre)	6369.00
27	1182.00	Sq.m	Plastering with Cement Mortar 1:5 (One cement and Five P.Sand), 12mm thick in all floors including curing etc. complete complying with standard specification and as directed by the departmental officers.	56, 57 & V, VI (s4) 3	Rs.	220.60	Rupees Two Hundred Twenty and Sixty Paise Only	1 Sqm (One Squire metre)	260749.00
28	270.00	Sq.m	Special ceiling plastering and finishing the exposed surface of all RCC items of work such as slabs, beams, sunshades, fascia, canopy slab, staircase waist slab, landing slab etc., with Cement Mortar 1:3 (One Cement and Three P.Sand) 10mm thick including hacking the surfaces, providing cement mortar nosing, beading for sunshades, staircases, steps, landing slabs and curing, etc., in all floors complying with standard specification and as directed by the departmental officers	Special	Rs.	252.50	Rupees Two Hundred Fifty Two and Fifty Paise Only	1 Sqm (One Squire metre)	68175.00
29	38.00	Sq.m	Plastering with Cement Mortar 1:3 (One Cement and Three P.Sand) 20mm thick mixed with water proofing compound conforming to BIS at 2% by weight of cement used including finishing, curing, etc., complete in all floors complying with standard specification and as directed by the departmental officers.	56, 57 & V, VI (s4) 3	Rs.	473.50	Rupees Four Hundred Seventy Three and Fifty Paise Only	1 Sqm (One Squire metre)	17993.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
30	3.78	Sq.m	Manufacturing supplying and fixing of Single Leaf Steel Door with the following specification MS angels of size 40x40x6mm are used for the outer frames and M.S. angles of size 35x35x5mm for the shutter frames stiffeners with 32 x 6mm M.S flat is provided at required intervals in the shutter frame. 18-gauge C.R. sheet laid as panel in the shutter and welded intact. M.S. flat 18x5mm is welded over the 32 x 6mm M.S. flat M.Sandwiching the C.R. sheet in between additional stiffeners with 18x5mm M.S. flat is provided diagonally at the rear side of the shutter, 3nos. of hinges in case of single leaf and 6nos. of hinges in double leaves shutter to be provided 6nos. of holdfasts 120 mm in length made of angle section spliced at the ends are welded to the outer frames of the door. Tower bolts 2nos. one at the top and the other at the bottom are provided 1no. Aldrop is provided incase of double leaf door at lock rail section in the door in single leaf door, one more aldrop is provided in the inner lock rail section of.All members are painted with one coat of anti-corrosive red oxide primer as directed by the departmental officers. All sections should be in confirmed with IS 7452/1990.The cost includes cost of all materials, labour charges and other incidental charges, etc., complete the one shutter t conceal the gap between the two shutters.at an appropriate place in the door. A tie bar is provided at the bottom of the frame to prevent twisting of frame during transportation and fixing. All members are given a coat of red oxide primer as directed by the departmental officers. The rate includes cost of all materials, labour charges, transportation to site of work, loading, un loading and all other incidental charges etc., complete.	Special	Rs.	4094.00	Rupees Four Thousand Ninety Four Only)	1 Sqm (One Squire metre)	15475.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
31	13.86	Sq.m	Manufacturing supplying and fixing of Double Leaf Steel Door with the following specification MS angels of size 40x40x6mm are used for the outer frames and M.S. angles of size 35x35x6mm for the shutter frames stiffeners with 32 x 6mm M.S flat is provided at required intervals in the shutter frame. 18-gauge C.R. sheet laid as panel in the shutter and welded intact. M.S. flat 18x5mm is welded over the 32 x 6mm M.S. flat M.Sandwitching the C.R. sheet in between additional stiffeners with 18x5mm M.S. flat is provided diagonally at the rear side of the shutter, 3nos. of hinges in case of single leaf and 6nos. of hinges in double leaves shutter to be provided 6nos. of holdfasts 120 mm in length made of angle section spliced at the ends are welded to the outer frames of the door. Tower bolts 2nos. one at the top and the other at the bottom are provided 1no. Aldrop is provided incase of double leaf door at lock rail section in the door in single leaf door, one more aldrop is provided in the inner lock rail section of the door One rotaing locking arrangements for the inner side of the door and additional provision for locking arrangements for lock is provided on the rear side of the door at an appropriate place. Incase of double leaf door M.S.Flat 32 x 3mm at 1.1Kg/m is provided on the one shutter t conceal the gap between the two shutters.at an appropriate place in the door. A tie bar is provided at the bottom of the frame to prevent twisting of frame during transportation and fixing. All members are given a coat of red oxide primer as directed by the departmental officers. The rate includes cost of all materials, labour charges, transportation to site of work, loading, un loading and all other incidental charges etc., complete.	Special	Rs.	4606.00	Rupees Four Thousand Six Hundred Six Only)	1 Sqm (One Squire metre)	63839.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
32			Fabricating, Supplying and fixing in position of steel sheeted windows with the following specifications. Outer frames of windows made of 'Z' section F7D of size 33 x 25 x 3mm at 1.419 kg/ m and mullion 'J' section (F4B) of size 46x25x3mm at 2.28kg/m and shutter section of made of F7D of 33x25x3mm at 1.419 kg/m as specified in IS 7452/1990. Each openable shutter should not exceed a width of 600mm to enable separate operations and easy maintenance. The panel of the shutters to be covered with 18 gauge cold rolled sheet of superior quality and welded intact with shutter frames. Horizontal stiffeners using 18x5mm MS Flat at 0.70kg/m at 3 Nos. for each shutter and additional diagonal stiffeners of the same MS flats at all the four corners of each shutters to the suitable length welded to the shutters, for holding the CR Sheets in position firmly. 2 numbers of sturdy hinges and one number of handle-cum-latch of special type made with 18x5mm MS flats are revetted to the shutters at an appropriate height in window. All members are painted with one coat of anti-corrosive red oxide primer as directed by the departmental officers. All sections should be in confirmed with IS 7452/1990. The cost includes cost of all materials, labour charges and other incidental charges, etc., complete						
a	23.40	Sq.m	Two Leaves with Four Shutter	Special	Rs.	5717.00	Rupees Five Thousand Seven Hundred Seventeen Only)	1 Sqm (One Squire metre)	133778.00
33	3.50	Sq.m	Solid PVC door shutters using 19 Gauge 19mm MS square tubes for styles and outer frames. 15mm MS square tubes for top, lock and bottom rails. The steel tubes shall be covered with 5mm thick solid PVC sheets. Shutter using 5mm thick solid PVC sheets for panelling shall rigidly fixed in position including necessary furniture and fittings. The over all size of styles shall be 50mm x 30mm. The over all size of top rail, Lock rail and bottom rail shall be 75mm x 30mm. The over all size of frames shall be 50mm x 45mm, with suitable rabate for housing the shutter.	Special	Rs.	3167.00	Rupees Three Thousand One Hundred Sixty Seven Only)	1 Sqm (One Squire metre)	11085.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
34	270.00	Sq.m	White washing two coats with freshly burnt white shell lime in all floors including cost of lime, blue powder fevicol type gum, brushes, scaffolding charges, etc., complete complying with standard specification and as directed.	SS 63 VI, VII 2, 3	Rs.	29.10	Rupees Twenty Nine and Ten Paise Only	1 Sqm (One Squire metre)	7857.00
35	613.00	Sq.m	Colour washing Two Coats in all floors using best freshly burnt white shell lime and best quality of approved variety of colouring pigment including cost of lime, colouring pigments, fevicol type gum, brushes, scaffolding charges etc., complete complying with standard specification. Mineral colouring pigments not affected by lime should only be used (stainers and colour solutions should not be used.)	Special	Rs.	43.65	Rupees Forty Three and Sixty Five Paise Only	1 Sqm (One Squire metre)	26757.00
36	570.00	Sq.m	Painting two coats of newly plastered wall surface with ready mixed plastic emulsion paint of first class quality and of approved colour over a priming coat including thorough scrapping, clean removal of dirt, and including necessary plaster of paris putty, wherever required etc., complete complying with standard specification.	Specials	Rs.	211.80	Rupees Two Hundred Eleven and Eighty Paise Only	1 Sqm (One Squire metre)	120726.00
37	96.00	Sq.m	Painting new iron works such as steel doors, windows, ventilators, window bars, balustrades etc., with two coats of best approved first quality and colour of synthetic enamel paint over the existing red oxide priming coat in all floors excluding cost of priming coat etc., complete complying with standard specification. (The make, quality and colour of paint should be got approved by the Executive Engineer before use on works.)	66, 66 V2, VII 13,5	Rs.	126.20	Rupees One Hundred Twenty Six and Twenty Paise Only	1 Sqm (One Squire metre)	12115.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
38			Supplying, laying, fixing and jointing the following size of B Class GI Pipe of approved quality and best variety above ground level including fixing of GI specials but excluding cost of such specials and cutting and threading of pipes and also fixing to the wall with necessary Teak Wood Plugs, Clamps and screws making holes on the wall or drilling holes in roof and making good of the disturbed portions to original condition with necessary brick work and plastering wherever necessary with necessary scaffolding changes. The pipe are to be painted with two coats of good variety and best quality synthetic enamel paint over a coat of red oxide primer etc., complying with standard specification (above ground level).						
a	20.00	Rm	15mm dia G.I Pipe	97 & 102	Rs.	245.85	Rupees Two Hundred Forty Five and Eighty Five Paise Only	1 RM (One Running metre)	4917.00
b	25.00	Rm	20mm dia G.I Pipe	97 & 102	Rs.	277.95	Rupees Two Hundred Seventy Seven and Ninety Five Paise Only	1 RM (One Running metre)	6949.00
c	25.00	Rm	25mm dia G.I Pipe	97 & 102	Rs.	310.10	Rupees Three Hundred Ten and Ten Paise Only	1 RM (One Running metre)	7753.00
39			Supplying, Laying, fixing and jointing the following size of B Class GI Pipes of approved quality and best variety before ground level and laid properly to alignment including fixing of GI specials but excluding cost of such specials and cutting and threading of pipes. The rate is inclusive of necessary earthwork excavation of size 40cms width to an average depth of 50ccms. Including M.Sand filling to a depth of 15cm. The pipes is to be covered with tar dripped gunny tapes and the trench refilled with the excavated earth etc., complete (Below ground level)						
a	25.00	Rm	20mm dia G.I Pipe	97 & 102	Rs.	353.65	Rupees Three Hundred Fifty Three and Sixty Five Paise Only	1 RM (One Running metre)	8841.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
b	25.00	Rm	25mm dia G.I Pipe	97 & 102	Rs.	382.75	Rupees Three Hundred Eighty Two and Seventy Five Paise Only	1 RM (One Running metre)	9569.00
c	25.00	Rm	32mm dia G.I Pipe	97 & 102	Rs.	543.90	Rupees Five Hundred Forty Three and Ninety Paise Only	1 RM (One Running metre)	13598.00
40			Supplying and fixing in position first quality and approved variety of Gun metal Gate Valve / Wheel Valve with BIS make of the following dia including cost of shellac, thread balls, etc., complete complying with standard specifications (for both internal and external water supply arrangements). The valves to be used on work shall be got approved by the Executive Engineer before use on work.						
I			Gate Valve						
a	2.00	Nos	20mm Gun Metal full way Gate valve	97 & 102	Rs.	677.20	Rupees Six Hundred Seventy Seven and Twenty Paise Only	1 No (One Number)	1354.00
b	2.00	Nos	25mm Gun Metal full way Gate valve	97 & 102	Rs.	917.20	Rupees Nine Hundred Seventeen and Twenty Paise Only	1 No (One Number)	1834.00
c	2.00	Nos	32mm Gun Metal full way Gate valve	97 & 102	Rs.	1190.80	Rupees One Thousand One Hundred Ninety and Eighty Paise Only	1 No (One Number)	2382.00
41			Supplying and fixing in position GI unions of heavy duty of approved quality and good variety of various sizes including necessary cutting and threading of GI pipes for jointing the union and providing two coats of painting with good variety and approved quality of synthetic enamel paint over one coat of primer in case of pipe line above ground level / one coat of tar in case of below ground level for both internal and external water supply arrangements, etc., complete complying with standard specifications. (The GI unions should be got approved by Executive Engineer before use on works).						
a	3.00	Nos	20mm Union	97 & 102	Rs.	334.32	Rupees Three Hundred Thirty Four and Thirty Two Paise Only	1 No (One Number)	1003.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
b	3.00	Nos	25mm Union	97 & 102	Rs.	363.12	Rupees Three Hundred Sixty Three and Twelve Paise Only	1 No (One Number)	1089.00
c	3.00	Nos	32mm Union	97 & 102	Rs.	392.05	Rupees Three Hundred Ninety Two and Five Paise Only	1 No (One Number)	1176.00
42			Supplying and fixing in position the following GI Specials of heavy type and approved quality and good variety excluding fixing charges but including necessary cutting and threading of GI pipes, jointing the GI specials and painting with two coats with good variety and best quality synthetic enamel paint over a coat of red oxide primer and jointing the specials with pipe line using shellac etc., complete complying with standard specification. (The GI specials should be got approved by the Executive Engineer concerned before use on works.)						
I			Elbow						
a	5.00	Nos	32mm dia Elbow	97 & 102	Rs.	168.00	Rupees One Hundred Sixty Eight Only)	1 No (One Number)	840.00
b	5.00	Nos	25mm dia Elbow	97 & 102	Rs.	119.15	Rupees One Hundred Nineteen and Fifteen Paise Only	1 No (One Number)	596.00
c	5.00	Nos	20mm dia Elbow	97 & 102	Rs.	58.50	Rupees Fifty Eight and Fifty Paise Only	1 No (One Number)	293.00
d	5.00	Nos	15mm dia Elbow	97 & 102	Rs.	48.60	Rupees Forty Eight and Sixty Paise Only	1 No (One Number)	243.00
II			Bend						
a	3.00	Nos	32mm dia Bend	97 & 102	Rs.	150.80	Rupees One Hundred Fifty and Eighty Paise Only	1 No (One Number)	452.00
b	3.00	Nos	25mm dia Bend	97 & 102	Rs.	113.05	Rupees One Hundred Thirteen and Five Paise Only	1 No (One Number)	339.00
c	3.00	Nos	20mm dia Bend	97 & 102	Rs.	56.30	Rupees Fifty Six and Thirty Paise Only	1 No (One Number)	169.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
d	3.00	Nos	15mm dia Bend	97 & 102	Rs.	46.30	Rupees Forty Six and Thirty Paise Only	1 No (One Number)	139.00
III			TEE						
a	4.00	Nos	32mm dia Tee	97 & 102	Rs.	226.20	Rupees Two Hundred Twenty Six and Twenty Paise Only	1 No (One Number)	905.00
b	4.00	Nos	25mm dia Tee	97 & 102	Rs.	178.00	Rupees One Hundred Seventy Eight Only)	1 No (One Number)	712.00
c	4.00	Nos	20mm dia Tee	97 & 102	Rs.	88.60	Rupees Eighty Eight and Sixty Paise Only	1 No (One Number)	354.00
f	4.00	Nos	15mm dia Tee	97 & 102	Rs.	81.85	Rupees Eighty One and Eighty Five Paise Only	1 No (One Number)	327.00
IV			Coupling						
a	7.00	Nos	32mm dia Coupling	97 & 102	Rs.	127.50	Rupees One Hundred Twenty Seven and Fifty Paise Only	1 No (One Number)	893.00
b	7.00	Nos	25mm dia Coupling	97 & 102	Rs.	89.65	Rupees Eighty Nine and Sixty Five Paise Only	1 No (One Number)	628.00
c	7.00	Nos	20mm dia Coupling	97 & 102	Rs.	49.00	Rupees Forty Nine Only)	1 No (One Number)	343.00
d	7.00	Nos	15mm dia Coupling	97 & 102	Rs.	46.30	Rupees Forty Six and Thirty Paise Only	1 No (One Number)	324.00
V			Reducer						
a	2.00	Nos	32 x 25 mm dia GI Reducer	97 & 102	Rs.	123.00	Rupees One Hundred Twenty Three Only)	1 No (One Number)	246.00
b	2.00	Nos	25 x 20 mm dia GI Reducer	97 & 102	Rs.	75.65	Rupees Seventy Five and Sixty Five Paise Only	1 No (One Number)	151.00
c	2.00	Nos	20 x 15 mm dia GI Reducer	97 & 102	Rs.	53.20	Rupees Fifty Three and Twenty Paise Only	1 No (One Number)	106.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
d	2.00	Nos	32 x 20 mm dia GI Reducer	97 & 102	Rs.	97.45	Rupees Ninety Seven and Forty Five Paise Only	1 No (One Number)	195.00
VI			Reducer Elbow						
a	2.00	Nos	32 x 25 mm dia GI Reducer Elbow	97 & 102	Rs.	140.80	Rupees One Hundred Forty and Eighty Paise Only	1 No (One Number)	282.00
b	2.00	Nos	25 x 20 mm dia GI Reducer Elbow	97 & 102	Rs.	99.05	Rupees Ninety Nine and Five Paise Only	1 No (One Number)	198.00
c	2.00	Nos	20 x 15 mm dia GI Reducer Elbow	97 & 102	Rs.	73.30	Rupees Seventy Three and Thirty Paise Only	1 No (One Number)	147.00
d	2.00	Nos	32 x 20 mm dia GI Reducer Elbow	97 & 102	Rs.	114.65	Rupees One Hundred Fourteen and Sixty Five Paise Only	1 No (One Number)	229.00
VII			Reducer Tee						
a	2.00	Nos	32 x 25 mm dia GI Reducer Tee	97 & 102	Rs.	210.70	Rupees Two Hundred Ten and Seventy Paise Only	1 No (One Number)	421.00
b	2.00	Nos	25 x 20 mm dia GI Reducer Tee	97 & 102	Rs.	150.55	Rupees One Hundred Fifty and Fifty Five Paise Only	1 No (One Number)	301.00
c	2.00	Nos	20 x 15 mm dia GI Reducer Tee	97 & 102	Rs.	123.35	Rupees One Hundred Twenty Three and Thirty Five Paise Only	1 No (One Number)	247.00
d	2.00	Nos	32 x 20 mm dia GI Reducer Tee	97 & 102	Rs.	172.15	Rupees One Hundred Seventy Two and Fifteen Paise Only	1 No (One Number)	344.00
VIII			Hex Nipple						
a	5.00	Nos	20mm dia GI Hex Nipple	97 & 102	Rs.	37.50	Rupees Thirty Seven and Fifty Paise Only	1 No (One Number)	188.00
b	5.00	Nos	15mm dia GI Hex Nipple	97 & 102	Rs.	26.00	Rupees Twenty Six Only)	1 No (One Number)	130.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
43			Supplying and fixing in position best quality and approved make Indian made white / colour glazed earthenware wash hand basin of size 550 x 400mm (with pedestal / without pedestal) with a pair of cast iron brackets, including cost 15mm dia brass CP pillar tap, 32mm dia "B" class GI waste pipe with rubber plug and chain, 15mm dia GM wheel valve, 15mm brass nipple, 15mm dia nylon connection, 32mm dia CP brass waste coupling including fixing of wash basin using CI brackets on to the wall in position with TW plugs and screws, rubber washers, white lead and giving necessary water supply connection and painting the brackets with two coat of painting over a priming coat of anti-corrosive paint including testing for leakages etc., complete complying with standard specification and as directed by the departmental officers. (The wash hand basin and specials should be got approved by the Executive Engineer before use on works).						
ii			Colour Glazed Wash Hand Basin						
a	2.00	Nos	Without Pedestal	Special	Rs.	4053.00	Rupees Four Thousand Fifty Three Only)	1 No (One Number)	8106.00
44	2.00	Nos	Supplying and fixing in position Indian Water Closet (Oriya type) of size 580 x 440mm white glazed earthen ware of approved quality and brand with "P" or "S" trap conforming to BIS with M.Sand cushion and forming flooring around the closet using 40mm broken brick jelly in lime concrete 1:2:5 (One lime, Two M.Sand and Five brick jelly) 100mm thick and finishing the top to the required slope and including giving necessary connection to PVC pipes (including the cost of 110mm dia PVC pipe for a length of 600mm) by dismantling brick masonry wall / reinforced cement concrete roof / floor slab and making good the dismantled portion to the original condition with leakages etc., complete complying with standard specifications and as directed by the departmental officers. (The water closet should be got approved by the Executive Engineer before use on works).	Special	Rs.	4882.00	Rupees Four Thousand Eight Hundred Eighty Two Only)	1 No (One Number)	9764.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
45			Supplying and fixing position CI Nahani Trap / Floor Trap of the 110mm x 75mm sizes with best stainless steel gratings of approved brand and quality, fixed over a bed of brick jelly lime concrete 1:2:5 (One part of lime, two part of M.Sand and five part of 40mm gauge brick jelly) and finished with Cement Mortar 1:3 (One Cement, Three M.Sand) including dismantling masonry works wherever found necessary and making good the dismantled portions to the original condition and giving connection to the CI / PVC pipes, etc., complete complying with standard specification. (The Nahani Trap should be got approved by the Executive Engineer before use on works)						
a	4.00	Nos	Nahani Trap of size 110 x 75mm with PVC gratings	Special	Rs.	528.50	Rupees Five Hundred Twenty Eight and Fifty Paise Only	1 No (One Number)	2114.00
46	1.00	Nos	Supplying and fixing PVC ventilating shaft of 110mm dia (having working pressure 4 kg. / sq.cm) with 3 metre height including cost of PVC cylindrical cowl of best approved quality etc., complete complying with standard specifications and as directed by the departmental officers	Special	Rs.	1058.50	Rupees One Thousand Fifty Eight and Fifty Paise Only	1 No (One Number)	1059.00
47			Supplying and fixing in position best quality PVC soil / waste pipes of various dia having 6 kg / sq.cm. pressure BIS mark and providing leak proof joints using PVC adhesives including fixing to the wall with special PVC / MS clamp, teak wood plugs, brass screws, etc., and making connection to all sanitary fittings, dismantling masonry / RCC works wherever found necessary and making the good dismantled portion to the original condition, including testing for any leakages, etc., complete complying with standard specifications. (The PVC pipes should be got approved by the Executive Engineer before use on works). The rate for earth work excavation will be measured and paid separately in the cases where the pipe lines are proposed to laid below ground level						

Sl No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
a	25.00	Rm	75mm dia PVC soil pipe	97 & 102		343.45	Rupees Three Hundred Forty Three and Forty Five Paise Only	1 RM (One Running metre)	8586.00
b	45.00	Rm	110mm dia PVC soil pipe	97 & 102	Rs.	447.65	Rupees Four Hundred Forty Seven and Sixty Five Paise Only	1 RM (One Running metre)	20144.00
48			Supplying and fixing in position PVC specials of the following dia and types of approved quality confirming to BIS and providing leak proof joints including fixing to the walls and giving connection to the PVC soil stacks, dismantling the masonry or RCC works and re-doing the dismantled portion to original condition etc., complete complying with standard specifications. (The PVC specials should be got approved by the Executive Engineer before use on works).						
a			PVC Plain Elbow						
i	3.00	Nos	110mm dia PVC Plain Elbow	97 & 102	Rs.	356.45	Rupees Three Hundred Fifty Six and Forty Five Paise Only	1 No (One Number)	1069.00
ii	3.00	Nos	75mm dia PVC Plain Elbow	97 & 102	Rs.	352.95	Rupees Three Hundred Fifty Two and Ninety Five Paise Only	1 No (One Number)	1059.00
b			PVC Door Elbow						
i	3.00	Nos	110mm dia PVC Door Elbow	97 & 102	Rs.	356.45	Rupees Three Hundred Fifty Six and Forty Five Paise Only	1 No (One Number)	1069.00
ii	3.00	Nos	75mm dia PVC Door Elbow	97 & 102	Rs.	352.95	Rupees Three Hundred Fifty Two and Ninety Five Paise Only	1 No (One Number)	1059.00
c		Nos	PVC Tee						
i	3.00	Nos	110mm dia PVC Tee	97 & 102	Rs.	446.05	Rupees Four Hundred Forty Six and Five Paise Only	1 No (One Number)	1338.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
ii	3.00	Nos	75mm dia PVC Tee	97 & 102	Rs.	386.45	Rupees Three Hundred Eighty Six and Forty Five Paise Only	1 No (One Number)	1159.00
d		Nos	PVC Tee with Single Door						
i	2.00	Nos	110mm dia PVC Tee with Single Door	97 & 102	Rs.	472.65	Rupees Four Hundred Seventy Two and Sixty Five Paise Only	1 No (One Number)	945.00
ii	2.00	Nos	75mm dia PVC Tee with Single Door	97 & 102	Rs.	413.05	Rupees Four Hundred Thirteen and Five Paise Only	1 No (One Number)	826.00
e		Nos	PVC Tee with Double Door						
i	1.00	Nos	110mm dia PVC Tee with Double Door	97 & 102	Rs.	545.35	Rupees Five Hundred Forty Five and Thirty Five Paise Only	1 No (One Number)	545.00
ii	1.00	Nos	75mm dia PVC Tee with Double Door	97 & 102	Rs.	446.05	Rupees Four Hundred Forty Six and Five Paise Only	1 No (One Number)	446.00
f		Nos	PVC Bend						
i	1.00	Nos	110mm dia PVC Bend	97 & 102	Rs.	392.95	Rupees Three Hundred Ninety Two and Ninety Five Paise Only	1 No (One Number)	393.00
ii	1.00	Nos	75mm dia PVC Bend	97 & 102	Rs.	360.05	Rupees Three Hundred Sixty and Five Paise Only	1 No (One Number)	360.00
g		Nos	PVC Door Bend						
i	1.00	Nos	110mm dia PVC Door Bend	97 & 102	Rs.	419.45	Rupees Four Hundred Nineteen and Forty Five Paise Only	1 No (One Number)	419.00
ii	1.00	Nos	75mm dia PVC Door Bend	97 & 102	Rs.	360.05	Rupees Three Hundred Sixty and Five Paise Only	1 No (One Number)	360.00

Sl No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
h		Nos	PVC Y						
i	2.00	Nos	110mm dia PVC Y	97 & 102	Rs.	452.95	Rupees Four Hundred Fifty Two and Ninety Five Paise Only	1 No (One Number)	906.00
ii	2.00	Nos	75mm dia PVC Y	97 & 102	Rs.	392.95	Rupees Three Hundred Ninety Two and Ninety Five Paise Only	1 No (One Number)	786.00
i		Nos	PVC "Y" with Single Door						
i	2.00	Nos	110mm dia PVC "Y" with Single Door	97 & 102	Rs.	479.65	Rupees Four Hundred Seventy Nine and Sixty Five Paise Only	1 No (One Number)	959.00
ii	2.00	Nos	75mm dia PVC "Y" with Single Door	97 & 102	Rs.	413.05	Rupees Four Hundred Thirteen and Five Paise Only	1 No (One Number)	826.00
j		Nos	PVC "Y" with Double Door						
i	1.00	Nos	110mm dia PVC "Y" with Double Door	97 & 102	Rs.	558.25	Rupees Five Hundred Fifty Eight and Twenty Five Paise Only	1 No (One Number)	558.00
ii	1.00	Nos	75mm dia PVC "Y" with Double Door	97 & 102	Rs.	459.25	Rupees Four Hundred Fifty Nine and Twenty Five Paise Only	1 No (One Number)	459.00
n			PVC Cowl						
i	2.00	Nos	110mm dia PVC Cowl	97 & 102	Rs.	234.70	Rupees Two Hundred Thirty Four and Seventy Paise Only	1 No (One Number)	469.00
ii	2.00	Nos	75mm dia PVC Cowl	97 & 102	Rs.	209.20	Rupees Two Hundred Nine and Twenty Paise Only	1 No (One Number)	418.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
49	2.00	Nos	Supplying and fixing in position CP shower rose with CP stop cock arrangement of size 15mm dia inlet and 100mm outlet to the pipe line with necessary cutting, threading and jointing using shellac etc., complete complying with standard specification and as directed by the departmental officers (The CP shower rose should be got approved by the Executive Engineer before use on works).	Special	Rs.	487.50	Rupees Four Hundred Eighty Seven and Fifty Paise Only	1 No (One Number)	975.00
50			Supplying and fixing in position 15mm dia brass CP screw down tap / Pillar tap (heavy duty) of approved make conforming to BIS specifications and quality including cost of shellac, thread, etc., complete complying with standard specification and including cutting and threading wherever necessary. (Taps should be got approved by the Executive Engineer before use on the works)						
a	12.00	Nos	15mm dia CP Screw Down Tap	Special	Rs.	337.65	Rupees Three Hundred Thirty Seven and Sixty Five Paise Only	1 No (One Number)	4052.00
51	2.00	Nos	Supplying and fixing in position Indian make bevelled edge mirror of approved quality and brand PVC / Fibre Glass framed 600 x 450 x 5.5mm thick mirror, shelf type with hard board backing of approved colour fixed with brass screws, rawl plug, etc., complete complying with standard specification. (The mirror should be got approved by the Executive Engineer before use on works)	Special	Rs.	957.50	Rupees Nine Hundred Fifty Seven and Fifty Paise Only	1 No (One Number)	1915.00
52	2.00	Nos	Supplying and fixing approved best quality brass CP towel rail 600mm long and 20mm dia with brackets of same materials including cost of teak wood plugs and CP screws, etc., complete complying with standard specifications. (The towel rail should be got approved by Executive Engineer before use on works).	Special	Rs.	483.55	Rupees Four Hundred Eighty Three and Fifty Five Paise Only	1 No (One Number)	967.00
53	2.00	Nos	Supplying and fixing best approved best quality brass CP soap tray of size 150 x 150mm including cost of teak wood plugs, brass screws, etc., complete complying with standard specifications. (The soap tray should be got approved by Executive Engineer before use on works).	Special	Rs.	296.95	Rupees Two Hundred Ninety Six and Ninety Five Paise Only	1 No (One Number)	594.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
54	3.00	Nos	Supplying and fixing of PVC ready made WATER TANK of 1000 Ltr capacity of best and approved quality with ISI specification and having inlet,outlet, overflow and clearing pipe arrangements and labour charges for fixing in position with all necessary accessories and transporting at site of work etc., complete complying as directed by the departmental officers	Special	Rs.	9600.00	Rupees Nine Thousand Six Hundred Only)	1 No (One Number)	28800.00
55	180.00	Rm	Drilling of 150mm (6") dia vertical bores in hard rock areas to any required depth as directed by the departmental officials. The rate is inclusive of assembling the equipment in the point as selected, drillingbore, labour charges for inserting casing pipe of necessary and also transportation charges for the rig and supporting vehicle to the bore point etc., complete complying with standard specification.	Borewell	Rs.	451.00	Rupees Four Hundred Fifty One Only)	1 RM (One Running metre)	81180.00
56	12.00	Rm	Supplying suitable PVC casing pipe for 6" dia borewell (6kg/cm ²) for 6" dia borewell of best quality with mark(The PVC pipe should be got approved by departmental officers before execution.)(PWD Sr Page 63/b-d)	Borewell	Rs.	549.00	Rupees Five Hundred Forty Nine Only)	1 RM (One Running metre)	6588.00
57	1.00	Nos	Supplying and fixing of suitable PVC endcap (6kg/cm ²)for 6"dia borewell of best quality with mark (The PVC pipe should be got approved by departmental officers before execution.) (PWD Sr Page 67/C-d)	Borewell	Rs.	137.50	Rupees One Hundred Thirty Seven and Fifty Paise Only	1 No (One Number)	138.00
58	175.00	Rm	Supply and fixing of 25mm dia UPVC Column pipe with ISI standard specification and confirming to BIS. UPVC pipe should be got approved by departmental officers before execution	Borewell	Rs.	69.00	Rupees Sixty Nine Only)	1 RM (One Running metre)	12075.00
59	1.00	Set	Supplying and fixing of hydraulically tested 3.00 HP.3 phase Motor with submersible pump set with motor with ISI making as per specification for (75x75) duty condition detailed below. The Motor fitted with the pump should be category suitable for installation in Bore well. The rate including cost of panel board with accessories switch starter and water level gauge (The pump set should be delivered at work site including freight charges etc. complete)	Borewell		54836.00	Rupees Fifty Four Thousand Eight Hundred Thirty Six Only)	1 Set (One Set)	54836.00
60	62.00	Rm	Supply and delivery of 3 core copper cable of 4.00 sq.m 1100V grade PVC insulated PVC sheathed water proof etc.(with excise duty)	Borewell	Rs.	161.00	Rupees One Hundred Sixty One Only)	1 RM (One Running metre)	9982.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
61	30.00	Rm	Supply and erecting of 19mm dia Nylon PVC Rope with approved Quality inside the bore well etc completed.	Borewell	Rs.	61.20	Rupees Sixty One and Twenty Paise Only	1 RM (One Running metre)	1836.00
ELECTRICAL WORKS									
62	36.00	Pt	Wiring with 2x1.5sqmm (22/0.3) PVC insulated unsheathed SC Cu. Conductor of 1100V grade in suitable PVC rigid pipe concealed in wall and ceiling with PVC accessoires with TW switch box and 5A F.T. switch in flush with wall with 3mm thick hylum sheet cover for making good of the concealed portion with suitable colour for PVC concealed light point / fan point (For electronic regulator)	Electrical Std Specification	Rs.	2340.00	Rupees Two Thousand Three Hundred Forty Only)	1 Pt (One Point)	84240.00
63	4.00	Pt	Wiring with 2 x 1.5 sqmm (22 / 0.3) PVC insulated SC unsheathed Copper conductor cable of 1100V grade in suitable PVC rigid pipe concealed in wall and ceiling with PVC accessories in flush with wall with 3mm thick hylum sheet cover with TW switch box and 5A F.T. switch and making good of the concealed portion with suitable Colour for PVC concealed light (6 points Per coil) (For Rooms like Bath, Toilet & Pump room etc.)	Electrical Std Specification	Rs.	1583.00	Rupees One Thousand Five Hundred Eighty Three Only)	1 Pt (One Point)	6332.00
64	15.00	Pt	Wiring with 2x1.5sqmm (22/0.3) PVC insulated SC unsheathed Cu. Conductor of 1100 V grade in suitable PVC rigid pipe concealed in wall and ceiling with PVC accessories, in flush with wall, with 150mm x 100mm x 113mm TW switch box with 3 mm thick Hylem sheet cover for 5 A 3 pin non inter locking CS Plug with continuous earth wire connection of 14 SWG TC wire and making good of the concealed portion with suitable colour for concealed PVC plug point.	Electrical Std Specification	Rs.	1401.00	Rupees One Thousand Four Hundred One Only)	1 Pt (One Point)	21015.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
65	9.00	Pt	Wiring with 2x4 sqmm(56/0.3) PVC insulated SC unsheathed Cu.Conductor cable of 1100V grade in suitable PVC rigid pipe concealed in wall and ceiling with PVC accessories, in flush with wall, with 150mm x 100mm x 113mm TW switch box with 3mm thick hylem sheet for 15 A 3 pin non inter locking CS plug with continuous earth wire connection of 14 SWG TC wire , and making good of the concealed portion, with suitable colour for concealed power plug point	Electrical Std Specification	Rs.	1765.00	Rupees One Thousand Seven Hundred Sixty Five Only)	1 Pt (One Point)	15885.00
66	30.00	Rm	Supply and run of 4 of 4sqmm (56/0.3) PVC insulated SC unsheathed Cu.Conductor of 1100V Grade in suitable PVC rigid pipe concealed in wall and ceiling with continuous earth wire connection of 14 SWG TC wire and making good of the concealed portion with suitable colour	Electrical Std Specification	Rs.	335.00	Rupees Three Hundred Thirty Five Only)	1 RM (One Running metre)	10050.00
67	30.00	Rm	Supply and run of 4 x 6 sq.mm (84/0.3) PVC insulated SC unsheathed Cu.Conductor of 1100V on 7/20 GI bearer wire for service connection mains	Electrical Std Specification	Rs.	286.00	Rupees Two Hundred Eighty Six Only)	1 RM (One Running metre)	8580.00
68	3.00	Rm	Supply and run of 4 x 6 sq.mm (84/0.3) PVC insulated SC unsheathed Cu.Conductor of 1100V grade in 32mm dia GI pipe (Class 'B') suitably bent at both ends with necessary angle iron up right and end supports for mains	Electrical Std Specification	Rs.	765.00	Rupees Seven Hundred Sixty Five Only)	1 RM (One Running metre)	2295.00
69	4.00	Nos	Supply and fixing of WT bulk head fitting with guard (Phillips / Bajaj / Crompton / K. Lite) suitable for 11W CFL lamp with CFL	Electrical Std Specification	Rs.	574.00	Rupees Five Hundred Seventy Four Only)	1 No (One Number)	2296.00
70	21.00	Nos	Supply and fixing of single box type 4'40 W flu fitting complete with copper choke and condensor with TW round blocks on wall or ceiling with flu tube with PVC unsheathed Copper leads from terminals to the fitting.	Electrical Std Specification	Rs.	604.00	Rupees Six Hundred Four Only)	1 No (One Number)	12684.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees
1	2	3	4	5	6	7	8	9	10
71	4.00	Nos	Supply and fixing of 4'40 W twin street light flu. fitting complete With copper choke and condensor with 19mm dia GI pipe (Class 'B') with 1 No. 19mm GI Bend complete on the existing post / wall With 16 A aerial fuse unit on MS plate with PVC unsheathed Cu. leads, with MS clarnps and aluminium painting with Flu. Tubes	Electrical Std Specification	Rs.	2016.00	Rupees Two Thousand Sixteen Only)	1 No (One Number)	8064.00
72	11.00	Nos	Supply and fixing of 1200 mm (48") AC ceiling fan complete with stepped electronic 300W regulator with 300mm down rod on the existing clamp.	Electrical Std Specification	Rs.	2074.00	Rupees Two Thousand Seventy Four Only)	1 No (One Number)	22814.00
73	1.00	Nos	Supply and fixing of 450 mm (18") sweep (light duty) AC exhaust fan complete with necessary wall opening and making good of the wall	Electrical Std Specification	Rs.	2753.00	Rupees Two Thousand Seven Hundred Fifty Three Only)	1 No (One Number)	2753.00
74	1.00	Nos	Supply and fixing of TNEB meter Board suitable for 32A Three Phase service connection with 3 Nos. 32A Fuse unit (500V) 32A neutral link and earth link (1" x 1/8" Copper flat) on TW plank of size 600mm x 450mm x 19mm with supporting TW reepers of 1" thick an either side with painting with suitable bolt and nuts for fixing the TW plank on wall with earth connection and inter connection with 7/20 PVC insulated copper wire from EB meter to fuse unit.	Electrical Std Specification	Rs.	1872.00	Rupees One Thousand Eight Hundred Seventy Two Only)	1 No (One Number)	1872.00
75	2.00	Nos	Supply and fixing of 3 Phase 32A aerial fuse unit for 3 Nos 32A fuse units (500V) on suitable MS sheet covered with 6mm thick hylem sheet on suitable angle iron work the tapping pole with necessary clamps.	Electrical Std Specification	Rs.	998.00	Rupees Nine Hundred Ninety Eight Only)	1 No (One Number)	1996.00
76	3.00	Nos	Supply and fixing of 4way SP DB of 16A / Way with 16A DP switch with metal clad of 500 V (Side Handle) F&N on suitable angle iron frame work with trunking box MS cable entry box with earth connection.	Electrical Std Specification		2468.00	Rupees Two Thousand Four Hundred Sixty Eight Only)	1 No (One Number)	7404.00

SI No.	Approximate Qty.	Unit	Description of Work	TNBP No	Rate (in words and figures)			Unit of Calculation	Amount in Rupees	
1	2	3	4	5	6	7	8	9	10	
77	1.00	Nos	Supply and fixing of 3 Phase 4 wire ICDB of 16 A per way, with 32 A TPN MC switch with suitable trunking box MS cable entry boxes and internal connection on suitable angle, iron frame work with earth connection only.	Electrical Std Specification		5638.00	Rupees Five Thousand Six Hundred Thirty Eight Only)	1 No (One Number)	5638.00	
78	1.00	Pt	Earthing as per P.W.D standard with an earth electrode of 2 Mtr. Class 'B' GI pipe of dia not less than 32mm complete with necessary masonry work.	Electrical Std Specification		2167.00	Rupees Two Thousand One Hundred Sixty Seven Only)	1 Pt (One Point)	2167.00	
78 (seventy eight items only)			Total (Rupees Forty Four Lakh Fifty Eight Thousand Nine Hundred And Thirty Eight Only)						4458938.00	
GST = 12 %									535073.00	
GRAND TOTAL (Rupees Forty Nine Lakh Ninety Four Thousand And Eleven Only)									4994011.00	

SCHEDULE - B						
LIST OF DRAWINGS			SUPPLEMENTAL LIST			
Note All drawings to be signed by the Contractor as well as the Officer entering into the contract			As referred to in the specifications (including the preliminary specification of the Madras Detailed standard specifications).			
Sl. No.	Drawing Number	Description	Sl. No.	Drawing Number	Description	Date on which the drawing was supplied
1	2	3	4	5	6	7
1	CONSTRUCTION OF COMMUNITY HALL TO MYLAMBADI PANCHAYAT (36 HAMLET) AT BHAVANI TALUK IN ERODE DISTRICT.	1.COMMUNITY HALL				

Contractor

General Manager (Tech),
TAHDCO, Chennai