

TENDER SCHEDULE TYPE "A"

Name of Work: Rejuvenation of Vandal Kaliyamman kovil kulam in S.F. No: 305 at Thalanayar Town Panchayat in Nagapattinam District.

Estimate Amount Rs. 4920000.00

Contract Amount Rs.

Name of Scheme:KNMT - 2022-2023

Sl. No	Probable Qty.		Description of Work	TNDS S or MORT	Rate in Rupees		Units	Amount in Rupees
					Figures	Words		
1	124.94	M ³	Earth work excavation for foundation in Hard stiff clay, stiff black cotton, hard red earth, shales murram, gravel, stoney earth and earth mixed with small size boulders SS.20B and Sand, silt or other loose soil, wet sand, or silt not under water, light black cotton soil, sandy loam ordinary soil and to full depth as may be directed except in hardrock requiring blasting inclusive of shoring shuttering, and baling out water wherever necessary refilling the sides of foundation with excavated soil other than sand in layers of 15cm thick well rammed and completed depositing the surplus excavated soil with in the compound in places shown by the departmental officers with initial lead and lifts and cleaning and levelling the site etc., complete as per TNSS 23 & 24, V, VI (S2), VII, 9, 10, complete - SS 20A				1M ³ (One Cubic Metre)	
2	24.84	M ³	Cement Concrete of mix 1 : 4 : 8 (One Cement four sand eight aggregates) using 40mm gauge hard broken including cost conveyance of all materials to site including formwork and centering labour charges, transporting and placing in position including shoring, strutting, forming protective bunds, cofferdams baling out of water labour for mixing compacting, finishing and curing, working at depths, tools and plants and incidental charges such as sheeting, shoring and bracing and their subsequent removal etc., complete as per standard specification. TNDSS NO: 28 V, VI (S2) V, VI (S5A) VII				1M ³ (One Cubic Metre)	

No. of Corrections:

No. of overwritings:

Signature of Contractor

3	218.34	M ³	Supplying and Filling of U/S Gravel from approved quarry in Layer of not more than 15cm thick including watering with all layers and consolidation complying with standard specification including cost and conveyance of sand at site and all labour charges and all other incidental charges etc., complete as per Standard Specification.				1M ³ (One Cubic Metre)	
4	1425.60	M ²	Suppling and Laying of manufacturing PCC Cement Blocks of Size 20x20x15cm and Dry packing them in apron or revetments and the cost Shall inclusive all materials and labour Charges etc.Complete				1M ² (One Square Metre)	
5	533.46	M ²	Supplying and erecting steel centering including necessary supports for plain surfaces for Reinforced Cement Concrete works such as Coloumn footing, Coloumn pedestals, plith beams, grade beams, staircase steps, etc which requires only nominal strutting using mild steel sheet of size 90mm x 60mm and 10Bg stiffened with welded mild steel angles of size 25mm x 25mm x 3mm for boarding, laid over silver oak joists of size 10cm x 6.5cm spaced at about 75cm centre to centre or at suitable intervals etc complete in all floors Complying with standard Specification(TNSS NO or NBC No 30(S) 86 86 A V, VI(S3)VII				1M ² (One Square Metre)	
6	92.15	M ³	Vibrated Plain Cement Concrete 1:2:4 (one cement two fine aggregates and four coarse aggregates) using 20mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges and all incidental charges such as water providing etc., complete as per standard specification 30 V, VI (S5) VII & 13				1M ³ (One Cubic Metre)	
7	18.00	M ²	Providing granolithic floor finish of 25mm thickness with plain cement concrete 1:2:4 (One Cement, Two crushed sand (M-Sand) and Four aggregate) using 10 to 12mm gauge hard broken stone jelly including laying, finishing and the top rubbed smooth with power trowl, thread lining, curing etc. complete complying with standard specification and as directed by the departmental officers. (The rate is inclusive of necessary planking for panelling wherever necessary and as directed by the departmental officers)				1M ² (One Square Metre)	

No. of Corrections:

No. of overwritings:

Signature of Contractor

8	243.00	M ²	Providing fencing with chain link diamond mesh 50mm x 50mm size made of 10 swg GI wire,including the cost of G.I binding wire and top of the mesh linked with 10 swg GI wire etc., completed-. 10m2.(consider 30m x 1.80m)				1M ² (One Square Metre)	
9	94.50	RM	Supply and Delivery of 32mm G.I Pipes Medium				1RM (One Running Metre)	

Note:

(1) Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the Other rates and prices in the Bill of /Quantity (refer: ITB clause 13.2 and GCC Clause 43.3

(2) Unit rates and prices shall be quoted by the bidder in Indian Rupee (ITB Clause 14.1)

(3) Where there is a discrepancy between the rate in figures and words, the rates in words will govern (ITB Clause 27s.1(a))

(4) Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity, the unit rate quoted shall govern (ITB Clause 27.1(b)).

Tender Schedule approved for 01 to 09 items only

No. of Corrections:

No. of overwritings:

Signature of Contractor