

SRIPERUMBUDUR TOWN PANCHAYAT

Online

NAME OF WORK: Providing new pipe line in Tambaram Road, Karuku Street, NGO colony, paanchalpattu, Iular kudiyrupu in Sriperumbudur town panchayat, Kancheepuram District

Estimate Amount : 1400000/-

Issued to :

Tender Schedule Cost Rs. /- remitted in Challan No. dated

Time for completion of work :

E.M.D Rs

Last Date for Tender upto **3.00** P.M. on

Tender Opening Time **3.30** P.M. on

SCHEDULE -A

Schedule of rates approximate Quantities

- a) The quantities here given those upon the lump sum tender cost of work is based but they are subject to alternations omissions deductions as provided for in the conditions of this contract and do not shown actual quantities of work top done to unit rate
b) It is to be expressal immderstood that rent works is to be taken net (not withstanding any custom or practice to the contrary) according to the actual quantities in Balance finished according to the drawings or as may be provided from time to time by t

SI No.	Quantity		Description	TNBPR NO	Rates in words and figures	Unit in words figures	Amount in figures
1			Supply delivery of unplasticised 90mm PVC 6ksc rigide pipes for portable water supply as per IS 4985/2000 and as amended from time to time with marking of various sizes for delivery anywhere in Kancheepuram District with necessary couplers or bell ended pipes as specified in ISI and required quantity of solvent cement having the following working pressure including loading, unloading, freight, stacking, and transit insurance charges etc., complete				
a	700.00	Rm	90mm PVC				
b	1100.00	Rm	110 mm PVC				
c	900.00	Rm	140mm PVC				

No of corrections :

No of overwriting :

Signature of Contractor

Sl No.	Quantity		Description	TNBPR NO	Rates in words and figures	Unit in words figures	Amount in figures
2	1620.00	M³	Earth work excavation for foundation in hard stiff clay, stiff black cotton, hard red earth, shales, murrum, gravel, stoney earth and earth mixed with small size boulders, sand, silt or other loose soil and to full depth as may be directed except in hardrock requiring blasting inclusive of shoring shuttering and bailing out water wherever necessary refilling the side of foundation with excavated soil other than sand in layer of 15cm thick well rammed and completed depositing the surplus excavated soil with in the compound in places shown by the departmental officers with initial lead and lifts and cleaning, levelling, the site etc,,, complete as per S 20B for pipe laying works				
3	0.00	M	Lowering 75mm Dia PVC rigid/ HDPE pipes and specials to trench and laying to proper grade and alignment, jointing with PVC couplers with cement paste. Testing of M.S. / C.I. / D.I / P.V.C. / H.D.P.E / pipes with hydraulic testing equipment by filling with water (including cost of water @ Rs. 60/KL) and testing to recommended pressure in convenient stretches and attending the bursts if any occurred during the test, excluding the cost of pipes but including other incidental and operational charges etc., complete for the following diametres of pipes.				
a	1800.00	rm	90-110				
b	900.00	rm	140mm Dia Pipe				
4	1296.00	M³	Refilling with excavated earth other than sand complying with standard specifications for filling in foundation and basement				
5	0.00	0.00	Specials and valve arrangements				

No of corrections :

No of overwriting :

Signature of Contractor