

# KALIYAKKAVILAI TOWN PANCHAYAT

KANNIYAKUMARI DISTRICT - NAGERCOIL ZONE

## \_ TENDER SCHEDULE \_

Name of Work : Improvements and construction of retaining wall at Kandarai to Sayarakkalvilai bridge in Kaliyakkavilai Town Panchayat.

Scheme Name : Namakku Naamey 22 - 23

Estimate amount : ` 19,50,000/-

Tender Date :

Schedule issued to M/s:

Closing Time :

Schedule cost `:

Opening Time :

Remitted vide chellan No:

EMD Rupees (`) :

Date:

THE EXECUTIVE OFFICER  
KALIYAKKAVILAI TOWN PANCHAYAT

Sl. No.	Quantity	Description of work	Unit	TNDSS & MORTH No.	Rate in	
					Figures	Words
01.	100.00 m <sup>3</sup>	Earth work excavation for foundation in all kinds of soils and sub soils to full depth as directed by the departmental officers except hard rock inclusive of shoring strutting and balling out water wherever necessary and refilling the sides of foundation with excavated earth in layers of 15 cm thick well rammed and consolidated and depositing the surplus earth with in the compound in places shown by the departmental officers with initial lead of 10 meters and initial lift of 2 meters including cost of all labour charges etc., complete as per standard specification SS 20B. TNDSS No:23&24	1m <sup>3</sup> (one cubic metre)			

Sl. No.	Quantity	Description of work	Unit	TNDSS & MORTH No.	Rate in	
					— - - Figures	- - - Words
02.	17.00 m <sup>3</sup>	Cement concrete of mix 1:4:8 (one part of cement four part of sand and eight part of aggregates) using 40 mm gauge machine broken granite stone jelly for foundation including de watering if found necessary and laid in layers of not more than 15 cm thick well rammed and consolidated etc complying with standard specification. TNDSS No:28	1m <sup>3</sup> (one cubic metre)			
03.	494.00 m <sup>2</sup>	Supplying and erecting shuttering including necessary supports plain surfaces in foundation and basement in all floors for reinforcement cement concrete works such as pedestal bed blocks, staircase steps, RCC column, grade beams, plinth beam etc using mild steel sheets of size 90x60 cm and BG10 gauge stiffened with welded mild steel angles of size 25x25x3 mm for boarding laid over silver oak country wood joists of size 10x6.5 cm spaced at about 90 cm center to center and supported with casurina props of 10 to 13 cm Ø spaced at 75 cm center to center at suitable intervals etc. complete complying with standard specification. TNDSS No:30&36	1m <sup>2</sup> (one square metre)			

Sl. No.	Quantity	Description of work	Unit	TNDSS & MORTH No.	Rate in	
					— - - Figures	- - - Words
04.	274.00 m <sup>3</sup>	Cement concrete of mix 1:3:6 (one part of cement three part of sand and six part of aggregates) using 40 mm gauge machine broken granite stone jelly for foundation including de watering if found necessary and laid in layers of not more than 15 cm thick well rammed and consolidated etc complying with standard specification. TNDSS No:24	1m <sup>3</sup> (one cubic metre)			
05.	237.25 m <sup>2</sup>	Plastering walls with cement mortar 1:4 (one part of cement four part of sand) 12 mm thick including all cost and conveyance of all materials and all labour charges etc. complete as per standard specification. TNDSS No:61	1m <sup>2</sup> (one square metre)			

(Approved in Item No. 01 to 05 only)