

## Item Rate BoQ

**Tender Inviting Authority: Commissioner, Thoothukudi City Municipal Corporation**

**Name of Work : Providing of Walking Track Arrangement at SV kulam in Thoothukudi City Municipal Corporation.**

**File No: E1/04737/2021**

Name of the Bidder/ Bidding Firm /							
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )</div>							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Earth work excavation for foundation in Hard stiff clay, stiff black cotton, hard red earth, shales murrum, gravel,stoney earth and earth mixed with small size boulders SS.20B and Sand, silt or other loose soil, wet sand,or silt not under water, light black cotton soil, sandy loam ordinary soil and to full depth as may be directed except in hardrock requiring blasting inclusive of shoring shuttering and baling out water and cleaning and levelling the site etc., complete	392.00	1M3 (One Cubic Meter)			0.00	INR Zero Only
2	Collection, supply and filling of Well gravel from approved quarry including cost and conveyance and stacking at road side to departmental gauge for taking pre measurement etc., complete as per specification.	914.00	1M3 (One Cubic Meter)			0.00	INR Zero Only

3	Plain Cement Concrete 1:4:8 (one cement four fine aggregates and eight coarse aggregates) using 40mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges and all incidental charges such as water providing etc., complete as per standard specification	145.00	1M3 (One Cubic Meter)			0.00	INR Zero Only
4	Centering for soffits of RCC slabs of plane surface like lintels, beams ,etc.,including strutting 3m high using mild steel sheets of size 90cm X 60cm X and B.G 10 stiffened with M.S angles of size 25mm X 25mm X 3mm laid over silver Oak (C.W) joists of size 10cm X 6.5cm (spaced at about 90cm c/c )and supported dy casurina props of 10cm to 13cm dia (spaced of 75cm C/C) complying with standard specification and directed	2610.00	1M2 (One Square Meter)			0.00	INR Zero Only
5	Plain Cement Concrete 1:2:4 (one cement, two fine aggregates and four coarse aggregates) using 20mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges etc., complete as per standard specification	543.00	1M3 (One Cubic Meter)			0.00	INR Zero Only
6	Supply and fixing of M.S Grills with Doors and Windows with one coat of Red oxide with Primer including all costs such as welding,grinding and fabrication charges, cost and conveyance of all materials to site etc,complete as per standard specification.	46985.00	1 Kg (One Kilogram)			0.00	INR Zero Only
7	Brick work in CM 1:5 (one cement & five sand) using II Class Country bricks of size 8 3/4"X43/8"X 2 3/4" including finishing, curing, etc., complete complying with standard specification	3.50	1M3 (One Cubic Meter)			0.00	INR Zero Only
8	Plastering with cement mortar (1:5) 12mm ,thick in all floors including cost and conveyance of all materilas to site and labour charges etc,complete as per standard specifications	170.00	1M2 (One Square Meter)			0.00	INR Zero Only

9	White washing two coats with freshly burnt shell lime white in colour in all floors including cost of lime and other materials brushes scaffolding charges etc.complete complying with standard specification and as directed.	1576.00	1M2 (One Square Meter)			0.00	INR Zero Only
10	Painting Two Coat with Ready Mixed Enamel Paint over the new Iron works of approved quality and colour with priming coat including the cost all materials etc.,complete, in all floors.	3131.00	1M2 (One Square Meter)			0.00	INR Zero Only
11	Supplying and laying Rubberised interlocking Paver block M35 grade Providing and laying of 63mm thick high strength type conforming IS 15658-2006 of rubberized interlocking paver lock in size of minimum compressive strength of 35 N/mm2 in uniform shape of approved make to be laid in flurring bone pattern with stone dust cushion below the uniform shap of approved non skitting surface in the top and the rate including levelling the base preparation of pavers as sub base, stone dust cushion 100mm thick laying out of pavement cut the pieces to fix the edge vibring the pavers,sweeping tranporting loading unloading of laying paver block as per standard specification.	8995.00	1M2 (One Square Meter)			0.00	INR Zero Only
<b>Total in Figures</b>						<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>		<b>INR Zero Only</b>					