

SCHEDULE - A

NAME OF WORK:Construction of Bridge and Flood Protection Wall at tile end of Kugalur Feeder Channel in Gobichettipalayam Taluk of Erode District

Item No.	Approximate Quantity in figures & Words	Description of Work	TNBP Specification No.	Rate in figures & in Words (Rs.)	Unit of measurement in figures & in words	Amount (Rs.)
1	830 M ³ (Eight hundred and thirty cubic metre only)	Earth excavation for foundation and depositing on bank with an initial lead of 10m and initial lift of 2m in sand, silt or other loose soil, wet sand or silt not under water light black cotton soil, sandy loam and ordinary soil including excavated earth, hard stiff clay, stiff black cotton, hard red earth, shales, murram, gravel, stoney earth and earth mixed with small size boulders(SS20B), soft disintegrated rock, laterite, soft rock or kankar not requiring blasting complete complying with standard specifications and as directed by the departmental officers	Sec- III SS-20B		1 M ³ (One cubic metre only)	
2	200 M ³ (Two hundred cubic metre only)	Providing and laying Plain Cement concrete of M10 grade (Design Mix) using 40mm HBGS jelly (well graded) conforming to IS specified grading (to produce concrete of the specified grading and characteristic strength of 10N/mm ² at 28 days) and mixing the ingredients by mixer machine including dewatering by bailing/pumping wherever necessary laying the concrete in layers and in bays with all leads and lifts, compacting and finishing the surface, watering, curing etc., complete complying with standard specifications and as directed by the departmental officers.	SS. 28 & 30		1 M ³ (One cubic metre only)	

No of over writings:

Contractor

No of corrections:

No of omissions:

Superintending Engineer

Item No.	Approximate Quantity in figures & Words	Description of Work	TNBP Specification No.	Rate in figures & in Words (Rs.)	Unit of measurement in figures & in words	Amount (Rs.)
3	1347 M ³ (One thousand three hundred and forty seven cubic metre only)	Providing and Laying in position, Plain Cement Concrete of M 15 grade (Design Mix) with well graded aggregates and the maximum nominal size of HBGS jelly of 40mm and down graded (60% of 40 mm and 40% of 20mm) confirming to IS specified grading and mixing by mixer machine (to produce concrete of the specified characteristic strength of 15N/mm2 at 28 days) including dewatering by bailing/ pumping wherever necessary laying the concrete in layers and in bays with all leads and lifts, vibrating, compacting, and finishing the surface, watering, curing, for various depth and height below and above ground level so as to attain the profile and strength specified in the drawings as per the direction of the departmental officers and complying with standard specification.	SS. 28 & 30		1 M ³ (One cubic metre only)	
4	80 M ³ (Eighty cubic metre only)	Providing and Laying in position, Plain Cement concrete M 25 grade (Design Mix) with well graded aggregates and the maximum nominal size of HBGS jelly of 20mm and down graded to IS specified grading and mixing by mixer machine (to produce concrete of the specified characteristic strength of 25 N/mm2 at 28 days) including dewatering by bailing/pumping wherever necessary laying the concrete in layers and in bays with all leads and lifts, vibrating, compacting and finishing the surface watering, curing for various depth and height below and above ground level so as to attain the profile and strength specified in the drawings as per the direction of the departmental officers and complying with standard specification.	SS. 28 & 30		1 M ³ (One cubic metre only)	

No of over writings:

Contractor

No of corrections:

No of omissions:

Superintending Engineer

Item No.	Approximate Quantity in figures & Words	Description of Work	TNBP Specification No.	Rate in figures & in Words (Rs.)	Unit of measurement in figures & in words	Amount (Rs.)
5	76 M ³ (Seventy six cubic metre only)	Providing and Laying in position, Plain Cement concrete M 15 grade (Design Mix) with well graded aggregates and the maximum nominal size of HBGS jelly of 20mm and down graded to IS specified grading and mixing by mixer machine (to produce concrete of the specified characteristic strength of 15 N/mm ² at 28 days) including dewatering by bailing/pumping wherever necessary laying the concrete in layers and in bays with all leads and lifts, vibrating, compacting and finishing the surface watering, curing for various depth and height below and above ground level so as to attain the profile and strength specified in the drawings as per the direction of the departmental officers and complying with standard specification.	SS. 28 & 30		1 M ³ (One cubic metre only)	
6	78 M ³ (Seventy eight cubic metre only)	Providing and laying in position, Standardised Reinforced Cement Concrete Mix M-30 Grade in accordance with IS:456-2000,using 20mm and down graded hard broken granite stone jelly for all RCC items of works with minimum cement content of 400 kg/m ³ and maximum water cement ratio of 0.45, including admixture (plasticiser / super plasticiser) in recommended proportions as per IS:9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability with about (5.0 cu.m) 7730 kg of 20mm machine crushed stone jelly and with about (3.3 cu.m) 5156kg. of 10-12mm machine crushed stone jelly and with about (4.79 cu.m) 7670kg of M.sand, but excluding cost of reinforcement grill and fabricating charges, centering and shuttering and also including laying, vibrating with mechanical vibrators,finishing,curing, etc., complete complying with standard specification and as directed by the departmental officers. The coarse and fine aggregates to be used should comply with the requirement of IS standards.(No separate payment will be made by the Department for the excess usage of materials)	SS.30		1 M ³ (One cubic metre only)	

No of over writings:

Contractor

No of corrections:

No of omissions:

Superintending Engineer

Item No.	Approximate Quantity in figures & Words	Description of Work	TNBP Specification No.	Rate in figures & in Words (Rs.)	Unit of measurement in figures & in words	Amount (Rs.)
7	60 RM (Sixty running metre only)	Supplying and fixing in position of seepage pipes having working pressure of 6 Kg/cm ² of 63mm dia PVC pipe of required lengths for retaining wall including cost and conveyance of all materials to the work site complete complying with standard specifications and as directed by the departmental officers.	Special		1 RM (One running metre only)	
8	9.09 M ² (Nine point zero nine square metre only)	Providing and fixing KRAFT PAPER for full width of seating of deck slab and including cost and conveyance to work site, labour for fixing the same in correct position and all other incidental charges etc., complete complying with standard specification and as directed by the departmental officers.	Special		1 M ² (One square metre only)	
9	9.30 M ² (Nine point three zero square metre only)	Supplying and fixing 300mm wide PVC EXPANSION JOINT in the 20mm expansion gap provided in between decks over piers and in between deck and dirt wall over abutment as shown in the drawing including cost and conveyance of expansion joints including shalimar pad and joint sealant etc., complete complying with standard specification and as directed by the Departmental officers. in between deck slabs over abutment and pier as shown in the drawing including cost and conveyance of expansion joints including shalimar pad and joint sealant etc, complete	Special		1 M ² (One square metre only)	

No of over writings:

Contractor

No of corrections:

No of omissions:

Superintending Engineer

Item No.	Approximate Quantity in figures & Words	Description of Work	TNBP Specification No.	Rate in figures & in Words (Rs.)	Unit of measurement in figures & in words	Amount (Rs.)
10	71 Qtl (Seventy one quintal only)	Supplying and fabrication of steel required for all RCC works involved in the schedule including cost of steel , cost of fabrication, labour charges for cleaning the rods straightening, cutting, bending, tying grills including over lapping to the required length wherever necessary and placing reinforcement in position as specified in the drawing including cost of binding wire provision for space bars, cover blocks and all other incidental charges etc., complete complying with standard specification and as directed by the departmental officers	SS. 86A		1 Qtl (one quintal only)	
11	98.01 M ² (Ninety eight point zero one square metre only)	Providing and Laying in position, Plain Cement concrete M 30 grade (Design Mix) for wearing coat 75 mm thick with well graded aggregates and the maximum nominal size of coarse aggregate of 20mm and down graded to IS specified grading and mixing by mixer machine (to produce concrete of the specified characteristic strength of 30 N/mm ² at 28 days) laying the concrete in layers and in bays with all leads and lifts, vibrating, compacting and finishing the surface watering, curing and strength specified in the drawings as per the direction of the departmental officers and complying with standard specification.	SS. 28 & 30		1 M ² (One square metre only)	

No of over writings:

Contractor

No of corrections:

No of omissions:

Superintending Engineer

Item No.	Approximate Quantity in figures & Words	Description of Work	TNBP Specification No.	Rate in figures & in Words (Rs.)	Unit of measurement in figures & in words	Amount (Rs.)
12	4 Nos (Four numbers only)	Supplying and fixing GI DRAINAGE SPOUTS 100mm dia as per GOI drawing SD/205 with grating arrangements at top as shown in the drawing and 100mm dia drainage spout projecting atleast 300mm beyond the bottom of deckslab as shown in the drawing, including cost and conveyance of Galvanised iron pipes and flats and fixing them in position, etc., complete as per cl 2705 of MORT&H specification and as directed by the departmental officers	Special		1 No (One number only)	
13		Providing steel centering for cement concrete block, column, footing, pedestal, plinthbeam, grade beam etc., which require nominal strutting etc, using MS sheets 10 gauge thick of size 90 x 60 cm stiffened with MS angle of size 25mm x 25mm x 3 mm laid over silver oak joists of size 10 cm x 6.5 cm spaced at 90 cm c/c duly supported and removing the strutting after specified period without damaging the concrete laid complete complying with standard specification and as directed by the departmental officers. Scaffolding and centering charges for the structural components is including the cost and conveyance of all material to the site including all labour charges and incidental charges etc., complete complying with standard specification and as directed by the departmental officers				
	470 M ² (Four hundred and seventy square metre only)	Below sill	SS 30 & 86.A		1 M ² (One square metre only)	

No of over writings:

Contractor

No of corrections:

No of omissions:

Superintending Engineer

Item No.	Approximate Quantity in figures & Words	Description of Work	TNBP Specification No.	Rate in figures & in Words (Rs.)	Unit of measurement in figures & in words	Amount (Rs.)
14		Supplying and erecting centering for sides and soffits including necessary supports and strutting upto 3.29m height for vertical/sloped surface as detailed below with all cross bracings using mild steel sheets 10 gauge thick of size 90cm x 60cm stiffened with welded mild steel angle of size (25x25x3)mm laid over silver oak joists of size 10x6.5cm spaced about 90cm c/c and supported by casurina props of 10 cm to 13cm dia spaced at 75 cm c/c and removing the centering and shuttering after specified period without damaging the concrete laid, complete complying with standard specification and as directed by the departmental officers.Scaffolding and centering charges for the structural components is including the cost and conveyance of all material to the site including all labour charges and incidental charges etc., complete complying with standard specification and as directed by the departmental officers				
	1605 M ² (One thousand sixhundred and five square metre only)	Above sill	SS 30 & 86.A		1 M ² (One square metre only)	
				Total	Rs.	
				Add 12% of GST	Rs.	
		Total Value of Civil work including GST			Rs.	

No of over writings:

Contractor

No of corrections:

No of omissions:

Total Number of items : 14 (Fourteen only)

Superintending Engineer, WRD,
Bhavani Basin Circle, Erode -11

Item No.	Approximate Quantity in figures & Words	Description of Work	TNBP Specification No.	Rate in figures & in Words (Rs.)	Unit of measurement in figures & in words	Amount (Rs.)
----------	---	---------------------	------------------------	----------------------------------	---	--------------