

" TENDER SCHEDULE "
HARUR TOWN PANCHAYAT
SCHEDULE - A
Schedule of rates and approximate quantities

a) The quantities here given are those upon which the estimate cost of the work is based but they are subject to alterations, commissions, deduction or additional as provided for in the conditions of this contract and do not necessarily show the actual quantities of work to be done. The unit rates notes below are those government payment for extra or deductions read with the Town Panchayat councils adaptation form and other conditions or specification of this contract and subject to the accepted tender percentage either below, above or at estimate rates as defined in the tender and as shown at the end of Schedule "A"

b) It is expressly understood that measured work is to be taken net-not withstanding any custom to practice to the contrary according to actual quantities when in place and finished according to the drawing or as may be ordered from time by the Assistant Executive Engineer at the cost calculated by measurement or weight at the respective prices with out any additional charge for any necessary or contingent works connected here with. The rates quoted are for works In-SITE and completed in every respect.

15th Finance Commission 2021-22(Phase I Tied Grant)

Name work : Extensition of Pipeline at ward no.4 Theerthamalai road muniyappan kovil to Maveripatti in Harur Town Panchayat,

Estimate Amount : Rs. 17.00 Lakh

Issued Thiru :

Chalan no.

Dt.

Executive Officer
Harur Town Panchayat
Dharmapuri District

Sl. No	Qty		Description of item	M.D.S.S No	Per	Rate in		Remarks
						Figure	Words	
1			Earth work excavation and depositing on bank with initial lead of 10 m and lift of 2 M in narrow trenches for laying of pipes for water supply and sewerage works in the following type of soils as directed by Departmental officers such as Hard stiff clay, stiff black cotton, hard red earth, shales, murram gravel, stoney earth and earth mixed with small size boulders and hard gravelly soil. One cubic metre		0.00			
	930.00	m	110mm Dia HDPE Pipe PN 8		m			

Sl. No	Qty		Description of item	M.D.S.S No	Per	Rate in		Remarks
						Figure	Words	
2			Supplying of DI Pressure pipes of 90mm PVC 4KSC pipe as per IS 8329/2000 excluding Excise Duty and VAT at Site		0.00			
	160.00	M	160mm Dia HDPE Pipe PN 8		M			
	2250.00	m	110mm Dia HDPE Pipe PN 8		m			
3			Conveying and Lowering 110mm and 160mm HDPE pipe to trench and Lowering in to the trenches, laying to proper grade and alignment including conveyance of water from 1KM lead for filling during testing		0.00			
	2410.00	mt	110mm Dia HDPE Pipe PN 8		mt			
4			Supplying of 100mm and 150mm dia CI D/F Sluice valve with Cap / Wheel as per IS 14846/2000 PN 1.0 with ISI mark excluding Excise Duty and VAT		0.00			
	1.00	M	100mm CI D/F Sluice Valve		M			
	4.00	M	150mm CI D/F Sluice Valve		M			
5	3.00	No	Supplying of 100 mm dia CI Double air valve as per G & K Catalogue excluding Excise Duty and VAT		No			
6	3.00	No	Supplying of 100mm dia D/F Non return Valve CI single door Conforming to IS 5312 to be fixed after water metre flow recorder on pumping main near pump house with dash pot arrangements for 90% fast closing & 10% slow closing.		No			

Sl. No	Qty		Description of item	M.D.S.S No	Per	Rate in		Remarks
						Figure	Words	
7	930.00	M3	Refilling in basement with excavated earth in layers of not more than 15cm thick well rammed and consolidated etc., complete		M3			

(Schedule item 1 to 7 Only)

Signanute of the Contrector