



HINDU RELIGIOUS & CHARITABLE ENDOWMENT DEPARTMENT

**Arulmigu Kailasanathar swamy Temple at
Valaramanickam village, Thirumayam Taluk,
Pudukkottai District.**

TENDER SCHEDULE

Name of works :

- 1-Repair work of Swamy Sannathi & vimanam and Arthamandapam
- 2-Reconstruction of Vinayagar Sannathi
- 3-Reconstruction OF Subramaniyar Sannathi
- 4-Repair work Of Sandikeswarar sannathi,bairavar sannathi , Navagragha sannathi Madappali ,Entrance Mandapam & Entrancae Vinayagar sannathi
- 5-Repair and Renovation work Of Thirumadhill Wall
- 6-Providing Cut Stone Flooring

Date of Tender : 28.07.2022

E. M. D. :

- 1-Rs. 7000/-
- 2-Rs. 9000/-
- 3-Rs. 9500/-
- 4-Rs. 8500/-
- 5-Rs. 8000/-
- 6-Rs. 9000/-

ANEXURE

(TO BE FILLED BY THE CONTRACTOR)

- 1 Name of Tenderer :
- 2 Name of Works :
 - 1-Repair work of Swamy Sannathi & vimanam and Arthamandapam
 - 2-Reconstruction of Vinayagar Sannathi
 - 3-Reconstruction OF Subramaniyar Sannathi
 - 4-Repair work Of Sandikeswarar sannathi,bairavar sannathi , Navagraha sannathi Madappali ,Entrance Mandapam & Entrancae Vinayagar sannathi
 - 5-Repair and Renovation work Of Thirumadhill Wall
 - 6-Providing Cut Stone Flooring
- 3 Date of Tender : 28.07.2022
- a) In Person :
- b) By registered post :
- 4 Total value of tender :
- 5 Details about E.M.D. enclosed for this tender and its validity. :
- 6 Registered class of the tenderer with monetary limit and Department in which registered (Certified copy of the registration should be attached) :
- 7 Recent works executed details about name and place of work, Agt. No and value of works etc., should be given. :
- 8 Works under execution details about name and place of work Agt. No. & value of works etc., should be furnished. :
- 9 Command of labour in brief.
- 10 Turn over of previous years (Particulars for a period of three consecutive years are to be furnished) :
- 11 Whether current Income Tax clearance certificate is enclosed? If not, when it will be produced? :

- 12 Whether current sales tax clearance certificate is enclosed?
If Not, when it will be produced?
- 13 Sales tax Registration No.

CONTRACTOR

***Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

APPENDICES

Appendix - I Tender Notice

(As amended in G.O. Ms. No. 618/P.W. dated 30.4.1985)

On behalf of the Pudukkottai Devasthanam Tenders will be received by the Executive Officer, HR&CE Department, Pudukkottai Devasthanam at his office at Pudukkottai **up to 3.30 p.m.** on **28.07.2022** for the work of **1-Repair work of Swamy Sannathi & vimanam and Arthamandapam , 2-Reconstruction of Vinayagar Sannathi, 3-Reconstruction OF Subramaniyar Sannathi, 4-Repair work Of Sandikeswarar sannathi,bairavar sannathi , Navagraha sannathi Madappali ,Entrance Mandapam & Entrancae Vinayagar sannathi, 5-Repair and Renovation work Of Thirumadhill Wall, 6-Providing Cut Stone Flooring, Arulmigu Kailasanathar swamy Temple at Valaramanickam village, Thirumayam Taluk, Pudukkottai District.**

E.M.D. 1-Rs. 7000/-, 2-Rs. 9000/-, 3-Rs. 9500/-, 4-Rs. 8500/-, 5-Rs. 8000/-, 6-Rs. 9000/-.

- 1.1. The Tenders should be in the prescribed, form obtainable from the Executive Officer, Pudukkottai Devasthanam, Pudukkottai.
The Tenders will be opened by the Executive Officer, Pudukkottai Devasthanam, Pudukkottai at the place and on the date aforementioned.
- 1.2. The Tenderers or their agents are expected to be present at the time of opening of tenders. The tender receiving officer will, on opening each tender, prepare a statement of the attested corrections therein and hand it over to the tenderer concerned and initial all corrections in the presence of the tenderer. If any of the tenderers or their agents finds it inconvenient to be present at the time, then in such a case the tender receiving officer will on opening the tender in the absence of tenderers make out a statement of the unattested corrections and communicate it to him. The absentee tenderer shall then accept the statement of the corrections without any question whatsoever.
2. Tenders must be submitted in sealed covers and shall be addressed on the Executive Officer, Pudukkottai Devasthanam, Pudukkottai district.,. The name of the tenderer and the name of the work are noted on the cover.

CONTRACTOR

*Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.*

- 2.1. If the tender is made by an individual, it shall be signed with his full name and his address shall be given. If it is made by a firm it shall be signed with the co-partnership name by a member of the firm who shall also sign his own name and the name and address of each member of the firm shall be given. If the tender is made by a corporation, it shall be signed by a duly authorised officer who shall produce with his tender, Satisfactory evidence of his authorisation, such tendering corporation may be required, before the contract is executed, to furnish evidence of its corporate existence.
- 2.2. Each tenderer must also send a certificate of Income-tax verification from the appropriate Income-tax authority in the form prescribed therefore. The certificate will be valid for one year from the date of issue for all tenders submitted during the period.
- 3.1. In case of proprietor or partnership firm it will be necessary to produce the certificate for mentioned for the proprietary or properties and for each of the partners as the case may be.
- 3.2. If the tenderer is registered as a SSI Unit in Government and if a certificate for the current year had already produced by him during the calendar year in which the tender is made. It will be sufficient, if particulars regarding the previous occasion on which the said certificate was produced are given.
- 3.3. All tenders received without certificate as aforementioned will be summarily rejected.
4. Each tenderer must pay as Earnest Money, a sum of **E.M.D. 1-Rs. 7000/-, 2-Rs. 9000/-, 3-Rs. 9500/-, 4-Rs. 8500/-, 5-Rs. 8000/-, 6-Rs. 9000/-** into the Branch of State Bank of India or any other nationalized bank within the jurisdiction of the cash paid at Pudukkottai devasthanam office **Executive Officer, Pudukkottai Devasthanam, Pudukkottai** and enclosed with his tender the chelan endorsed accordingly. Earnest money will be refunded to the unsuccessful, tenderer on application, after intimation is sent of rejection of the tender whichever is earlier. The earnest money will also be received in cash or currency notes by the Executive Officer. When currency notes given the tenderer should sign his name in full with date on the back of all the currency notes given by him, whatever their denomination may be.
- 4.1. The earnest money will be retained in the case of the successful tenderer and will not carry any interest. It will be dealt with, as provided in the tender.
5. The tender will remain valid for a period of ninety days from the last date for receipt of tender, the validity period can be extended further, if the contractor gives his consent in writing specifying the period of extension.

CONTRACTOR

*Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai*

- 5.1. The rates noted in the tender will not be final and further negotiation of the tenderer rates will be entertained. He shall forthwith upon and intimation being given to him of acceptance of his tender by the Officer duly authorised in this behalf under article 299(I) of the constitution. Hereinafter called the accepting authority take security Deposit of 2% of the value of contract in one of the forms prescribed in Tamilnadu Public Works account code i.e. by taking into account of the amount of Earnest Money Deposit already deposited with the tender. It would be sufficient to pay the balance amount to make up the 2% of the value of contract for the purpose of security Deposit.
- 5.2. The Security deposit together with earnest money deposit and the amount with held according to clause 64-1 of general conditions to the contract shall be retained as security for due fulfillment of contract. If a cash security deposit by the contractor he shall follow the procedure laid down in the proceeding paragraph for payment of earnest money deposit and such deposit shall not bear any interest.
- 5.3. On receipt of written communication of acceptance of tender if the tenderer fails to pay the requisite security deposit within the period specified in the written communication or backs out from the tender or with-drawn his tender, the earnest money deposit shall be forfeited to the Government.
- 5.4. If the contractor fails to carryout the contract after paying the requisite deposit, then he will be liable for the excess expenditure if any incurred to complete the works as contemplated in the general conditions to the contract.
- 5.5. It shall be expressly understood by the tenderer that on receipt of written communication of acceptance of tender from the accepting authority, there emerges a valid contract between the Executive Officer and the tenderer for execution of the work without any separate written agreement. Hence for the purpose the tender documents i.e. tender notice tender offered by the contractor, general conditions to the contract, negotiation, correspondences, written communication of acceptance of foundation of the rights of both the parties to the contract. Provided that it shall be open to the accepting authority to insist execution of any written agreement by the tenderer, if administratively considered necessary of expedient.
- 5.6 **Eligibility Class of contractor in first class P.W.D/Water Resource Department Only.**
- 5.7 **A Person who ever is not initializing a contractual work in due time (or) If initiated but incompleted is ineligible to Apply again in the Pudukkottai Devasthanam.**
- 5.8 **A person who ever lost his Deposit (EMD) Amount, is ineligible to Apply.**

CONTRACTOR

*Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.*

6. The tenderer shall examine clearly the Tamilnadu building practice and also the general conditions to contract contained therein and sign the Temple office copy of the Tamilnadu building practice and its addenda volume in token of such study before submitting his tender unit rates, which shall be for finished work in situ. He shall also carefully study the drawing and additional specifications and all the documents connected with the contract. The Tamilnadu building practice and other connected documents with the contract such as specifications, plans, descriptive specification sheet regarding materials, etc. Can be seen at any time between 10:00 A.M. and 5:45 PM. on office of the Executive Officer, Pudukkottai Devasthanam, Pudukkottai.

A copy of the set of contract documents can also be had on payment of **1.Rs.1500 + 270/-, 2. Rs.1500 + 270/-, 3. Rs.1500 + 270/-, 4. Rs.1500 + 270/-, 5. Rs.1500 + 270/-, 6. Rs.1500 + 270/-**

Down load the on line tender Schedule document must paid Schedule Cost with schedule time at Pudukkottai Devasthanam Head office.

7. The tenderer attention is directed to adhere the requirements for Materials under the clause "Materials and Workmanship in the general conditions to the contract. Materials conforming to the I.S.I. standards shall be used on the work, and the tenderer shall quote his rates accordingly.
8. The Government will not, however, after acceptance of contract rate, pay any extra charges for lead or for any other reason, in case the contractor is found later on to have misjudged the materials available. Attention to the contractor is directed to the general conditions to contract regarding payment of signaorage, tolls etc.
9. The tenderers particular attention is drawn to the sections and clauses in the General conditions to contract dealing with.
1. Test, Inspection and rejection of defective materials and work.
 2. Garage.
 3. Construction plant.
 4. Water & lighting
 5. Clearing up during progress and for delivery.
 6. Accidents
 7. Delays.
 8. Particulars of payment
- 9.1. The contractor should closely peruse all the specification clauses, which govern the rates, which he is tendering.
10. A schedule of quantity accompanies this tender notice. It shall be definitely understood that the Government does not accept any responsibility for the correctness or completeness of this schedule and that this schedule is liable to alterations by omission, deductions, or additions at the discretion of the

CONTRACTOR

*Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.*

Executive Officer, Pudukkottai Devasthanam, Pudukkottai set forth in the conditions of contract. The tenderer will, however quote this lump sum tender on this schedule of quantities. He should quote specific rates of each item in the schedule and the rates should be in Rupees and in sum of five paise. The rates should be written both in words and figures and the units in words.

- 10.i. The tenderer should also show the totals of each items and the grand total of the whole contract and quote in the tender a lump sum. For which will be undertaken to do the whole work subject to the conditions of contract such lumpsum agreeing with the total amount of schedule 'A'. This schedule accompanying the lumpsum tender shall be written legibly and free from erasers overwriting of conversion figures. Corrections where unavoidable should be made by crossing out, initialing, dating and rewriting.
11. Tenderer offering a percentage deduction from or increase on the estimate amount and these not submitted in proper form or in due time will be rejected. Rates or lump sum amount for items not called for shall not be included in the tender. No alteration which is made by the tenderer in the contract form in the conditions of contract, the drawings, specification quantities accompanying same will be recognized and if any such alterations are made the tender will be a void.
12. The tenderer should work out own his rates without reference being made to HR&CE Department estimates which are not open for inspection by the tenderer.
13. The tenderer must accept the materials at these prices and shall quote their price for finished work accordingly. Not with standing any subsequent Change in the market value for these materials, the change to contract. No centage or incidental charges will be borne by Government in connection with this supply.
14. The attention of the tenderer is directed to the contract requirements as to the time of beginning work, the rate of progress and the dates for the completion of the whole work and its several parts. The following rates of progress and proportionate value of work done from time to time as will be indicated by the Executive officer certificate of the value of work done will be required. Date of commencement of this program will be the date on which the site (or premises) is handed over to the contractor.

The contractor has to maintain the Percentage of work specified below.

If the contractor fails to keep the rate of progress as stipulated, Penalty will be imposed on the contractor for his slow progress with reference to clauses from 55 to 57 to general conditions of contract in T.N.B.P. Vol. II

CONTRACTOR

*Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.*

Period after date of Commencement	Percentage of work to be completed (based on contract Lump sum amount)
1.Upto the end of Two Month	20 % (Fifteen Percent Only)
2. Upto the end of Four Month	20 % (Fifteen Percent Only)
3. Upto the end of Six Month	20 % (Fifteen Percent Only)
4. Upto the end of Eight Month	20 % (Fifteen Percent Only)
5. Upto the end of Nine Month	20 % (Twenty Percent Only)
Work should be completed fully at end of Nine months	

NOTE: The periods to be entered in column for the purpose of defining the rate of progress may be fixed by the Executive Officer to suit each case.

15. No part of the contract shall be sub-let without written permission of the Executive Officer nor shall transfer be made by power of attorney authorising others to receive payment on the contractor's behalf.
16. If further necessary information is required the Executive Officer will furnish such information but it must be clearly understood that tenders must be received in order and according to instructions.
17. The Commissioner or other sanctioning authority reserves the right to reject any tender or all the tenders without assigning any reason therefore.
18. The tenderers who are them selves not professionally qualified shall undertake to employ qualified technical men at their cost to look after the work. The tenderers should state in clear terms whether they are professionally qualified or whether they undertake to employ technical men required by the department specified in the schedule below for the work. In case the selected tenderer is professionally qualified or has undertaken to employ technical men under him, he should see that one of the technically qualified men is always at the site of the work during working hours personally checking all items of works, and paying extra attention to such works as may demand special attention (e.g.) reinforced concrete works etc.
(In format below entered incorporate the latest forms fixed by Government for the Employment of Technical Assistant from time to time and penalty for non-employment of such Technical Assistant, etc.,)

CONTRACTOR

*Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.*

Value of contract	Qualification and No. of Technical Assistant to be employed
1.Upto Rs.1.00 Lakh	No Technical Assistant need be employed. However if the officer, who accepts the tender, considers that the nature of work requires a Technical Assistant conditions may be stipulated in the tender while that i) One Diploma holder in Civil Engineering (or) ii) a retired J.E. may be employed.
2. Rs.1.00 lakh to Rs.5.00 lakhs	i) One Diploma holder in Civil Engineering (or) ii) not less than, one retired Junior Engineer
3. Rs.5.00 lakh to Rs.10.00 lakhs	i) One B.E. (Civil) (or) ii) equivalent degree holder (or) iii) not less than one retired Sub-Divisional officer (AEE or ADE) or) iv) one diploma holder with 3 years experience.
4. Rs.10.00 lakh to Rs.25.00 lakhs	i) One B.E. (Civil) with 3 years experience (+) One Diploma Holder in Civil Engineering (or) ii) Equivalent degree holder with 3 years experience (+) One Diploma Holder in Civil Engineering (or) iii) Not less than One retired AEE / ADE (+) One Diploma Holder in Civil Engineering (or) iv) Two Diploma Holders in Civil Engineering with 3 and 5 years experience respectively.
5. Rs.25.00 lakh to Rs.50.00 lakhs	i One B.E. (Civil) with 3 years experience (+) Two Diploma Holder in Civil Engineering (or) ii) One B.E. (Civil) with 3 years experience (+) Two retired Junior Engineers (or) iii) Equivalent degree holder with 3 years experience (+) Two Diploma Holder in Civil Engineering / Two retired Junior Engineers (or) iv) One retired AEE or ADE (+) Two Diploma Holders in Civil Engineering (or) v) One retired AEE or ADE (+) Two retired Junior Engineers.
6. Above Rs.50.00 lakhs	(i) Three B.E. (Civil) with 3 years experience (+) (ii) Two Diploma Holder in Civil Engineering

CONTRACTOR

***Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

- Note: 1. Item 1,2,3,4,5 or 6 should be scored out in case where not applicable to the particular work.
- Note: 2. A penalty of Rs.2000/- per month, for diploma holder and Rs.5000/- per month for degree holder levied in case of default on the part of contractors, in following the norms laid down above.
- Note: 3. The employment of Technical Assistant could be based only on the value of contract.
- Note: 4. Engineers with Mechanical Engineering qualification and retired from Civil Engineering Department are also suitable to supervise the civil Engineering works because of their experience in Civil Engineering field.
- Note: 5. In case the contractor who is professionally qualified is not in a possession to remain always at the site of work and to pay extra attention to such work as may demand special attention (eg. RCC. Work etc.) He should employ technically qualified man as prescribed above.
19. A tenderer submitting a quotation which the tender accepting authority considers excessive and or indicative of the insufficient knowledge of current prices or definite attempt at profiteering will tender himself liable to be debarred permanently from tendering or for such period as the tender accepting authority may decide. The tender rates should be based on the controlled price for materials, price permissible for the tenderer to change a prevent purchased of under the provision of clause 8 of hearing and profiteering prevention ordinance 1943 as amended from time to time and in similar principles in regard to labour and supervision in the construction.
20. The contractor should offer employment to ex-toddy tappers as far as possible. The number of ex-toddy tappers to whom he can see after employment should be mentioned in the tender and he should undertake in the contract to offer such employment to such number.
- Note: This paragraph should be scored out if the cost of the work involved is less than Rs.10000/-.
20. The contractor shall comply with provisions of the apprentices' act 1961 and the rules and orders issued there under from time to time. If he fails to do so, his failure will be a breach of contract and the competent authority may at his discretion, cancel the contract of invoice any of the penalties for the breach of contract provided in the conditions of contract. The contractor shall also be liable for any pecuniary liability arising on account of any violation by him of the provisions of the Act. Contractor shall, during the currency of the contract ensure engagement of the apprentices in the categories mentioned below who may be assigned by the Director Employment and Training/State apprenticeship advisor, Tamilnadu. The contractor shall train them as required under the apprentices Act 1961 and the rules made there under and shall be responsible for all obligations of the employer under the said act including the liability to make payments to the apprentices as required under the said act.

CONTRACTOR

*Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.*

22. The contractor should employ I.T.I. Trained mason for every ten masons or part thereof. In the case of non-availability of I.T.I. Trained masons, the contractor should obtain the prior approval of the Executive Officer concerned before proceeding with the contract with the other kinds of masons.

CONTRACTOR

*Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.*

APPENDIX II (A) TENDER

DATE :

To
 Pudukkottai Devasthanam
 Represented the
 Executive Officer,
 Pudukkottai Devasthanam, Pudukkottai.

Sir,

I/we do hereby tender and if this tender be accepted undertake to execute the following works. **1-Repair work of Swamy Sannathi & vimanam and Arthamandapam , 2-Reconstruction of Vinayagar Sannathi, 3-Reconstruction OF Subramaniyar Sannathi, 4-Repair work Of Sandikeswarar sannathi,bairavar sannathi , Navagraha sannathi Madappali ,Entrance Mandapam & Entrancae Vinayagar sannathi, 5-Repair and Renovation work Of Thirumadhill Wall, 6-Providing Cut Stone Flooring, Arulmigu Kailasanathar swamy Temple at Valaramanickam village, Thirumayam Taluk, Pudukkottai District** as shown in the drawings and described in the specifications prescribed in the office of the Executive Officer, Pudukkottai Devasthanam, Pudukkottai such variations by way of alterations (or) additions to and omissions from the said works and method of payment are as provided for in the conditions of contract for the sum of Rupees (to be entered in words and figures)

Or such other sum as may be arrived at under the clause of the General conditions to contract, relating to and payment on lump sum basis or by final measurements at unit prices.

2. I/We have also completed the price list of items in schedule 'A' annexed (in words and figures) for which I/We agree to execute the work and receive the payment on measured quantities as per the General conditions to the contract.
3. I/We do hereby distinctly and expressly declare and acknowledge that before the submission of my or our tender. I/We have carefully followed the instructions in the tender notice and have read the Tamil Nadu Building Practice and the General Conditions to the contract therein and the Tamil Nadu Building Practice Addenda volume that I/We have made such examinations of the contract documents and of the plans specifications quantities and of the location where the said work is to be done and such investigation of the work required to be done and in regard to the materials required to be furnished as to enable me/us to thoroughly understand the intention of the same and the requirement convenient, stipulations and restrictions contained in the contract and in the said plans and specifications and distinctly agree that I/We will not here after make any claim or demand upon the Government based upon or arising out of any alleged misunderstanding or misconception or mistake on my or our part of the said requirements convenient stipulations, restrictions and conditions.

CONTRACTOR

*Executive Officer,
 Pudukkottai Devasthanam,
 Pudukkottai.*

4. I/We enclose an income tax verification certificate.

I/We being a registered Public Works Department contractor.

I/We have already produced an Income Tax verification certificate during the current calendar year in respect of

(Here particulars of the previous occasions on which the certificate was produced should be given. The legal address of the contractor for service of all letters and notices will be as follows:)

5.i.a I/We enclose herewith the chalans for the payment of the sum of Rupees (to be entered in words and figures) as earnest money not to bear interest.

5.i.b I/We have paid **1.Rs.1500 + 270/-, 2. Rs.1500 + 270/-, 3. Rs.1500 + 270/-, 4. Rs.1500 + 270/-, 5. Rs.1500 + 270/-, 6. Rs.1500 + 270/-** as against the E.M.D. of Rs. _____ (Rupees _____ only) since I am/We are eligible to pay the E.M.D. at concessional rate.

5.i.c In lieu of cash deposits, I/We have enclosed a _____ bearing No. _____ issued for value of Rs. _____ (Rupees _____ only) drawn/endorsed/pledged in favour of the Executive Officer, Pudukkottai Devasthanam, Pudukkottai. _____

6. If my/our tender is not accepted, this sum shall be returned to me/us on my/our applications when intimation is sent to me/us of rejections or at the expiration of ninety days from the date of this tender, whichever is earlier. If my/our tender is accepted, the earnest money shall be retained by the Government as security Deposit for the due fulfillment of contract. If upon intimations being given to me/us by the authority authorised by the Governor under Article 299 (i) of the constitutions (hereinafter called the accepting authority) of acceptance of tender I/We fail to make the additional security deposit then I/We agree to the forfeiture of earnest money deposit. Any notice required to be served on me/us here under shall be sufficiently served on me/us. If delivered to me/us personally or forwarded to me/us by post to (Registered or Ordinary) or left at my/our address, given herein. Such notice shall, if sent by post be deemed to have been served on me/us at time when in due course of post, it would be delivered at the address as to which it is sent.

CONTRACTOR

*Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.*

7. I/We fully understand that on receipt of communication of acceptance of tender from the accepting authority, there emerges a valid contract between me/us and the Executive Officer and in the tender documents i.e tender notice, tender with schedules general conditions to the contract and special conditions of the tender, negotiation letter, communication of acceptance of tender, shall constitute, the contract for this purpose and be the foundation of rights of both the parties, as defined in clause 4 of tender notice, provided that, it shall be open to the accepting authority to insist on execution of any written agreement by tenderer if administratively considered necessary (or) expedient.
8. I/We have also signed the copy of the Tamilnadu building practice and National Building code and addenda volume there to, maintained in the Temple office in acknowledgement of being bound by all conditions of the clauses of the general conditions to the contract and all specifications for items of works described by a specification number in schedule 'A'.
9. In consideration of the payment of Rupees or such other sum as may be arrived at under the clause of the general conditions to the contract, relating to payment on lumpsum basis or by final measurement at unit prices, I/We agree subject to said conditions to execute and complete the works shown upon the said conditions drawing serially from Number 1st inclusive (Schedule B) and described in the specification (Schedule C) and to the extend of probable quantities shown in schedule, 'A' with such variations by way of alterations or additions to or deductions from the said works and method of payment therefore as are provided for in the said conditions.
10. The term Executive Officer in the said conditions shall the HR&CE Officer incharge of the Temple having jurisdiction for the time being over the work, who shall be competent to exercise all the powers and privileges receive here in favour of Government with the previous sanction of or subject to ratification by the competent authorities in case where such sanction or ratification may be necessary one who has been during authorised under Article 299(1) of the constitution.
11. I/We agree that the time shall be considered as the essence of this contract, and to commence the work as soon as this contract is accepted by the competent authority as defined by the TNPWD Code and the site is handed over to me as provided for in the agreement, said conditions and agree to complete the work with in months from the date of such handing over of the site (or premises) and to show progress as defined in the tabular statement. Rate of progress subject nevertheless to the provisions for extension of time contained in clause 56 of Tamilnadu Building Practice.
12. I/We agree that upon the terms and conditions of contract being fulfilled and performed to the satisfaction of the Executive Officer the security deposited by me/us herein before received of such portion of as I/We may be entitled to under the said conditions be paid back to me/us provided in clause 64 of the General conditions to the contract.

CONTRACTOR

*Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.*

13. I am/We are professionally qualified and my/our qualifications are as follows:

I/We in pursuance of clause 18 of tender notice undertake to employ the following technical staff for supervising the work and will see that the one of them is always at site during working hours personally checking all items of works and paying extra attention to such works as may require special attention (e.g. reinforced cement concrete).

Name of Technical staff proposed to be employed (1)	Qualification (2)	Experience (3)
1.		
2.		
3.		

14. I/we agree that the Arbitrator for fulfilling the duties set forth in the arbitration clause of the General Condition to contract shall be

- i. The Joint Commissioner Thanjavur in case the value of claim is upto Rs.50000/- and
- ii. I/We that in case, the value of claim is Rs.50000/- and above, the remedy will be through the competent Civil Court only.

15. On behalf of the Pudukkottai Devasthanam, Pudukkottai and as duly authorised by the Commissioner the above tender for a value of Rs. _____ (Rupees _____ only) is accepted on this day of _____ 20____
Signature of witness in full
address with Name in Block letters.

16. "On evaluation of Tender it is found that if the overall quoted amount of the, Tender is less than 5 to 15% of the value put to Tender, the Contractor shall pay an additional security at 2% of the estimated value. If the Tender discount exceeds 15% to 20%, the contractor shall pay an additional Security deposit of 50% of the difference between the quoted amount and estimated amount. Failure to furnish the Additional Security Deposit within 15 days from the date of receipt of Acceptance order and execute the Agreement shall entail cancellation of award of contract and forfeiture of E.M.D furnished.

CONTRACTOR

***Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

Annexure to Tender Notice

Schedule 'A'

Schedule of Rates and Approximate Quantities:-

a) The quantities hereby given those upon which the lumpsum tender cost of the work is based but they are subject to alternations omissions, deductions or additions as provided, for in the conditions of this contract and do not necessarily show the actual quantities of work to be done. The unit rates noted below are those governing payment of extras or deductions or omissions according to the conditions of the contract of the Tamilnadu Building Practice and other conditions or specifications of this contract.

b) It is to be expressly understood that the measured work is to be taken (notwithstanding any custom or practice to the contrary) according to the actual quantities when, in place and finished according to the drawing or as may be ordered from time to time by the Executive Officer and the cost calculated by measurement or weight at the respective prices, without any additional charge for any necessary and contingent works connected therewith. The rates quoted are for works in site and complete in every respect.

Item No.	Probable Quantity Figures	Description of Work	T.N.B.P. No.	Unit in Words Rs. P.	Rate in		Amount in
					Figures	Words	Figures Rs. P.
1.	2.	3.	4.	5.	6.	7.	8.
(Vide separate sheet enclosed)							

Date

Signature of the Contractor

The second sub division of this column (i.e) column is for entering description of units in words such as numbers cubic metre Kg,etc.

SCHEDULE 'B'

List of Drawings

Note: all drawing to be signed by the contractor as well as the officer entering into contract.

Supplemental list

As referred to in the specifications including the General conditions to the contract of Tamil Nadu Building Practice.

Sl. No.	Drawing Number	Description	Date on which the Drawing was supplied	Sl. No.	Drawing Number	Description	Date on which the Drawing was supplied
1.				2.			
3.				4.			

CONTRACTOR

*Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.*

SCHEDULE - 1**NAME OF WORK :**

Repair work of Swamy Sannathi & vimanam and Arthamandapam in Arulmigu Kailasanathar swamy Temple at Valaramanickam village, Thirumayam Taluk , Pudukkottai District.

Validity of Tender: 9 month **Value of Contract:Rs.6,82,552/-**

E.M.D. Rs.7000/-

Date of Tender:28.07.2022

Sl. No.	Quantity in Figures and in words	Description of Work	TNBP No.	Unit in Figures and in words	Rates in		Amount in Figures Rs. P.
					Figures	Words	
1	2085 Sqft	Scaffolding charges for Vimanans and gopurams with casurina posts coconut or plam trees wherever necessary for main, form work and providing with coconut keeth coverings, providing ladder arrangements, country wood pland for working, inpection etc, complete hire charges only for erection, maintainance and removing the same on completion of the work 1 sq.ft.		One Sqft			
2	140 Sqm	Providing Water wash and appropriate methodology to restore the originalities of the existing Granite structures inclusive of necessary scaffolding charges, conveyance and all hire charegs for all tools and plants and clearing the site after completeion of work etc., complete.		One Sqm			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
3	140 Sqm	Pointing the cut stone joints with Lime Mortar 1:1.5 20 mm deep using red and yellow oxide and including cost of special tiles such brush and watering, curing etc complete, as per standard specifications. The lime used should be sourced from Pollachi which is highly iron fortified and suitable for structural and masonry works.		One Sqm			
4	640 Sqft	Providing Vargapoochu over the corewalls of Vimanams / Gopurams, with Lime Mortar 1:1.5 complete including shaping the mukhapathram, mahanasi, Koodu all ornamentals works to proper shape by embedding broken bricks of shaped/chiseled bricks, rough-plastering with Combination Mortar 1:1:4 and finishing with final ornamental plastering and nayam theervani including cost and conveyance of all materials, labour therefore, lifting of materials, all working in heights, curing with water etc, complete including all extra for folding and including clearing from the vimanams/gopurams 100sft superficial area.		One Sqft			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
5	640 Sqft	Painting with multicolour (Panchavarnam) good Emulsion paints complete for the Vinamans/Gopurams, including cost and conveyance of all materials, labour charges including Artist painter, working in heights, lifting of material, cost of brushes etc, complete-which including all extra for foldings-100sft, superficial area.		One Sqft			
6	2 Cum	Supplying and fixing in position of Country wood frames & Machupalagai, including cost and conveyance of all materials etc complete with standard specifications.		One Cum			
7	21.50 Sqft	Supplying & fixing Country wood temple type door including all materials, labour charges for manufacturing and fixing in position including all furniture fittings etc complete with std. Specifications		One Sqft			
8	3 Sqm	Best varnish two coats for wood works etc, complete complying with standard specifications.		One Sqm			
9	10 Sqm	Flooring with cut stone slab of size 600mmX600mm and other sizes suitable for site requirement not less than 100mm thick with machine cut edges and top surface dressed as directed by the departmental officers including cost and conveyance of materials to site and labour charges for paving and Pointing With Lime Mortar 1:1:5 etc complete.		One Sqm			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
10	6 Nos	Providing new sudhai vigrahams in the vimanams and Rajagopurams with galvanised iron rod reinforcement of suitable dia with binding wires wherever necessary, shaping the core with broken bricks set in Lime Mortar 1:1:3 finishing the same with Combination Mortar 1:1:3 bringing to the correct shape (Lakshana) in conformift with silpa sastra inclusive of special ornaments, wiapons, peedam etc., complete and providing C.M. Nayam theervai wherever necessary. inclusive of cost and conveyance of all materials, such as cement broken bricks, and G.I. rods.binding wire all labour for working in heights, curing lifting of materials etc., complete including cement painting 2 coats over a primary coat (one vigraham is accountable with one head, 4 hands with weapons, ornamental costumes etc., as per prathima lakshans, Vighraham height is measurable from the crown top to the bottom of foot only If peetam is pt\rovided the rate with peetam may be adopted as detailled hereunder)		One Nos			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

SCHEDULE - 2**NAME OF WORK :****RECONSTRUCTION OF VINAYAGAR SANNATHI TO ARULMIGU KAILASANATHAR SWAMY
THIRUKKOIL,VALARAMANICKAM,THIRUMAYAM TK ,PUDUKKOTTAI District.**Validity of Tender: 9 month **Value of Contract:Rs.8,93,275/-****E.M.D. Rs.9000/-**

Date of Tender:28.07.2022

Sl. No.	Quantity in Figures and in words	Description of Work	TNBP No.	Unit in Figures and in words	Rates in		Amount in Figures Rs. P.
					Figures	Words	
1	2.50 Cum	Dismantling weathering course in lime concrete cleaning away and carefully stacking materials usefull for re-use all labour charges etc. complete complying with standarad specfications.		One Cum			
2	6.50 Sqm	labour charges for Dismantling the existing cut stone structure including ,Numbering all labour charges ,hire for all tools and plants for employed ,scaffolding charges handling charges hoisting and stacking them in places shown by the departmental officers etc.complete as per standard specfication.		One Sqm			

Contractor***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.*****No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
3	8.00 Sqm	Labour charges for dismantling the vari vargam numbering all labour charges hire for all tools and plants for employed ,scaffolding charges handling charges hositing and stacking them in the places shown by the depatmental officers etc.complete as per standard specfications		One Sqm			
4	33 Cum	Earth work excavation for foundation in all classes of soils and sub soils and todepth as may be directed except in hard rock, requiring blasting, including infinal leads and lifts and re-filling the sides of foundation, with excavated earth in 150mm layers well watered rammed and consolidated, including depositing surplus earth clearing and levelling the site, shoring shuttering baling out water wherever necessary etc., complete complying with standard specification.		One Cum			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
5	4.50 Cum	Supplying and filling in basement and foundation with filling sand in layers not exceeding 150mm thick well watered rammed and consolidated including watering etc., complete complying with standard specification.		One Cum			
6	5.00 Cum	Supplying and filling with sand gravel mix including cost and conveyance of sand, gravel and all labour charges for filling ramming etc. complete with standard specifications.		One Cum			
7	4.50 Cum	Cement concrete 1:5:10 (One of cement five of sand and ten of HBG jelly) for foundation using 40mm gauge HBG jelly inclusive of shoring strutting and baling out water where ever necessary ramming curing etc., complete in respects complying with relevant Std, Specification and as directed by the Dept, Officers.etc, complete with standard specifications.		One Cum			
8	12.00 Cum	Random Rubble masonry work in CM 1:5 (One of cement and five of sand) Using selected stones and bond stones in foundation and basement including dewatering wherever necessary proper setting, curing etc., complete in all respects complying with relevant standard Specifications.		One Cum			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
9	3 Sqm	Centering for soffis of RCC slab of plane surface like lintel, beam etc., including strutting 3.0m height using M.S. sheets of size 90 x 60cm and BG 10 stiffener with M.S. Angles of size 25x25x3mm laid over silver oak (CW) joists size 10cm x 6.5 cm (spaced at about 90cm c/c) and supported by Casurina prop. 10cm to 13cm dia (spaced of 75cm C/C) complying with standard specification.		One Sqm			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
10	5.50 Cum	Providing and laying in position, Standardised Concrete Mix M-20 Grade in accordance with IS:456-2000, using 20mm and down graded hard broken granite stone jelly for all RCC items of works with minimum cement content of 325 kg/m ³ and maximum water cement ratio of 0.55, including admixture (plasticiser / super plasticiser) in recommended proportions as per IS:9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability with about (5 cu.m.) 7730 kg. of 20mm machine crushed stone jelly and with about (3.3 cu.m.) 5156 kg. of 10-12mm machine crushed stone jelly and with about (4.79 cu.m.) 7670 kg. of sand, but excluding cost of reinforcement grill and fabricating charges, centering and shuttering and also including laying, vibrating with mechanical vibrators, finishing, curing, etc. and providing fixtures like fan clamps in the RCC floor/ roof slabs wherever necessary without claiming extra, etc., complete complying with standard specification and as directed by the departmental officers. The coarse and fine aggregates to be used should comply with the requirements of IS Standards. (No separate payment will be made by the Department for the excess usage of materials).		One Cum			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

11	550.00 KG	Supplying fabrication and placing in possition of MS or RTS bars for all RCC works including cutting bending placing and the cost of binding wire etc.,complete.		One Kg			
12		Supplying of cut stone for carrying out Garpagraham, Arthamandapam,Thirumathil and Other Temple Structures upto 10 fee length.					
a	430 Cft	labour charges for kalkaram		One Cft			
b	110 Cft	labour charges for pavukkal		One Cft			
c	50 Cft	labour charges for pillar		One Cft			
d	26 Cft	labour charges for uthiram		One Cft			
13		Labour charges for cut stone masonry work in combination mortar 1:1:5 excluding cost and conveyance of cut stone but including all labour charges scaffolding etc complete with standard specifications. The lime used should be sourced from pollachi which is highly iron fortified and suitable for structural and masonry works.					
a	225 Sqft	labour charges for kalkaram		One Sqft			
b	52 Sqft	labour charges for pavukkal		One Sqft			
c	68 Sqft	labour charges for pillar		One Sqft			
d	26 Sqft	labour charges for uthiram		One Sqft			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
14	10 Sqm	Flooring with cut stone slab of size 600mmX600mm and other sizes suitable for site requirement not less than 100mm thick with machine cut edges and top surface dressed as directed by the departmental officers including cost and conveyance of materials to site and labour charges for paving and Pointing With Combination Mortar 1:1:5 etc complete.		One Sqm			
15	1.25 Cum	Weathering course concrete with broken jelly 20mm size and pure slaked lime over Pavukkal roof the proportion being 32:12.5 for required depth of 80mm for giving required slope and thickness of roof on required, well beaten with wooden beater etc, complete with standard specifications.		One Cum			
16	7 Sqm	Finishing the top of roof with one course of machine pressed tiles 20cmx 20cmx20mm of approved quality laid in combination mortar 1:1:3, 12mm thick mixed with water proofing compound 2% by weight of cement used etc, complete with standard specifications.		One Sqm			
17	20 Sft	Supplying & fixing Teak wood temple type door including all materials, labour charges for manufacturing and fixing in position including all furniture fittings etc complete with std. Specifications		One Sft			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
18	20 Sft	Best varnish two coats for wood works etc, complete complying with standard specifications.		One Sft			
19	624 Sft	Scaffolding charges for Vimanans and gopurams with casurina posts coconut or plam trees wherever necessary for main, form work and providing with Non flammable steel sheet, providing ladder arrangements, country wood pland for working, inpection etc, complete hire charges only for erection, maintainance and removing the same on completion of the work 1 sq,ft.		One Sft			
20	335 Cft	Brick masonry Combination Mortor 1:1:4 using Stock bricks including all varivargams,moulds, sthambams,mukapathrams, koodu, nasi and all ornamental brick work complete,all pancharams, agarais, karnakoodus, etc., forming core walls oof Rajagopuram/Vimanams complete including cost and conveyance of all materials including cement,all the laboue charges including marking pathies shaping of the bricks,lifting of all the materials to required heights,curing and extra for working in heights etc., complete 100 cft for vimanam/gopuram.		One Cft			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
21		Providing new sudhai vighrams in the vimanams and Rajagopurams with galvanised iron rod reinforcement of suitable dia with binding wire wherever necessary, shaping the core with broken bricks set in Combination Mortar 1:1:3 bringing to the correct shape (Lakshana) in conformity with silpa sastra inclusive of special ornaments, weapons, peedam etc., complete and providing C.M Nayam theervai wherever necessary. inclusive of cost and conveyance of all materials, such as cement broken bricks, and G.I rods. binding wire all labour for working in heights, curing lifting of materials etc., complete including cement painting 2 coats over a primary coat (one vighram is accountable with one head, 4 hands with weapons, ornamental costumes etc., as per prathima lakshans, vighram height is measurable from the crown top to the bottom of foot only if peetam is provided the rate with peetam may be adopted as detailed hereunder)					
	7 Nos	Sudhai size above 1'0" upto 2'6"		One Nos			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
22	200 sft	Providing Vargapoochu over the corewalls of Vimanams/Gopurams, with Combination mortar 1:1:4 complete including shaping the mukhapathram,mahanasi,koodu all ornamentals works to proper shape by embedding broken bricks of shaped /chiseled bricks,rough-plastering with Combination mortar 1:1:4 and finishing with final ornamental plastering and nayam theervani including cost and conveyance of all materials, labour therefore,lifting of materials,all working in heights,curing with water etc,complete including all extra for folding and including clearing from the vimanams/gopurams 100 sft superficial area.		One Sft			
23	200 sft	Painting with multicolour (Panchavarnam) good Emulsion paints complete for the Vinamans/Gopurams, including cost and conveyance of all materials, labour charges including Artist painter, working in heights, lifting of material, cost of brushes etc, complete-which including all extra for foldings-100sft, superficial area.		One Sft			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

SCHEDULE - 3**NAME OF WORK :****RECONSTRUCTION OF SUBRAMANIYAR SANNATHI TO ARULMIGU KAILASANATHAR SWAMY
THIRUKKOIL,VALARAMANICKAM,THIRUMAYAM TK, PUDUKKOTTAI District.**Validity of Tender: 9 month **Value of Contract:Rs.9,03,646/-****E.M.D. Rs.9500/-**

Date of Tender:28.07.2022

Sl. No.	Quantity in Figures and in words	Description of Work	TNBP No.	Unit in Figures and in words	Rates in		Amount in Figures Rs. P.
					Figures	Words	
1	6 Cum	Dismantling weathering course in lime concrete cleaning away and carefully stacking materials usefull for re-use all labour charges etc. complete complying with standarad specifications.		One Cum			
2	7 Sqm	labour charges for Dismantling the existing cut stone structure including ,Numbering all labour charges ,hire for all tools and plants for employed ,scaffolding charges handling charges hoisting and stacking them in places shown by the departmental officers etc.complete as per standard specification.		One Sqm			

Contractor***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.*****No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
3	37 Sqm	Labour charges for dismantling the vari vargam numbering all labour charges hire for all tools and plants for employed ,scaffolding charges handling charges hositing and stacking them in the places shown by the depatmental officers etc.complete as per standard specfications		One Sqm			
4	33 Sqm	Earth Work Excavation for foundation in all soils except hard rock requiring blasting to a full depth with initial lead of 10m and lift of 2m etc complete with standard specification		One Sqm			
5	4.50 Cum	Supplying & Filling in foundation and basement with filling sand, well watered rammed and standard specification including cost of supplying filling sand with standard specification		One Cum			
6	5 Cum	Supplying and filling with sand gravl mix including cost and coveyance of sand,gravel and all labour chares for filling ramming etc.complete with standard specifications.		One Cum			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
7	4.50 Cum	Cement concrete 1:5:10 (One of cement five of sand and ten of HBG jelly)for foundation using 40mm gauge HBG jelly inclusive of shoring strutting and baling out water where ever necessary ramming curing etc.,complete in respects complying with relevant Std, Specification and as directed by the Dept, Officers.		One Cum			
8	12 Cum	Random Rubble masonry work in CM 1:5 (One of cement and five of sand) Using selected stones and bond stones in foundation and basement including dewatering wherever necessary proper setting, curing etc., complete in all respects complying with relevant standard Specifications.		One Cum			
9	5.50 Sqm	Centering for soffis of RCC slab of plane surface Iike lintel,beam etc.,including strutting 3.0m height using M.S.sheets of size 90 x 60cm and BG 10 stiffener with M.S.Angles of size 25x25x3mm laid over silver oak (CW) joists size 10cm x6.5 cm (spaced at about 90cm c/c) and supported by Casurina prop. 10cm to 13cm dia (spaced of 75cm C/C) complying with standard specification.		One Sqm			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
10	5.50 Cum	Providing and laying in position, Standardised Concrete Mix M-20 Grade in accordance with IS:456-2000, using 20mm and down graded hard broken granite stone jelly for all RCC items of works with minimum cement content of 325 kg/m ³ and maximum water cement ratio of 0.55, including admixture (plasticiser / super plasticiser) in recommended proportions as per IS:9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability with about (5 cu.m.) 7730 kg. of 20mm machine crushed stone jelly and with about (3.3 cu.m.) 5156 kg. of 10-12mm machine crushed stone jelly and with about (4.79 cu.m.) 7670 kg. of sand, but excluding cost of reinforcement grill and fabricating charges, centering and shuttering and also including laying, vibrating with mechanical vibrators, finishing, curing, etc. and providing fixtures like fan clamps in the RCC floor/ roof slabs wherever necessary without claiming extra, etc., complete complying with standard specification and as directed by the departmental officers. The coarse and fine aggregates to be used should comply with the requirements of IS Standards. (No separate payment will be made by the Department for the excess usage of materials).		One Cum			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

11	550.00 KG	Supplying fabrication and placing in position of MS or RTS bars for all RCC works including cutting bending placing and the cost of binding wire etc.,complete.		One Kg			
12		Supplying of cut stone for carrying out Garpagraham, Arthamandapam,Thirumathil and Other Temple Structures upto 10 fee length.					
a	430 Cft	labour charges for kalkaram		One Cft			
b	110 Cft	labour charges for pavukkal		One Cft			
c	50 Cft	labour charges for pillar		One Cft			
d	26 Cft	labour charges for uthiram		One Cft			
13		Labour charges for cut stone masonry work in combination mortar 1:1:5 excluding cost and conveyance of cut stone but including all labour charges scaffolding etc complete with standard specifications. The lime used should be sourced from pollachi which is highly iron fortified and suitable for structural and masonry works.					
a	225 Sqft	labour charges for kalkaram		One Sqft			
b	52 Sqft	labour charges for pavukkal		One Sqft			
c	68 Sqft	labour charges for pillar		One Sqft			
d	26 Sqft	labour charges for uthiram		One Sqft			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
14	10 Sqm	Flooring with cut stone slab of size 600mmX600mm and other sizes suitable for site requirement not less than 100mm thick with machine cut edges and top surface dressed as directed by the departmental officers including cost and conveyance of materials to site and labour charges for paving and Pointing With Combination Mortar 1:1:5 etc complete.		One Sqm			
15	1.50 Cum	Weathering course concrete with broken jelly 20mm size and pure slaked lime over Pavukkal roof the proportion being 32:12.5 for required depth of 80mm for giving required slope and thickness of roof on required, well beaten with wooden beater etc, complete with standard specifications.		One Cum			
16	7 Sqm	Finishing the top of roof with one course of machine pressed tiles 20cmx 20cmx20mm of approved quality laid in combination mortar 1:1:3, 12mm thick mixed with water proofing compound 2% by weight of cement used etc, complete with standard specifications.		One Sqm			
17	20 Sft	Supplying & fixing Teak wood temple type door including all materials, labour charges for manufacturing and fixing in position including all furniture fittings etc complete with std. Specifications		One Sft			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
18	20.00 Sft	Best varnish two coats for wood works etc, complete complying with standard specifications.		One Sft			
19	624 Sft	Scaffolding charges for Vimanans and gopurams with casurina posts coconut or plam trees wherever necessary for main, form work and providing with Non flammable steel sheet, providing ladder arrangements, country wood pland for working, inpection etc, complete hire charges only for erection, maintainance and removing the same on completion of the work 1 sq,ft.		One Sft			
20	335 Cft	Brick masonry Combination Mortor 1:1:4 using Stock bricks including all varivargams,moulds, sthambams,mukapathrams, koodu, nasi and all ornamental brick work complete,all pancharams, agarais, karnakoodus, etc., forming core walls oof Rajagopuram/Vimanams complete including cost and conveyance of all materials including cement,all the laboue charges including marking pathies shaping of the bricks,lifting of all the materials to required heights,curing and extra for working in heights etc., complete 100 cft for vimanam/gopuram.		One Cft			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
21		Providing new sudhai vighrams in the vimanams and Rajagopurams with galvanised iron rod reinforcement of suitable dia with binding wire wherever necessary, shaping the core with broken bricks set in Combination Mortar 1:1:3 bringing to the correct shape (Lakshana) in conformift with silpa sastra inclusive of special ornaments, wiapons,peedam etc., complete and providing C.M Nayam theervai wherever necessary. inclusive of cost and conveyance of all materials,such as cement broken bricks,and G.I rods.binding wire all labour for working in heights, curing lifiting of matrerials etc., complete including cement painting 2 coats over a primary coat (one vighram is accountable with one head,4 hands with weapons, ornamental costumes etc., as per prathima lakshans,vighram height is measurable from the crown top to the bottom of foot only if peetam is pt/rovided the rate with peetam may be adopted as detailed hereunder)					
	4 Nos	Sudai size above 1'0" above 2'6"		One Nos			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
22	200 sft	Providing Vargapoochu over the corewalls of Vimanams/Gopurams, with Combination mortar 1:1:4 complete including shaping the mukhapathram,mahanasi,koodu all ornamentals works to proper shape by embedding broken bricks of shaped /chiseled bricks,rough-plastering with Combination mortar 1:1:4 and finishing with final ornamental plastering and nayam theervani including cost and conveyance of all materials, labour therefore,lifting of materials,all working in heights,curing with water etc,complete including all extra for folding and including clearing from the vimanams/gopurams 100 sft superficial area.		One Sft			
23	200 sft	Painting with multicolour (Panchavarnam) good Emulsion paints complete for the Vinamans/Gopurams, including cost and conveyance of all materials, labour charges including Artist painter, working in heights, lifting of material, cost of brushes etc, complete-which including all extra for foldings-100sft, superficial area.		One Sft			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

SCHEDULE - 4**NAME OF WORK :**

Repair work Of Sandikeswarar sannathi,bairavar sannathi , Navagraha sannathi Madappali ,Entrance Mandapam & Entrancae Vinayagar sannathi in Arulmigu Kailasanathar swamy Temple at Valaramanikkam village ,Thirumayam Taluk & Pudukkottai District.

Validity of Tender: 9 month **Value of Contract:Rs.8,46,076/-**

E.M.D. Rs.8500/-

Date of Tender:28.07.2022

Sl. No.	Quantity in Figures and in words	Description of Work	TNBP No.	Unit in Figures and in words	Rates in		Amount in Figures Rs. P.
					Figures	Words	
1	970 Sqft	Scaffolding charges for Vimanans and gopurams with casurina posts coconut or plam trees wherever necessary for main, form work and providing with coconut keeth coverings, providing ladder arrangements, country wood pland for working, inpection etc, complete hire charges only for erection, maintainance and removing the same on completion of the work 1 sq.ft.		One Sqft			
2	103 Sqm	Providing Water wash and appropriate methodology to restore the originalities of the existing Granite structures inclusive of necessary scaffolding charges, conveyance and all hire charegs for all tools and plants and clearing the site after completeion of work etc., complete.		One Sqm			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
3	103 Sqm	Pointing the cut stone joints with Lime Mortar 1:1.5 20 mm deep using red and yellow oxide and including cost of special tiles such brush and watering, curing etc complete, as per standard specifications. The lime used should be sourced from Pollachi which is highly iron fortified and suitable for structural and masonry works.		One Sqm			
4	360 Sqft	Painting with multicolour (Panchavarnam) good Emulsion paints complete for the Vinamans/Gopurams, including cost and conveyance of all materials, labour charges including Artist painter, working in heights, lifting of material, cost of brushes etc, complete-which including all extra for foldings-100sqft, superficial area.		One Sqft			
5	3014 Sqft	Painting two coat with approved Emulsion over the lime plastered wall surface, ceiling and other new surface including clearing preparing the surface curing in all floors including brushes etc., complete as per specification.-10 m2		One Sqft			
6	11 Sqm	Flooring with cut stone slab of size 600mmX600mm and other sizes suitable for site requirement not less than 100mm thick with machine cut edges and top surface dressed as directed by the departmental officers including cost and conveyance of materials to site and labour charges for paving and Pointing With Lime Mortar 1:1.5 etc complete.		One Sqm			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

SCHEDULE - 5**NAME OF WORK :**

Repair and Renovation work Of Thirumadhill Wall in Arulmigu Kailasanathar Swamy Temple at Valaramanikkam village & Thirumayam Taluk , Pudukkottai District.

Validity of Tender: 9 month **Value of Contract:Rs.7,83,868/-**

E.M.D. Rs.8000/-

Date of Tender:28.07.2022

Sl. No.	Quantity in Figures and in words	Description of Work	TNBP No.	Unit in Figures and in words	Rates in		Amount in Figures Rs. P.
					Figures	Words	
1	22 Cum	Earthwork excavation for foundation in all soils except hard rock requiring blasting to full depth with initial lead of 10m and lift of 2m etc., complete		One Cum			
2	3 Cum	Supplying and filling in foundation in basemenet with filling sand in layars of 148mm thickness well watered rammed and consolidated complying with relevant Std Specification including cost of supplying filling sand		One Cum			
3	3 Cum	Cement concrete 1:5:10 (One of cement five of sand and ten of HBG jelly)for foundation using 40mm gauge HBG jelly inclusive of shoring strutting and baling out water where ever necessary ramming curing etc.,complete in respects complying with relevant Std, Specification and as directed by the Dept, Officers.		One Cum			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
4	15 Cum	Random Rubble masonry work in CM 1:5 (One of cement and five of sand) Using selected stones and bond stones in foundation and basement including dewatering wherever necessary proper setting, curing etc., complete in all respects complying with relevant standard Specifications.		One Cum			
5	15 Cum	Supplying of cut stone for carrying out Thirumathil and Other Temple Structures upto 10 feet length		One Cum			
6	20 Sqm	Labour charges for cut stone masonry work in combination mortar 1:1:5 excluding cost and conveyance of cut stone but including all labour charges scaffolding etc complete with standard specifications. The lime used should be sourced from pollachi which is highly iron fortified and suitable for structural and masonry works.		One Sqm			
7	6 Cum	Brick work in lime mortar 1:2 using country brick of size 83/4"x41/4"x21/4" including cost and conveyance of all materials and labour charges and all other incidental charges etc complete complying with standard specification.		One Cum			
8	307 Sqm	Plastering with Lime mortar 1:5, 12mm thick including cost and conveyance of all materials and all labour charges, curing etc, complete complying with standard specification. The lime used should be sourced from pollachi which is highly iron fortified and suitable for structural and masonry works.		One Sqm			
9	307 Sqm	Painting two coat with approved Emulsion over the lime plastered wall surface, ceiling and other new surface including clearing preparing the surface curing in all floors including brushes etc., complete as per specification.-10 m2		One Sqm			
10	515 Sqm	Pointing the cut stone joints with Lime Mortar 1:1.5 20 mm deep using red and yellow oxide and including cost of special tiles such brush and watering, curing etc complete, as per standard specifications. The lime used should be sourced from Pollachi which is highly iron fortified and suitable for structural and masonry works.		One Sqm			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

SCHEDULE - 6**NAME OF WORK :**

Providing Cut Stone Flooring of Arulmigu Kailasanathar Swamy Temple at Valaramanikkam, Thirumayam Taluk & Pudukkottai District.

Validity of Tender: 9 month **Value of Contract: Rs.8,92,450/-**

E.M.D. Rs.9000/-

Date of Tender: 28.07.2022

Sl. No.	Quantity in Figures and in words	Description of Work	TNBP No.	Unit in Figures and in words	Rates in		Amount in Figures Rs. P.
					Figures	Words	
1	35 Cum	Earthwork excavation for foundation in all soils except hard rock requiring blasting to full depth with initial lead of 10m and lift of 2m etc., complete		One Cum			
2	20 Cum	Supplying and filling in foundation in basement with filling sand in layers of 148mm thickness well watered rammed and consolidated complying with relevant Std Specification including cost of supplying filling sand		One Cum			
3	4 Cum	Cement concrete 1:5:10 (One of cement five of sand and ten of HBG jelly) for foundation using 40mm gauge HBG jelly inclusive of shoring strutting and baling out water where ever necessary ramming curing etc., complete in respects complying with relevant Std, Specification and as directed by the Dept, Officers.		One Cum			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

1.	2.	3.	4.	5.			8.
					6.	7.	
4	15 Cum	Brick work in lime mortar 1:2 using country brick of size 83/4"x41/4"x21/4" including cost and conveyance of all materials and labour charges and all other incidental charges etc complete complying with standard specification.		One Cum			
5	20 Sqm	Flooring with cut stone slab of size 600mmX600mm and other sizes suitable for site requirement not less than 100mm thick with machine cut edges and top surface dressed as directed by the departmental officers including cost and conveyance of materials to site and labour charges for paving and Pointing With Lime Mortar 1:1:5 etc complete.		One Sqm			
6	125 Sqm	Plastering with Lime mortar 1:5, 12mm thick including cost and conveyance of all materials and all labour charges, curing etc, complete complying with standard specification. The lime used should be sourced from pollachi which is highly iron fortified and suitable for structural and masonry works.		One Sqm			

Contractor

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

**No of Correction
No of Overwriting**

SCHEDULE `C'

List of the specifications for the various items of works, supply these described in Schedule `A' by Standard specification numbers.

1. The contractor shall employ the following Technical staff supervising the work and shall see that one of them is always at site during working hours, personally checking all items of works and paying extra attention to such works as may demand special attention e.g. reinforced cement concrete work etc.,

Name of the members of the Technical staff to be employed	Qualifications	Experience
---	----------------	------------

(Vide separate sheet enclosed)

Note: In case contractor is himself professionally qualified the above specification should be suitably altered and in cases in which the contractor selected has not given an undertaking to employ qualified men it should be scored out.

Note: Additional specification if any which have to be entered in schedule `C' should be entered the item (1) above and numbered continuously.

GENERAL CONDITIONS

1. The work shall be carried out in strict accordance with Tamilnadu Building Practice and its volumes.
2. The contractor shall make his own arrangements for the procurement of materials to the required specifications required for the work.
3. The Executive Engineer shall reject any materials, which is proved to be not according to standards.
4. All storage facilities shall be subject to approval of the Engineer in charge and shall be constructed to prevent easy access for inspection and identification
 - a. Avoid storage for long periods, do not store at all if Possible during the rain season.
 - b. For other precautions in this regard I.S.4082 - 1987 shall apply

CONTRACTOR

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

1. One I.T.I trained mason for every ten masons or part thereof should be employed.
2. The tenderer shall not employ the labour below the age of 18 years.
3. He should offer employment to Ex-servicemen, ex-toddy tappers and unemployed agricultural labours as far as possible.
4. Sufficient labourers as may be required by the Executive Engineers shall be employed on the work so as to gear up the progress of the work.
5. The tenderer shall not claim for any loss due to foreseen circumstances including suspension of work due to cause.
6. Accident to people employed by the contractor resulting compensation to be paid, as per the workmen 'compensation' act shall be on the contractor's account.
7. The tenderer should make his own arrangements for the conveyance of materials to the work site from sources specified.
8. Payment will be made on detailed measurement. Any of the items in the schedule may be omitted or altered technically and no variation in the rate shall become payable to the contractor on account of the omission of variation in quantities.
9. Before payment of final bills the contractor shall produce certificate from the Income-Tax authority that all income-tax payable by him upto date has been paid and certificate from the sales tax authority that all the S.T. Payable by him upto date has been paid.
10. The Executive Engineer will be at liberty to withdraw any portion of work or to carry out any portion of the work at any time either Departmentally or through any other agency in the interest of Government without assigning any reasons to the contractor who is actually doing the work and the Executive- Engineer's decision will be final and binding on the contract and contractor is not entirely entitled for any compensation on account of the same.
11. In the event of work being transferred to any other Temple the Executive Officer who is incharge of the Temple having Jurisdiction over the work shall be competent the exercise all the power and privileges and reserved in favour of the Government.
12. The tenderer shall fill in column 7 of the Schedule also
13. The rates should inclusive of all taxes payable to the Government by the tenderer.
14. The rate will be for the finished items of works and no extra bill is paid for seignorage.
15. a. An amount of 2% or 1% of the value of the work including cost of all materials such as Cement, steel etc. will be deducted from the contractor's bill at the time of payment towards income tax.
b. An amount of 2% for civil works and 4% for other than civil works on the value of work done including cost of materials supplied by departmentally will be deducted towards sales tax from the contractors bill at each stage of payment.
16. Tenders with tampered seal will not be accepted.

CONTRACTOR

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

17. Tenders in which the rates are not written in words will summarily be rejected. In case of any discrepancy while expressing the rates in words, the rate whichever is advantage to Government will only to be taken into account.
18. Tenders containing over writing or corrections, which are not attested by the tenderer, will be liable for rejection.
19. Tenders received without E.M.D. will be summarily rejected.
20. The site should be cleared by the contractor after completing the work as required by the departmental Engineers.
21. The work shall be carried out without any hindrance or damage to the existing cross masonry works such as bridges, super passages etc.
22. The recovery towards hire charges of machineries will be made at the rates specified and for the time actually utilized by the contractor, for time required as per the data considering the out turns whichever is higher.
23. The contractor should prepare a bar chart for the works costing more than Rs.5.00 lakhs and produce the same before starting the work.
24. In case of any dispute of difference between the parties for the contract either during the progress (or) after the completion of the works or after determination, abandonment or breach of the contract as to any other matter or thing arising there under except as to matters left to the self discretion of the Executive Officer of the clause 18,20,25-3,27(1) 34,35 and 37 of the General conditions of contract as to the works holding Executive Officer of the payment of any items on which the contractor may claim to be entailed them either party shall forthwith give to the other notice or such dispute or difference shall be and is hereby referred to the arbitration of the Superintending Engineer, of the nominated circle mentioned in the article of agreement herein after called the arbitrator, in cases where the value of claim is less than and upto Rs.50,000/- In cases where the value of claim more than Rs. 50,000/- the parties will seek remedy through the competent civil court.
25. The contractor has to maintain the progress of work as per the percentage of work specified in tender notice.

If the contractor fails to keep the rate of progress as stipulated in the tender notice penalty will be imposed on the contractor for his slow progress with reference to clause of T.N.B.P. under preliminary specification.
26. Similarly for lighting arrangements to do any work to keep up the accepted progress of work, the contractor has to make his own arrangements at his cost. Possible help to get power connections from the electricity Board will be given by the Department. The contractor will be permitted to do night work like earth work excavation etc. So as to complete the work within the accepted contract period. But concreting has to be done in daytime. No extra payment will be paid for such works.

CONTRACTOR

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

27. The leads and lifts involved for the various materials as well as finished work are clearly, furnished in the schedule. However the contractors are request to inspect the places of work both casting yard for precast blocks and the canal breach for, in situ concrete and borrow areas for the conveyance of earth and the quarries for sand and metal and satisfy themselves about the adequacy of the provision made for lift and lead before tendering. The contractor will not be eligible for extra lead and lift even if it is actually involved during the course of the work.

CONTRACTOR

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

GENERAL CONDITIONS

1. Period of completion months.
2. The successful tenderer will be required to make a further security Deposit at the direction of the accepting authority. Execution and completion of the work should be within the period specified in the tender notice from the date of commencement of work or handing over of site which ever is earlier.
3. Specification for the various materials and the execution of all works shall be as per Tamilnadu Building Practice.
4. It must be distinctly and specifically understood that whole works will be executed complying with the specification in metric system found by T.N.B.P. payment will be made as per measurement recorded metric units only.
5. Every tenderer before tendering is expected to inspect the proposed work site. Any claim for extra cost on account of increase in lead of materials will not be accepted.
6. The work shall be produced with expeditiously from the date on which the site is handed over and completed as early as possible as required by the Departmental officers.
7. The contractor must make his own arrangement to form approach roads and ramps if any required at his own cost and maintain the same through out the period of contract. On permission for using Existing roads if any by the contractor will be commenced to the authorities concerned and the contractor must bear all charges incidental to using the road, No extra cost on this account will be entertained by the Department.
8. If night work is required to fulfill the agreed rate of progress all arrangements shall be made by the contractor including lighting the area without any additional claims.
9. The plan and schedule of quantities are subject to alternate during execution and payment shall be made as per actual measurement of works done. No claims for any extra cost of works whatsoever shall be entertained for such revision in design extra.
10. The rates specified in the schedule for the different items of work are for the finished works and no extra will be paid for baling and pumping charges indented on the work.
11. The shed for storing the materials should be put up by the contractor at his own cost. The contractor's special attention is invited to clause general conditions of T.N.B.P. and also required to provide at his own expenses, sheds, latrine, water, lights, urinals etc. for his workers.

CONTRACTOR

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

12. In case it is found by the Departmental officers that the contractor has brought any of the required materials from quarry with lesser Lead than the specified in the schedule, proportionate deduction will be made from the contractor's rate of payment for the finished work for the respective item.
13. The contractor will be held responsible for the proper and safe custody of all the Department Materials which are handed over to the contractor until they are finally used on the work (or) taken over by the Department.
14. The Executive Officer will be liberty to withdraw and carryout any portion of the work at any time either Departmentally or through any other agency, in the interest of Temple.
15. In the event of the work being transferred to any other Temple to Executive Officer who is incharge of Temple having jurisdiction over the work shall be competent to exercise all the work and privilege reserved in favour of the Government.
16. The contract rates are inclusive of Sales-Tax payable by the contractor to the Government as per the Tamilnadu General Sales-Tax Act 1989 as amended from time to time. No enhanced rates will be payable to the contractor for any upward revision of Sales-Tax during the currency of the contract.
17. Tenderers should obtain from the authorities concerned an Income-Tax clearance certificate and sales- Tax Clearance certificate for the current year and submit it along with the tenders. The Tenderers who are engaged in works contract as well as Business for selling materials should produce sales tax clearance certificate or they should produce NIL certificate.
18. The work executed by the contractor under the contract shall be maintained at the contractor's risk until the work is taken over by the Executive officer. The Temple shall not be liable to pay for any loss or damages occasioned by or arising out of famine flood, cyclonic-eruption, earth-quake other convulsions of nature and all other calamities risk arising as nature of act of God during such period and that the option whether to take insurance coverage or not to cover such risks is left to the contractor.
21. Recovery under Revenue Recovery Act:
Whenever any amount has to be paid by the contractor by virtue and class 57-4 or any amount that may be due or may become due from the contractor under these presence and the contractor is not responding to the demands for payments against a said amount, then the Government shall be entitled to recover the said amount under the provisions of the Tamil Nadu Revenue Recovery Act 1964 (Tamil Nadu Act V of 1964). G.O.Ms.No. 1318 / PW / Dt.22.5.1986 amended in Government letter No.135130 / Y2 / 88-3 / Dt.30.1.1990.

CONTRACTOR

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

SPECIAL CONDITIONS FOR MATERIALS

A. Materials

1. The contractor shall make his own arrangements to procure all materials like Burma teak wood, cement, steel, binding wire and others required for the work, at his own cost.
2. The contractor shall always purchase the materials as fresh as possible after manufacture and he shall on demand by the Executive Engineer, furnish a laboratory test certificate of a character meeting with the approval of the consignment of steel rods and for each category of rods.

The quality of steel procured shall be with the I.S.I. Standards the quality tests shall be conducted by the contractors at their own cost in the Government testing laboratories (or) in the laboratories of P.W.D if available at various stages, P.W.D. has liberty to confirm the quality of the materials supplied By the contractor at various levels and stages at their own laboratory at the cost of contractor.

3. The Executive Engineer shall reject any steel which is proved to be not according to standards.

B. MEASUREMENT

The measurement will be taken as per the specifications and units mentioned in the Schedule "A"

The Engineer in-charge will supply drawing for adoption.

SPECIAL CONDITIONS

1. The contractor shall be responsible for the safe custody and storage of the materials under dry condition at the places approved by the Executive Engineer.
2. No royalty shall be charged where due for materials quarried from the Public Works Department (or) Government quarries. Assistance as necessary will be given to the contractor by the Department to obtain access to quarries approved by the Executive Engineer, plot rent shall be charged so far material stocked in the Department land during the course of construction provided such materials are removed in a month after the works are completed.
3. The contractor should make his own arrangements for providing approach road to the work site for which no extra will be paid to him on completion of the work the contractor shall not permitted to remove the materials laid for formation of road. If the contractor is allowed to use the existing roads he shall maintain it in good condition at his own cost through out the period of the execution of work.
4. Reference to TNPB No. in the Schedule of quantities referred to Vol 1 and Vol.II of 85 and 88.

CONTRACTOR

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

5. The contractor shall abide by the contractor labour regulation of the P.W.D. framed by the Tamil Nadu Government.
6. The contractor should bear his own expense for providing safety materials for any labourer during work and all the types of works and on his failure to do so Government shall be entitled to provide the same and the cost will be recovered from the contractor.
7. When there are any complaints of non-payment of wages, the labour bill of the contractor maybe withheld pending clearance certificate obtained from the labour Department.
8. Any amount fallen due to the contractor even after effect in recovery from his bill for this work and other works and due to the contractor will be arranged to be recovered from the contractor under provision of revenue recovery act.
9. The Executive Officer may put an end to the agreement at his opinion at any time.
10. Provided in respect of work costing above Rs.2500/-a notice of 10 days shall be given in writing before such termination of work or for subletting for the portion of the work for any other reason.
11. And provided that in the case of bad work (or) materials, action will be taken as provided in the clause TNDSS.27 (c) Standard Preliminary specification.
12. When an agreement is terminated under the clause (10) above the Officer terminating the agreement shall have the option to take over any or all the materials and other equipments at a value of assessed by him and of the contractor does not agree to this, he shall clear the site by removing at his own cost of all such materials, equipment within 10 days from the termination of the agreement, failing which the Government may remove and settle the same after holding the posts and removal and sale to the credit of the contractor.
13. Contractor's rates for the different items of the work involving the uses of cement are inclusive of the cost of cement.
14. The contractor shall be responsible for the safe custody and proper storage of material at the place near the work spots approved by the Executive Officer.

CONTRACTOR

***The Executive Officer,
Pudukkottai Devasthanam,
Pudukkottai.***

தமிழ்நாடு அரசு

இந்து சமய அறநிலையத்துறை

செயல் அலுவலர் புதுக்கோட்டை தேவஸ்தானம்

புதுக்கோட்டை வட்டம் மற்றும் மாவட்டம்

ஒப்பந்தப்புள்ளி அழைப்பு அறிவிப்பு

புதுக்கோட்டை மாவட்டம் , திருமயம் வட்டம், கீழே குறிப்பிட்ட பணி களுக்கு புதுக்கோட்டை தேவஸ்தானம் அலுவலகத்தில் மூடி முத்திரையிடப்பட்ட ஒப்பந்தப்புள்ளிகள் வரவேற்கேப்படுவதுடன் பெறப்பட்ட ஒப்பந்தப்புள்ளிகள் அட்டவணையில் குறிப்பிட்டுள்ளவாறு திறக்கப்படும் என்று அறிவிக்கப்படுகிறது.

வ. எண்	வேலையின் பெயர்	பணியின் தோராய மதிப்பு ரூபாயில்	முன் வைப்புத் தொகை ரூபாயில்	ஒப்பந்தப் புள்ளிகள் படிவம் விற்பனைக்கு கிடைக்கும் நாள்	ஒப்பந்தப் புள்ளிகள் சமர்ப்பிக்க கடைசி நாள்	ஒப்பந்தப் புள்ளிகள் திறக்கப்படும் நாள்
1.	புதுக்கோட்டை மாவட்டம், திருமயம் வட்டம், வாளாமாணிக்கம், அருள்மிகு கைலாசநாதர் திருக்கோயில், 1.சுவாமி சன்னதி மராமத்துப்பணி, 2.விநாயகர் சன்னதி திரும்ப கட்டுதல் பணி 3.சுப்ரமணியர் சன்னதி திரும்ப கட்டுதல் பணி 4.சண்டிகேஸ்வரர் சன்னதி பைரவர் சன்னதி , வெளிவிநாயகர் சன்னதி மராமத்துப்பணி 5.மதில்சுவர் மராமத்துப்பணி 6.சுற்றுப்பிரகாரம் கல்தளம் பாவுதல் பணி	6,82,552 8,93,275 9,03,646 8,46,076 7,83,868 8,92,450	7000 9000 9500 8500 8000 9000	11.07.2022 முதல் 27.07.2022 வரை	28.07.2022 பிற்பகல் 3.00 மணி	28.07.2022 பிற்பகல் 3.30 மணி

ஒப்பந்தக்காரரின் தகுதி

தமிழ்நாடு அரசு இந்து சமய அறநிலையத்துறையில் பதிவுபெற்ற மற்றும் நடப்பில் உள்ள ஸ்தபதி (நடப்பாண்டு வருமானவரி, விற்பனை வரி நிலுவை இல்லா சான்று மற்றும் GST சான்று வழங்குபவர்கள் மட்டும் கலந்து கொள்ளலாம்)

ஒப்பந்தப்புள்ளி படிவ விலை மற்றும் பொருட்கள் மற்றும் சேவை வரி பணி

- 1.ரூ.1500/- + ரூ.270/-
- 2.ரூ.1500/- + ரூ.270/-
- 3.ரூ.1500/- + ரூ.270/-
- 4.ரூ.1500/- + ரூ.270/-
- 5.ரூ.1500/- + ரூ.270/-
- 6.ரூ.1500/- + ரூ.270/-

முடிக்க வேண்டிய காலம்

முன்வைப்பு தொகை செலுத்தப்பட வேண்டிய
செயல் அலுவலர் முகவரி

9 மாதங்கள்

செயல் அலுவலர்
புதுக்கோட்டை தேவஸ்தானம் அலுவலகம் , அருள்மிகு
பிரகதாம்பாள் திருக்கோயில் அருகில் , திருக்கோகர்ணம்,
புதுக்கோட்டை-622001.

செயல் அலுவலர்
புதுக்கோட்டை தேவஸ்தானம்
புதுக்கோட்டை

அறங்காவலர் குழுத் தலைவர்,
புதுக்கோட்டை தேவஸ்தானம்,
புதுக்கோட்டை.