

Validate

Print

Help

**Item Rate BoQ****Tender Inviting Authority: Commissioner, Tambaram City Municipal Corporation****Name of Work: Providing False Ceiling and Air Conditioning in Bill Collection Centre in TCMC (Zone - I, Pammal Office)****Contract No: 44 / 2022 / E1**

<b>Name of the Bidder/ Bidding</b>						
<b>PRICE SCHEDULE</b>						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )						
<b>NUMBER</b>	<b>TEXT #</b>	<b>NUMBER #</b>	<b>TEXT #</b>	<b>NUMBER #</b>	<b>NUMBER #</b>	<b>TEXT #</b>
<b>Sl. No.</b>	<b>Item Description</b>	<b>Quantity</b>	<b>Units</b>	<b>BASIC RATE In Figures To be entered by the Bidder Rs.    P</b>	<b>TOTAL AMOUNT Without Taxes in Rs.    P</b>	<b>TOTAL AMOUNT In Words</b>
<b>1</b>	<b>2</b>	<b>4</b>	<b>5</b>	<b>13</b>	<b>53</b>	<b>55</b>
1	Supply and fixing Perculated gypsum board false ceiling using 18 mm thick of approved Quality and design suspended from the ceiling using 'U' shaped Galvanised Iron channel of size 25 x 25 x 0.55 mm thick at 1.20 M centre to centre on both longitudinal and cross direction for vertical support and fixing 'U' shaped G.I. Channel of size 50 x 30 x 0.55 mm thick at 0.60 m centre to centre on cross direction and fixing of 'U' shaped G.I. channel of size 50 x 10 x 0.55 mm thick at 0.90 m centre to centre on longitudinal direction respectively for horizontal support by using T.W. reapers at corners and at intermediately and fixing of plaster of paries on the panel provided as per design/pattern given by the site officer and finishing the ceiling surface with some plaster of paries materials etc. Necessary openings should be made for providing spotlights, florescent tubes in the ceiling by using kit ply 12 mm thick and opening should be covered with Acrylic panel etc. complete complying with standard specification and as	80.00	M2		0.00	INR Zero Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
2	SUPPLY & INSTALLATION OF AIR-CONDITIONER WITH COPPER COIL 2.0 TR Split Type AC Unit (5 Star Rating) including cost and conveyance of materials and all other labour charges etc., complete	1.00	Nos		0.00	INR Zero Only
3	Dismantling Floor finish in cement mortar with Mosaic Tiles / Glazed Tiles / Cuddapah Slabs including cost and conveyance of materials and all other labour charges etc., complete	40.00	M2		0.00	INR Zero Only
4	Paving the floor with design Antiskirt ceramic tiles (colour and shade as directed) of size 305 mm x 305mm x 6 mm in all floors over a base layer of cement mortar 1:3 (one cement and three sand ) 20mm thick laid in-situ and pointed with same coloured cement	40.00	M2		0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				