

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Commissioner, Tambaram City Municipal Corporation

Name of Work: Providing RCC Culvert at Ward No. 1, JN Salai Vinobha Nagar Junction, J.N. Salai, Vinobha Nagar Junction in TCMC, Zone-1

Contract No: 191 / 2022 / E1

Name of the Bidder/ Bidding						
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>						
NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Earthwork Excavation and depositing on bank with initial lead and lift of 10m & initial lift of 2m in hard stiff clay, stiff black cotton, hard red earth, shales, murrum, gravel, stoney earth and earth mixed with small size boulders as per SS208B	18.00	M3		0.00	INR Zero Only
2	Supplying and filling in foundation and basement with filling sand in layers of not more than 15cm.thick well rammed watered and compacted etc., complete complying with standard specification	2.00	M3		0.00	INR Zero Only
3	Plain Cement Concrete 1:4:8 (one cement four fine aggregates and eight coarse aggregates) using 40mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges and all incidental charges such as water providing etc., complete as per standard specification	4.00	M3		0.00	INR Zero Only
4	Supplying, fabricating, erecting structural steel work for roofing welded or bolted type using MS channels, angles, plates and round bars etc. conforming to IS specification including primer coating and enamel painting as per Design given by the departmental officers etc, complete as per standard specification	36.00	M2		0.00	INR Zero Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
5	Plain Cement Concrete 1:3:6 (one cement, three fine aggregates and six coarse aggregates) using 20mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges etc., complete as per standard specification	7.00	M3		0.00	INR Zero Only
6	Reinforced Cement concrete 1:1.5:3 (one cement, one and half sand & three course aggregate) using 20mm gauge hand broken/ and broken granite stone for all RCC items of works excluding centering shuttering and cost of reinforcement but including curing etc.,complete and also including fixing fan clamps and fixtures in rcc works wherever necessary as directed by departmental officer etc. complete	3.00	M3		0.00	INR Zero Only
7	Suppling and fabricating and placing in position MS (or) R.T.S. bar for reinforcement to all RCC works as per the design given including cost of steel and binding wire also in all floors	229.00	Kgs		0.00	INR Zero Only
8	Plastering with cement mortar (1:5) 12mm ,thick in all floors including cost and conveyance of all materilas to site and labour charges etc,complete as per standard specifications (S.I.306)	3.00	M2		0.00	INR Zero Only
9	Removal of Excavated Excess Earth away from the site to 2K.M including loading and transportation charges etc, complete as per standard specification. For 1M3	13.00	M3		0.00	INR Zero Only
10	Plain Cement Concrete 1:2:4 (one cement, two fine aggregates and four coarse aggregates) using 20mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges etc., complete as per standard specification	3.00	M3		0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				