

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Commissioner, Tambaram City Municipal Corporation

Name of Work: Providing Restoration of Temporary CC Road at Ward No. 3, Kanniyamman Koil Street and Sengutuvan Street Junction in Tambaram City Municipal Corporation, Anaputhur

Contract No: 191 / 2022 / E1

Name of the Bidder/ Bidding						
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>						
NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Sinking well in loose soils, light black cotton soil, sandy loam and ordinary soil under water including bailing (or) pumping charges if necessary etc., complete (First 2.00m depth)	556.00	M3		0.00	INR Zero Only
2	Providing Supply fo weld mesh covering in well portion including cost and conveyance etc., complete as per standard specification	135.00	M2		0.00	INR Zero Only
3	Removal of silt fro the JCB including cost and conveyance of all materials and all other labour charges and incidenal charges etc., complete	32.00	Hrs		0.00	INR Zero Only
4	Lead and lift charges for avove material silt including cost and conveyance and transport charges dn filling with 2km around the lowlying area etc., complete	556.00	M3		0.00	INR Zero Only
5	Dismantling the existing Brick work including dismantling and remove the same at site minimum 2Km away from the site including unloading labour charges etc., complete	5.00	M3		0.00	INR Zero Only
6	Dismantling the existing PCC work including dismantling and remove the same at site minimum 2Km away from the site including unloading labour charges etc., complete	0.30	M3		0.00	INR Zero Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
7	Earthwork excavation and depositing on bank with initial lead and lift of 10m & initial lift of 2m in hard stiff clay, stiff black cotton, hard red earth, shales, murrum, gravel, stoney earth and earth mixed with small size boulders as per SS20B.	3.00	M3		0.00	INR Zero Only
8	Filling with dry river Sand including cost and conveyance of material, and labour for placing, watering and consolidation etc., complete as per specification	0.60	M3		0.00	INR Zero Only
9	Plain Cement Concrete 1:4:8 mix (One Cement, Four Fine Aggregate and Eighth Course Aggregate) Using 40mm ISS HBG metal including all cost conveyance of materials and labour charges etc. complete as per standard specification.	0.60	M3		0.00	INR Zero Only
10	Reinforced Cement Concrete 1:1½:3 mix (One Cement, One and Half Fine Aggregate and Three Course Aggregate) Using 20mm ISS HBG metal including all cost conveyance of materials and labour charges including vibrating charges etc. complete as per standard specification.					
10.01	Ground Level	1.10	M3		0.00	INR Zero Only
10.02	Above Basement	1.50	M3		0.00	INR Zero Only
11	Suppling and fabricating and placing in position MS (or) R.T.S. bar for reinforcement to all RCC works as per the design given including cost of steel and binding wire also in all floors	78.10	Kgs		0.00	INR Zero Only
12	Brick work in CM 1:5 (one cement & five sand) using II class ground moulded bricks of size 9"X43/8"X 2 3/4" including finishing, curing, etc., complete complying with standard specification					
12.01	Ground Level	0.70	M3		0.00	INR Zero Only
12.02	Basement	2.40	M3		0.00	INR Zero Only
13	Plastering with CM 1:5 mix using 12 mm thick including cost and conveyance of materials and labour charges etc., complete as per Standard Specification	30.20	M2		0.00	INR Zero Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
14	Plastering with cement mortar 1:3, 20mm ,thick in all floors including cost and conveyance of all materilas to site and labour charges etc,complete as per standard specifications (S I 306)	1.80	M2		0.00	INR Zero Only
15	Supply and fixing of Oriya Type Indian Water Closet 580mm x 440mm with "P" or "S" Trap including cost and conveyance of materials and all other labolur charges etc., complete as per standard specifcaiton	2.00	Nos		0.00	INR Zero Only
16	Laying the Flooring with Anti skid coloured ceramic tiles of sizes 200mm X200mm X 6mm size of approved make and quality and colour I Set in cement mortar 1:3 (one cement ,three sand) over 10 mm base layer plastering and pointing with white cement neatly as directed	6.10	M2		0.00	INR Zero Only
17	Daddoing with glazed tiles of 150 mm x 150 mm x 6mm size of approved make and quality and colour set in Cement Mortar 1:2 (One Cement and Two Sand) and pointing with white cement neatly as directed : (P& D) Data 52	25.70	M2		0.00	INR Zero Only
18	White Washing with two coats of fresh shell lime including cost and conveyance of materials and labour charges etc. complete as per Standard specification.	1.80	M2		0.00	INR Zero Only
19	Distempering two coats of best oil bound distemper of approved colour and quality including preparation of surface including cost and conveyance of all materials and all other labour charges etc	30.20	M2		0.00	INR Zero Only
20	Solid PVC door shutters using 19 gauge 19mm MS square tubes for styles and outer frames. 15mm MS square tubes for top, lock and bottom rails. The steel tubes shall be covered with 5mm thick solid PVC sheets. Shutter using 5mm thick solid PVC sheets for panelling shall rigidly fixed in position including necessary furniture and fittings. The overall size of styles shall be 50mm x 30mm. The over all size of top rail, lock rain and bottom rail shalle be 75mm x 30mm. The overall soze of frames shall be 50mm x 45mm, with suitable rabate for housing the shutter	3.00	M2		0.00	INR Zero Only
21	Wiring with 2 x 1.5 Sq.mm (22 / 0.3) PVC insulated SC unsheated cu. Conductor of 100v grade in suitable pvc rigid pipe on wall and ceiling with PVC accessories and with TW switch box and 5A Pt switch with painting of suitable colour PVC light point / Fan Point SD - 18	3.00	M2		0.00	INR Zero Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
22	Supply and fixing of 4 Feet 40 Watts Type single type street light flourscent fitting suitable for the one no. flourscent tube with copper choke * condensor complete including cost and conveyance of materials and all other labour charges etc. complete	2.00	Nos		0.00	INR Zero Only
23	Supply and fixing of WT bulk head fitting with guard (Philips / Bajaj / Crompton / K. Lite) suitable for 11W CFL lamp with CFL including cost and conveyance of materials and all other labour charges etc. complete	1.00	Nos		0.00	INR Zero Only
24	Supply and fixing of PVC Nahini Floor Trap with PVC Grating including cost and conveyance of materials and all other labour charges etc., complete	2.00	Nos		0.00	INR Zero Only
25	Supply and fixing of 20mm GI Pipe including cost and conveyance of materials and all other labour charges etc., complete	5.00	RM		0.00	INR Zero Only
26	Supply and fixing of PVC Screw down tap heavy type 20mm dia including cost and conveyance of materials and all other labour charges etc., complete	2.00	Nos		0.00	INR Zero Only
27	Paving the flooring with special type of Eurocan flooring tiles cement based hydraulically pressed Antiskirt 20mm thick tiles cm 1:3 mix 20mm thick etc., including cost of all materials and all labour charges etc. complete	5.00	M2		0.00	INR Zero Only
28	Removal of excess excavated earth minimum 2Km lead including all cost and conveyance of all materials and all other labour charges etc., complete.	6.00	M3		0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				