

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Commissioner, Tambaram City Municipal Corporation

Name of Work: Providing HDPE Tank and EB MS Kiosk Box @ Zone -1 (Ward No. 29) Solomon Colony, New Street, 1st Mettu Street and Nagappa Nagar in Thiruneermalai

Contract No: 191 / 2022 / E1

Name of the Bidder/ Bidding						
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>						
NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Construction of 2000 Litre PVC Water Tank Pedestalo including earth work, sank filling, PCC 1:4:8, Construction of Solid Blocks of Sie 40cm x 20cm x 15cm in cement mortar 1:5, Plastering and colour washing including cost and conveyance of materials and all other labour charges etc. complete as per standard specification	6.00	Nos		0.00	INR Zero Only
2	Supply and delivery of HDPE Tank 2000 Litre Capacity bearing with ISI Mark providing 1 Nos of 20mmm Tap connection with check nut washer nipple arrangement and 1 No of 25mm scour and 32mm for over flow arrangemetrn etc. complete (TWAD SOR 2021-22)	6.00	Nos		0.00	INR Zero Only
3	Supply and delivery of MS Kiosk of size 0.75 x 0.45 x 0.75m made up of MS angle of size 50mm x 50mm x 4mm alround covered with 16 gauge MS sheet and kiosk door made up of MS Plates of size 25mm x 3 mm including cutting, welding, grinding, locking arrangements and labour etc. (TWAD Sor 2021-22)	6.00	Nos		0.00	INR Zero Only
4	Construction of Kiosk pedestal including earth work, sand filling, pcc 1:4:8 brick work, plastering and colour washing including cost and conveyance of materials and all other labour charges etc. complete as per standard specification	6.00	Nos		0.00	INR Zero Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
5	Supply and delivery of single phase panel board with two level gauged with auto start for 1/5 hp singl ephase submerisble pumpset including cost and conveyance of materials etc., compelte as per standard specification	6.00	Nos		0.00	INR Zero Only
6	Earth work excavation in all classes of soil except sand and rock such as hard stiff clay black cotton soil murrums hard red earth hard gravelly soil etc., complete (TWAD SOR 2021-22)	36.00	M3		0.00	INR Zero Only
7	Supply and delivery of 50mm dia 6 KSC PVC pipe including cost and conveyance of materials to site etc., complete	60.00	RM		0.00	INR Zero Only
8	Labour charges for laying and jointing for 63mm PVC pipe only labour charges etc., complete (TWAD SOR 2021-22)	60.00	Nos		0.00	INR Zero Only
9	Refilling charges for the excavation earth including cost and conveyance of material and labour for mixing and labour for mixing placing and consolidation and watering for curing etc., compelte as per relevant (TWAD SOR 2021-22)	36.00	RM		0.00	INR Zero Only
10	Supply and delivery of 32mm GI Elbow including all charges etc., complete (TWAD SOR 2021-22)	6.00	Nos		0.00	INR Zero Only
11	Supply delivery and fixing of following items of materials including cost and conveyance of material and labour charges etc., complete as per standard specification					
11.01	0.60 x 0.60 Hylem Sheet 3mm thick	2.16	M2		0.00	INR Zero Only
11.02	32 Amps Porcelin Fuse Unit	6.00	Nos		0.00	INR Zero Only
11.03	32 Amps DP Swith with metal clad	6.00	Nos		0.00	INR Zero Only
11.04	4 Way Neutral Link	6.00	Nos		0.00	INR Zero Only
11.05	56/0.3 (4 Sq.mm)	240.00	RM		0.00	INR Zero Only
11.06	Earthing	6.00	Nos		0.00	INR Zero Only
11.07	25mm GI Service Pipe	18.00	RM		0.00	INR Zero Only
11.08	Wooden board	6.00	Nos		0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				