

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Commissioner, Tambaram City Municipal Corporation

Name of Work: Providing BT/CC Patches Ramp and Drain at (Ward No. 30) Durga Nagar Main Road, Pillayair Koil 2nd Street, Bhavani Amman Koil Street, Kamaraj Street

Contract No: 191 / 2022 / E1

Name of the Bidder/ Bidding						
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>						
NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1	Preparing the Existing surface to UGD/WS /road to Proper Gradient and remove the loose soil without damage the Water Supply Pipes. The Rate inclusive of all charges such as Earth work and remove the same 2Km away from the site etc, complete as per standard specifications.	47.00	M3		0.00	INR Zero Only
2	Earthwork Excavation and depositing on bank with initial lead and lift of 10m & initial lift of 2m in hard stiff clay, stiff black cotton, hard red earth, shales, murram, gravel, stoney earth and earth mixed with small size boulders as per SS20BB	3.00	M3		0.00	INR Zero Only
3	Providing laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mix plant carrage of the mixed material by tipper to site laying in uniform layers with pavers in subbase /basecourse on well prepared surface and compacting with vibratory roller to achieve the decide density etc, complete as per standard specifications. As per Clause 406 of Morth	14.00	M3		0.00	INR Zero Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
4	Providing and laying Prime coat of 7 kgs/10 sqm over the WMM surface treated with primer using 7 kgs of bituminous Emulsion for 10 square meter area including cost of bituminous binder, including labour charges for	88.00	M2		0.00	INR Zero Only
5	Providing and laying tack coat of 2.5 kgs/10 sqm over the WMM surface treated with binder using 2.5 kgs of bituminous Emulsion for 10 square meter area including cost of bituminous binder, including labour charges for	88.00	M2		0.00	INR Zero Only
6	Providing and laying 50mm consolidated thick Dense Bituminous Macadam using 0.24 cum of 26.50- 13.20mm, 0..25cum of 13.20-2.36mm and 0.23cum of 2.36mm & below and with 53.20 Kgs of VG30/ VG40 bitumen for premixing per 10sqm including cost and conveyance of all materials to CMP site, heating the bitumen and aggregate to required temperature and mixing them in required temperature in central hot mix plant 20-30 ton capacity, conveying the mix by tipper trucks to work site, spreading the mix to uniform thickness of 50mm with paver to the specified grades and cross sections and compacted by Vibratory / Pneumatic Roller to the required density etc., including labour for attending to paver at site etc., including hire charges and fuel charges for 20-30 t CMP with bitumen boiler, tipper trucks, Paver Finisher / 9m paver finisher, Vibratory / Pneumatic rollers and all other tools and plant required, including fuel and all other incidental charges etc., complete as per specification using CMP as per clause 505 MORTH Rev-5	4.70	M3		0.00	INR Zero Only
7	Providing and laying Bituminous concrete to 30mm thick using 0.13cum of 19.00-9.50mm graded metal 0.17 cum of	2.82	M3		0.00	INR Zero Only
8	Providing steel centering and shuttering using 10cm to 15cm dia casurina post and MS sheet of size 60cm x 90 cm	50.00	M2		0.00	INR Zero Only
9	Plain Cement Concrete 1:4:8 (one cement four fine aggregates and eight coarse aggregates) using 40mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges and all incidental charges such as water providing etc., complete as per standard specification	18.00	M3		0.00	INR Zero Only

Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
10	Plain Cement Concrete 1:2:4 (one cement, two fine aggregates and four coarse aggregates) using 20mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and labour charges etc., complete as per standard specification	28.00	M3		0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				