

[Validate](#)[Print](#)[Help](#)

Item Rate BoQ

Tender Inviting Authority: Commissioner, Tambaram City Municipal Corporation

Name of Work: Construction RCC Culvert with Storm Water Drain @ (Ward No. 31) Subburaya Nagar Main Road in Zone-1, TCMC

Contract No: 191 / 2022 / E1

| | | | | | | |
|--|--|----------|--------|---|---|--------------------------|
| Name of the Bidder/ Bidding | | | | | | |
| <div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div> | | | | | | |
| NUMBER | TEXT # | NUMBER # | TEXT # | NUMBER # | NUMBER # | TEXT # |
| Sl. No. | Item Description | Quantity | Units | BASIC RATE In Figures To be entered by the Bidder Rs. P | TOTAL AMOUNT Without Taxes in Rs. P | TOTAL AMOUNT In Words |
| 1 | 2 | 4 | 5 | 13 | 53 | 55 |
| 1 | Earthwork excavation and depositing on bank with initial lead and lift of 10m & initial lift of 2m in hard stiff clay, stiff black cotton, hard red earth, shales, murrum, gravel, stoney earth and earth mixed with small size boulders as per SS20B. | 63.00 | M3 | | 0.00 | INR Zero Only |
| 2 | Filling with dry river Sand including cost and conveyance of material, and labour for placing, watering and consolidation etc., complete as per specification | 7.20 | M3 | | 0.00 | INR Zero Only |
| 3 | Plain Cement Concrete 1:4:8 mix (One Cement, Four Fine Aggregate and EighthCourse Aggregate) Using 40mm ISS HBG metal including all cost conveyance of materials and labour charges etc. complete as per standard specification. | 7.20 | M3 | | 0.00 | INR Zero Only |
| 4 | Providing Steel centering and shuttering using 10cm to 15cm dia casurina post and M.S sheet of size 60cm X 90 cm etc., complete as per standard specification for Drain | 146.00 | M2 | | 0.00 | INR Zero Only |

| Sl. No. | Item Description | Quantity | Units | BASIC RATE In Figures To be entered by the Bidder Rs. P | TOTAL AMOUNT Without Taxes in Rs. P | TOTAL AMOUNT In Words |
|----------------------|---|---------------|-------|---|---|--------------------------|
| 1 | 2 | 4 | 5 | 13 | 53 | 55 |
| 5 | Plain Cement Concrete 1:2:4 (one cement, two fine aggregates and four coarse aggregates) using 20mm size ISS HBG metal including cost and conveyance of all materials to site and including for the mixing, laying and | 20.00 | M3 | | 0.00 | INR Zero Only |
| 6 | Supplying, fabricating, and placing in position of mild steel for all reinforced cement concrete works including cost and conveyance of steel and binding wire and all other labour charges for cutting bending tying etc, complete as per standard specification | 120.00 | Kgs | | 0.00 | INR Zero Only |
| 7 | Reinforced Cement Concrete 1:1½:3 mix (One Cement, One and Half Fine Aggregate and Three Course Aggregate) | 2.40 | M3 | | 0.00 | INR Zero Only |
| 8 | Removal of excess excavated earth minimum 2Km lead including all cost and conveyance of all materials and all | 42.07 | M3 | | 0.00 | INR Zero Only |
| Total in Figures | | | | | 0.00 | INR Zero Only |
| Quoted Rate in Words | | INR Zero Only | | | | |