

### **TENDER SCHEDULE**

**Name of the Work:** New Construction of Compound Wall for Belongs to Kancheepuram Egambaranathar Temple @ Poonamallee High Road, Kilpauk, Ch-10

**Name of Contractor:**

**Tender Value:**32,76,570/-

**Cost Of EMD : Rs.26,400/-**

Sl.N o.	Quantity	Description of item	TNDSS NO.	Rate		Per	Amount
				In Figure	In words		
1	35.00 Cu.m	Demolishing of the existing compound Wall including all cost of Labour ,clearing away and carefully stacking materials useful for re-use for any thickness of walls					
2	135.00 Cu.m	Earthwork excavation for foundation in all soils and sub soils except hard rock not requiring blasting and filling the sides of foundation with same soil including well consolidation etc complete as per standard specification					
3	12.00 Cu.m	Supplying and filling the foundation and basement with filling river sand in layer of roof more than 15cm thick including cost of all charges etc complete as per standard specification.					
4	14.00 cu.m	Cement Concrete 1:5:10 Using 40mm Size HBG Jelly for foundation and flooring concrete including cost of all charges etc complete as per specification.					
5		Supplying erecting and centering for sides and soffits of all R.C.C items of works including cost of all charges etc complete as per standard specification.					
	184.00 Sq.m	Columns					
	116.00 Sq.m	Plinth Beam Sides					

**Signature of Executive Officer**

**No.of Correction/Overwriting:**

**Signature of Contractor**

6		R.C.C. Standardised M-20 Grade Concrete in all R.C.C. items of works including cost of materials but excluding cost of steel and also including cost of labour charges etc complete as per standard specification.					
	45.00 cu.m	For Foundation and Basement					
	9.00 cu.m	For Ground floor					
7	5.4 MT	Supplying, Fabricating and placing in position MS/RTS For all RCC works including cost of steel and GI binding wire an all floors etc. complete complying with standard specification					
8	58.00 Cu.m	Brick work in cm 1:4 using Stock Bricks of size 9" x 4 1/2" x 3" including cost and conveyance of all materials and labour charges and all other incidental charges etc complete complying with standard specification.					
9	274.00 Sq.m	Plastering with cemet mortar 1:5,12mm thick including cost and conveyance of all materials and all labour charges,curing etc,complete complying with standard specifications.					
10	234.00 Sq.m	Providing Vargapoochu over the corewalls of Compund Wall with Cement Mortor 1:4 complete including shapping the mukhapathram, mahanasi, Koodu all ornamentals works to proper shape by embdding broken bricks of shaped/chiselled bricks, rough-plastering with C.M. 1:4 and finishing withfinal ornamental plastering and nayam theervani including cost and conveyance of all materials, labour therefore, lifting of materials, all working in heights, curing with water etc, complete inculding all axtra for folding and inculuding clearing.					

Signature of Executive Officer

No.of Correction/Overwriting:

Signature of Contrractor

11	118.00 Sq.m	Special plastering for R.C.C. slab beam and sunshades with cement mortar 1:3, 10mm thick including cost and conveyance of all materials and labour charges, curing etc. complete complying with standard specifications.					
12	3490.00 Kg	Supplying and fixing in position of M.S. grill Over the compound wall including cost of materials and labour charges for Fixing etc complete as per standard specification.					
13	757.00 Sq.m	painting two coats to walls using best quality and brand of exterior plastic emulsion paint over one priming coat including cost of all charges etc complete as per standard specification.					
14	124.00 Sq.m	painting two coats to new iron works using best quality and brand of Synthetic enamel over one priming coat including cost of all charges etc complete as per standard specification.					

Signature of Executive Officer

No.of Correction/Overwriting:

Signature of Contractor