

ISSUED TO THIRU :

ASSISTANT COMMISSIONER / EXECUTIVE OFFICER (IC)

TENDER SCHEDULE

Schedule Of Quantities To Accompany The Providing in Estimate for the Repaire and Renovation of work for Outer Compound Wall area Cleaning cutstone with Pointing, damaged area Plastering, Panchavarnam and Wall Painting use in Arulmigu Venkatachalapathy Swamy Temple @ Oppiliappan koil, Thirunageswaram, Kumbakonam Taluk, Thanjavur District

EMD : Rs.10700/-

Date of tender : 22.07.2022

Contract value: Rs.10,64,360/- (Including GST 12%)

Time of completion : 3 months

Sl. No	Qty		Description of Work	TNBP No.	Unit in words	Rate in figures	Rate in Word	Amount
1	23310.00	Sqft	Restoration by providing herbal water wash(Combination of Venthayam powder 20%, Siyakai Powder 10%, Arapu powder 5%, Boonthi kottai powder 50%, Arugampul powder 3%, Nannari ver powder 3%, Vettiver powder 3%, Korai kizhangu powder 3%, and sembaruthi leaf powder 3% total 100%) are used for removal of lime wash on stone and oil smudge) and approrimats methodology to restore the originalities of the existing granite structure inclusive of hire charges scaffolding arrangements conveyance charges for tools & plants and machinaries to the workshop spot and cleaning the site after completion of work etc		one Square feet			
2	2170.00	Sqm	Pointing the cut stone joints with Lime mortar 1:1.5, 20mm deep including cost of special tiles such brush and watering, curing etc., complete as per standard specifications.		one Square meter			
3	23.00	Sqft	Painting with multicolour (Panchavarnam) good water based exterior emulsion paints complete for the Vinamans/Gopurams, including cost and conveyance of all materials, lobour charges including Artist painter, working in heights, lifting of material, cost of brushes etc, complete-which including all extra for foldings - 25'0"sft, superficial area		one Square feet			
4	160.00	Sqm	Plastering with One coat Lime mortar 1:2,12 mm thick including cost and conveyance of all materials and all labour charges, curing etc., complete complying with standard specifications.		one Square meter			

No. of correction :
No. of over writing

Contractor

A.C. / E.O(IC).

5	1590.00	Sqm	Thorough scrapping of old plastered surface/Painting two coats with approved water based exterior Emulsion over the cement and Lime plastered wall surface, ceiling and other surface including clearing preparing the surface curing in all floors including brushes etc., complete as per specification.		one Square meter			
			Sub Total					
			GST 12%					
			Total					

No. of correction :
No. of over writing

Contractor

A.C. / E.O(IC).