

ISSUED TO THIRU :

ASSISTANT COMMISSIONER / EXECUTIVE OFFICER (IC)

### TENDER SCHEDULE

**Schedule Of Quantities To Accompany The Providing in Estimate for the Repaire and Renovation of work for Madapalli and Yagasalai in Arulmigu Venkatachalapathy Swamy Temple @ Oppiliappan koil, Thirunageswaram, Kumbakonam Taluk, Thanjavur District**

**EMD : Rs.5100/-**

**Date of tender : 22.07.2022**

**Contract value: Rs.5,01,020/- (Including GST 12%)**

**Time of completion : 3 months**

| Sl. No | Qty  |      | Description of Work  | TNBP No. | Unit in words    | Rate in figures | Rate in Word | Amount |
|--------|------|------|--|----------|------------------|-----------------|--------------|--------|
| 1      | 1386 | Sqft | Restoration by providing herbal water wash(Combination of Venthayam powder 20%, Siyakai Powder 10%, Arapu powder 5%, Boonthi kottai powder 50%, Arugampul powder 3%, Nannari ver powder 3%, Vettiver powder 3%, Korai kizhangu powder 3%, and sembaruthi leaf powder 3% total 100%) are used for removal of lime wash on stone and oil smudge) and approrimats methodology to restore the originalities of the existing granite structure inclusive of hire charges scaffolding arrangements conveyance charges for tools & plants and machinaries to the workshop spot and cleaning the site after completion of work etc |          | one Square feet  |                 |              |        |
| 2      | 73   | Sqm  | Supplying and paving fixing with New Cut stone of sizes suitable for site requirement not less than 100mm thick size and top surface dressed inculding cost and conveyance of all materials and all labour charges etc., complete as per the standard specification.   |          | one Square meter |                 |              |        |
| 3      | 143  | Sqm  | Pointing the cut stone joints with Lime Mortar 1:1.5, 20mm deep including cost of special tiles such brush and watering, curing etc., complete.  |          | one Square meter |                 |              |        |
| 4      | 29   | Sqm  | Dismantling, clearing away and carefully stacking materials useful for reuse for any thickness one coursed of Pressed Tiles roof finish in cement mortar (si.no.33, sch.item.no.38c, page.no.22 S.R 2021-2022) etc., complete complying with standard specification.   |          | one Square meter |                 |              |        |
| 5      | 29   | Sqm  | Finishing the top of roof with one course of machine pressed tiles 20cmx 20cmx2cm of approved quality laid in Lime mortar 1:1.5, 12mm thick mixed with water proofing compound 2% by weight of cement used etc., complete with standard specifications.  |          | one Square feet  |                 |              |        |

No. of correction :

No. of over writing

Contractor

A.C. / E.O(IC).

|    |      |      |  |  |                  |  |  |  |
|----|------|------|--|--|------------------|--|--|--|
| 6  | 66   | Sqm  | Pointing the top of roof tiles joints area use water proofing compound conforming to ISS at 2% by weight of Lime used and the joints pointed neatly to full depth of tiles with the same Lime mortar mixed with red oxide and water proofing compound including curing etc., complete complying with standard specification and as directed by the departmental officers   |  | one Square meter |  |  |  |
| 7  | 31   | Sqft | Supplying & fixing Teak wood temple type door (Temple pattern ornamental doors with high quality teak wood (country) with 2" minimum to 7" maximum thick ornamental frames, 2" thick to 5" thick kamala (flower planks), creeper, birds, animal figures sculptures, etc., back side 1" thick to 3" plank including necessary carving, shaping, wastage, etc., as per approved plan and design. (page.no.163, 2a)) including all materials, labour charges for manufacturing and fixing in position including all furniture fittings etc., complete complying with standard Specifications. |  | one Square feet  |  |  |  |
| 8  | 251  | Sqm  | Painting two coats with approved water based Exterior/interior Emulsion over the cement plastered wall surface, ceiling and other new surface including clearing preparing the surface curing in all floors including brushes etc., complete as per specification.   |  | one Square meter |  |  |  |
| 9  | 21   | Sqm  | Best varnish two coats for wood works etc, complete complying with standard specifications.  |  | one Square meter |  |  |  |
| 10 | 2.50 | Sqm  | Clean removal of old paint from the surface OLD IRON WORK and Repainting old iron works such as gate, steel doors windows ventilators with two coats of approved quality and color of synthetic enamel paint over the existing red oxide primer in all floor etc., complete complying with standard specifications.  |  | one Square meter |  |  |  |
|    |      |      | <b>Sub Total</b>   |  |                  |  |  |  |
|    |      |      | <b>GST 12%</b>   |  |                  |  |  |  |
|    |      |      | <b>Total</b>   |  |                  |  |  |  |

No. of correction :  
No. of over writing

Contractor

A.C. / E.O(IC).