

" TENDER SCHEDULE "
PAPPIREDDIPATTI TOWN PANCHAYAT
SCHEDULE - A
Schedule of rates and approximate quantities

a) The quantities here given are those upon which the estimate cost of the work is based but they are subject to alterations, commissions, deduction or additional as provided for in the conditions of this contract and do not necessarily show the actual quantities of work to be done. The unit rates notes below are those government payment for extra or deductions read with the Town Panchayat councils adaptation form and other conditions or specification of this contract and subject to the accepted tender percentage either below, above or at estimate rates as defined in the tender and as shown at the end of Schedule "A"

b) It is expressly understood that measured work is to be taken net-not withstanding any custom to practice to the contrary according to actual quantities when in place and finished according to the drawing or as may be ordered from time by the Assistant Executive Engineer at the cost calculated by measurement or weight at the respective prices with out any additional charge for any necessary or contingent works connected here with. The rates quoted are for works In-SITE and completed in every respect.

15TH FINANCE 2021-22(Ind UNTIED Grant)

**Name of the work : Providing Pipeline at Ward No.10 Kaliyamman Koil Street and 11th ward Moopanan koil Street in
Pappireddipatti Town Panchayat**

EST.Rs.7,20,000

Issued Thiru :
Chalan no. Dt.

Executive Officer
Pappireddipatti Town Panchayat
Dharmapuri District

Sl. No	Qty	Description of item	M.D.S.S No	Per	Rate in		Remarks
					Figure	Words	

1	108.00	cum	Dismantling the Cement Concrete Pavement including all cost of machinery and labour charges etc as per standard Specification		cum			
2	324.00	cum	Earth work excavation for foundation and depositing on bank with in the initial lead of 10m and a lift of 2m in hard stiff clay, stiff block cotton, hard red earth, shales, murrum, gravel, stoney earth and earth mixed with small size boulders etc. complete. complying with std. specifications.SS 20 B		cum			
3			Supply and delivery of pipes and pipes specials including all charges etc.,					
	600.00	M	90mm PVC Pipe 6KSC		M			
	500.00	M	80mm GI Pipe		M			
	48.00	M	80mm GI pipe		M			
	4.00	M	50mm Gate valvue		M			

	2.00	M	65mm Gate valve		M			
	12.00	No	50mm GI Bend		No			
	6.00	No	50m m GI TEE		No			
4			Lowering PVC/ DWSC rigid pipes and specials to trench and laying to proper grade and alignment, jointing with PVC couplers with cement paste.					
	700.00	M	90mm PVC		M			
	500.00	M	110mm HDPE Pipe		M			

5	378.00	m3	Re filling the Excavated earth including cost and conveyance of gravel to work site and all labour charges foe stacking them to departmental gauge at road sides for preparmental officers and spreading and compacting in layers as directed by the dept officers. As per clause 301 & 305 of Morth Specification.		m3			
---	--------	-----------	---	--	----	--	--	--