

PAPPIREDDIPATTI TOWN PANCHAYAT
SCHEDULE - A
Schedule of rates and approximate quantities

a) The quantities here given are those upon which the estimate cost of the work is based but they are subject to alterations, commissions, deduction or additional as provided for in the conditions of this contract and do not necessarily show the actual quantities of work to be done. The unit rates notes below are those government payment for extra or deductions read with the Town Panchayat councils adaptation form and other conditions or specification of this contract and subject to the accepted tender percentage either below, above or at estimate rates as defined in the tender and as shown at the end of Schedule "A"

b) It is expressly understood that measured work is to be taken net-not withstanding any custom to practice to the contrary according to actual quantities when in place and finished according to the drawing or as may be ordered from time by the Assistant Executive Engineer at the cost calculated by measurement or weight at the respective prices with out any additional charge for any necessary or contingent works connected here with. The rates quoted are for works In-SITE and completed in every respect.

Name of work : Construction of Segregation Shed at Compost Yard in Pappireddipatti Town Panchayat

Issued Thiru :
Chalan no. Dt.

Executive Officer
Pappireddipatti Town Panchayat
Dharmapuri District

Scheme :- 15TH FINANCE COMMISSION 2021-22(TIED GRANT IIND PHASE)

Sl. No	Qty	Description of item	M.D.S.S No	Rate in Rupees		Unit in	Amount in Rupees
				Rupees In Fig	Rupees In Words		

Sl. No	Qty		Description of item	M.D.S.S No	Rate in Rupees		Unit in	Amount in Rupees
					Rupees In Fig	Rupees In Words		
1	250	M2	Supplying and fixing of Corrugated Galvain sheet of 0.60 mm thick over MS steel truss including 15cm lapping necessary GI bolts and nuts and washers including cost of all materials and labour charges etc., complete complying with standard specifications. as directed. as per std specification.				M2 (One Square Metre)	
2	2500.00	Kgs	Supplying and fixing of M.S. " L "ANGLES of approved design for truss using necessary mild steel flats for inner and outermembers which should be fixed to "truss" inclusive of priming coat of best approved quality red oxide primer etc., complete complying with standard specifications.				Kgs(One Kilogram)	

Schedule Item 1 to 2 only

Signature of contractor