

Name of the Work : Demolition of unused Dilapidated Buildings chennai - 10, Poonamallee High Road, Door No.769 to 772 Buildings Belongs to A/m Ekambaranathar Thirukkoil at Kancheepuram Town, Taluk and District.

Value of Work Rs.12,80,000/-

Tender schedule

Name of the contractor

Value of tender Rs.12,13,006/- EMD = 12130/-

Period of work 15 days

M.R.NO/Date

Cost of Schedule Rs.7080/-

S.No.	Qty	Description of Work	Rate		Amount
			in figure	in words	
1	2302.65 m ³	Dismantling, clearing away and carefully stacking materials useful for re-use for any thickness of walls Brick / stone masonry in lime mortar walls under 3m high			
2	2571.38 m ²	Dismantling, clearing away and carefully stacking materials useful for re-use for Terracing work in roof or floor			
3	113.93 m ³	Dismantling, clearing away and carefully stacking materials useful for re-use for Wrought & putup framed timbers in roofs/floors (Teak wood)			
4	12125.61 kg	Dismantling, clearing away and carefully stacking materials useful for re-use for iron items as directed by departmental officers			

Executive Officer

No. Of correction in figures in words

Contractor

5	177.40 m ²	Dismantling, clearing away and carefully stacking materials useful for re-use for Doors & windows including removal of frames, hinges and fastenings			
6	39.19 m ²	Dismantling, clearing away and carefully stacking materials useful for re-use for corrugated iron sheet roofing with pan tiles over, without roof timbers			
7	131.44 m ²	Dismantling, clearing away and carefully stacking materials useful for re-use for flat & pan tiles or Mangalore tile over flat tiles, with out roof timbers			
8	5.50 m ³	Dismantling, clearing away and carefully stacking materials useful for re-use for RCC items			

Executive Officer

No. Of correction in figures in words

Contractor