

**SCHEDULE – A**  
**ANAIMALAI TOWN PANCHAYAT**

Est. No.:  
Estimate Amount: **11,00,000**  
EMD.Amount : **Rs. 11,000.00**  
Tender Date & Time:

Sold to : Thiru.  
Challan No.

Date.

Tender Schedule cost Rs.6000.00      + VAT Rs.1080.00      =    Rs.7080.00      Remittance as per Chalan No:      Dated:

Schedule of rates and approximate quantities to accompany the tender for the work of

**Extention of Pipe Line at ward No 7 Ramapuram OHT to ward o 11 Moideenkan street and Ramapuram OHT to ward No 10 Chinnakadai Street in Anaimalai Town Panchayat**

- a) The quantities have given are those upon which the lump-sum tender cost at the work is caused but they are subject to alterations, omissions, deductions or additions as provided for in the conditions of the contract and do not necessarily show the actual quantities of the work to be done. The unit of rates noted below are those governing payment for extras or deductions for omission according to the conditions of the contract as set forth in the conditions and specification for the contract.
  
- b) It is to be expressively understood that the measured work it is to be taken out (Not withstanding any customarily practice to the contrary according to the actual quantities when the place and finished accordingly to the Drawings or as may be ordered time to time by the Town Panchayat Engineer and the cost calculated by works connected there with. The rate quoted is for the works in site and complete in every respect.
  
- c) The material required for the works must be supplied by the contractor and of the approved quality

Signature of Contractor

## TENDER SCHEDULE

**Name of work :** Extention of Pipe Line at ward No 7 Ramapuram OHT to ward o 11 Moideenkan street and Ramapuram OHT to ward No 10 Chinnakadai Street in Anaimalai Town Panchayat

**Estimate amount:** 11,00,000

**Name of Scheme:** 15th FINANCE UNTIED GRANT- 2021-2022

Sl. No.	Probable Quantity		Description of Work	TNDSS & MORTH Specification No.	Rate		Unit	Amount
					In Figures	In Words		
1	882.00	M <sup>3</sup>	Earthwork excavation and depositing on bank with initial lead of 10m and initial lift of 2m sand, silt not under water light back cotton soil, sandy loam and ordinary soil including excavated earth as per standard specifications.				1 m3 (One Cubic Metre)	
2			Supply of PVC & GI Pipes including cost of all charges etc., completed					
	1400.00	M	110 mm OD dia 6kg/ cm2 PVC Pipe				1 m (One Metre)	
	12.00	M	125 mm "B" GI Pipe				1 m (One Metre)	
3		0.00	Towards laying of PVC & GI Pipes including cost of all charges etc., completed					
	1400.00	M	110 mm OD dia 6kg/ cm2 PVC Pipe				1 m (One Metre)	
	12.00	M	125 mm "B" GI Pipe				1 m (One Metre)	

Signature of Contractor

Sl. No.	Probable Quantity		Description of Work	TNDSS & MORTH Specification No.	Rate		Unit	Amount
					In Figures	In Words		
4	882.00	M <sup>3</sup>	Refilling the excavated earth including cost of labour charges etc., completed				1 m3 (One Cubic Metre)	
5	3.00	No	Supply and delivery of 100 CI Sluice valve				1 No (One Number)	
6	2.00	No	Supply and delivery of 200 CI Sluice valve				1 No (One Number)	
7	10.00	No	Supply of 110 mm PVC Bend				1 No (One Number)	
8	4.00	No	Supply of 110 mm PVC Tee				1 No (One Number)	

Assistant Engineer  
Anaimalai Zone  
Coimbatore Dt

Signature of Contractor