

**SCHEDULE – A**  
**KINATHUKADAVU TOWN PANCHAYAT**

Est. No.:

Sold to : Thiru.

Estimate Amount: **Rs,500000/=**

Challan No.

Date.

EMD.Amount :

Tender Date & Time:

Schedule of rates and approximate quantities to accompany the tender for the work of

**Repairs and Maintenance works to the Anna Nagar (60,000Litres) , The street(2,00,000Litres) and Kallankattupudur OHT in Kinathukadavu Town Panchayat**

- a) The quantities have given are those upon which the lump-sum tender cost at the work is caused but they are subject to alterations, omissions, deductions or additions as provided for in the conditions of the contract and do not necessarily show the actual quantities of the work to be done. The unit of rates noted below are those governing payment for extras or deductions for omission according to the conditions of the contract as set forth in the conditions and specification for the contract.
  
- b) It is to be expressly understood that the measured work it is to be taken out (Not withstanding any customarily practice to the contrary according to the actual quantities when the place and finished accordingly to the Drawings or as may be ordered time to time by the Town Panchayat Engineer and the cost calculated by works connected there with. The rate quoted is for the works in site and complete in every respect.
  
- c) The material required for the works must be supplied by the contractor and of the approved quality

# KINATHUKADAVU TOWN PANCHAYAT

## 15 th Finance Commission Grant-Tied Grand 2021-22

Name of work: Repairs and Maintenance works to the Anna Nagar (60,000Litres) , The street(2,00,000Litres) and Kallankattupudur OHT in Kinathukadavu Town Panchayat

Estimate Amount: Rs 5,00,000/.

Schedule Cost remitted vide Challan no-  
Date -  
Issued to Thiru.

Sl. No.	Probable quantity.		Description of work etc.,	MOT SSR B	Rate in		Per	Remarks
					Figures	Words		
1	182.00	M2	Plastering with cement mortar 1:3 mix to 20mm thick including cost and conveyance of all materials to site including curing etc.,complete as per standard specification – 10m2				1m2 (One square metre)	
2	0.00	0.00	Supplying and fixing of following items					
a	5.00	Nos	a)65mm dia GM Gate valve				1No (One Number)	
b	2.00	Nos	b)80mm CI sluice valve				1No (One Number)	
c	2.00	Nos	c)80mm GI Flange set				1No (One Number)	
d	15.00	Rm	e)80mm dia GI 'B' class Pipe fixing				1RM (One Running Metre)	
3	100.00	Kg	Supply and Fixing of steel Hand rail including cost and conveyance of all materials to site including all labour charges etc complete.				1 Kg (One Kilo Gram)	

4	430.00	M2	Painting the new walls two coats over one coat of priming with best Emulsion paint of approved colour and quality including preparation of surface and finishing neatly etc., complete complying with standard specification and as directed by the department officers etc., complete complying				1m2 (One square metre)	
5	6.00	m3	Plain Cement Concrete 1:2:4 Mix (one part cement, Two part sand and Four part of aggregate) using 20mm size ISS HBG metal machine crushed from approved quarry including cost and conveyance of all materials to site, loading and unloading charges and labour charges for mixing, laying and curing etc. complete. Complying with std. specifications.				1Points (One Point)	
6	0.00	0.00	Providing two legged scaffolding using 15cm dia- meter blue-gum posts or casurina posts or best quality bamboo posts of 4m overall length (3m height + 0.5m. in to the ground +0.5m projection) the distance between the two rows being 1.25m, and the spacing of posts being 2m, in both the rows with two horizontal posts with 0.5m overlap on either side and braces at 2m, c/c including longitudinal and transverse middle braces to step up and providing a platform with country wood planks of 40mm, thick and 1m width, etc., in a complete form using coir and nails - 1m. Run.					
a	111.00	M	a)3.00 to 5.50m Height				1RM (One Running Metre)	
b	111.00	M	d)10.50 to 13.00m Height				1RM (One Running Metre)	
7	4.50	M2	Labour charges for Painting TWAD Board Emblem in accordance with the size and specifications as approved by the Board on the Service Reservoirs including cost of all consumables, one coat of base paint. scaffolding charges including painting				1m2 (One square metre)	