

**TAMBARAM CITY MUNICIPAL CORPORATION**  
**BILL OF QUANTITIES**

Issued to Contractor Thiru / Tmt.  
Remitted in Challan No.         /dt.

Tender Date: 28.07.2022  
Upto Time: 3.00 P.M.  
Deposit: Rs.5000/-  
Estimate Amount: Rs.5,00,000/-

**Assistant Executive Engineer**  
**Tambaram City municipal Corporation**

**Name of The Work :Providing pipe Distribution line in Ward no 65 Indira nagar West Extn,Lowra St,Janigiraman st,Ward No 47  
Anthoni pella st,Ward no 63 Muthiml St,Ward no 68 Bhavani Nagar in Tambaram City Municipal Corporation.**

S. No	QTY		DESCRIPTION OF WORK	Morth and TNBPC	Rate		Unit	Amount
					In Figure	In words		
1	48.00	C.um	Dismantaling the old fully damaged Using Erath excavater machine including removal of Debrise with transporation and all oter charges etc ... copmlete. TWAD Sor 2021-2022 P.no 278 2 b				1M <sup>3</sup> (One cubic meter)	
2	358.00	C.um	Earth work excavation for foundation in all sub soils and to full depth as may be directed except hard rock requiring blasting inclusive of shorting . Stutting and bailing out water wherever necessary and refilling the sides of foundation with excavated earth in layer of 15cm thick well rammed and consolidated earth deposing the surplus earth in layers with the compound in place shown by the departmental officers with the compound in place shown by the departmental officers with initial leads and lifts and clearing and leveling the site including refilling excavated earth etc., complete as per standard specification. TWAD SOR 2021-22.P.no -261				1M <sup>3</sup> (One cubic meter)	

No. of corrections  
No.of Overwriting

Contractor Signature

S. No	QTY		DESCRIPTION OF WORK	Morth and TNBPC	Rate		Unit	Amount
					In Figure	In words		
3			Twards cost and supply of Varies size of 6 Kgs / Cm2 PVC O.D. Pipe including cost and conveyance of all materials and labour charges for loading and Unloading charges etc Complete....as per standard specification. I.S 4965/2000 2021-22. Page No 15				1M <sup>3</sup> (One cubic meter)	
	144.00	Rm	110 mm Pvc Pipe p No 21				1 Rm (one runningg Meter)	
	90.00	Rm	100 mm K 9 D.I Spi Got p.No 47				1 Rm (one runningg Meter)	
	590.00	Rm	90 mm 6 KSc P.no 21				1 Rm (one runningg Meter)	
4			Twards cost and supply of Varies size of 6 Kgs / Cm2 PVC Specials including cost and conveyance of all materials and labour charges for loading and Unloading charges etc Complete....as per standard specification. I.S 4965/2000 2021-22. Page No 15					
	2.00	Nos	110 mm Bend				1 No ( One Number)	
	9.00	Nos	160 X 110 mm Reducer				1 No ( One Number)	
	5.00	Nos	90 mm Tee				1 No ( One Number)	
	5.00	Nos	90 mm Bend				1 No ( One Number)	
	1.00	Nos	110 mm End Cap				1 No ( One Number)	
	4.00	Nos	90 mm End Cap				1 No ( One Number)	
	6.00	Nos	90 mm Valve P.no 45				1 No ( One Number)	

No. of corrections  
No. of Overwriting

Contractor Signature

S. No	QTY		DESCRIPTION OF WORK	Morth and TNBPC	Rate		Unit	Amount
					In Figure	In words		
	6.00	Nos	100 mm Valve p.no 45				1 No ( One Number)	
5			Lowering PVC rigid pipes and specials to trench and laying to proper grade and alignment,jointing with PVC couplers with cement paste.2021-22.P.no -261 - 11b(i)					
	144.00	Rm	110 mm				1 Rm (one runningg Meter)	
	90.00	Rm	100 mm K 9 D.I Spi Got p.No				1 Rm (one runningg Meter)	
	590.00	Rm	90 mm				1 Rm (one runningg Meter)	
6	331.00	Cum	Refilling with excavated soil (other than sand) complying with the standard specification for filling in foundation and basement and pipe line works as per standard specification etc...complete.2021-22.P.no - 261-19 b				1M <sup>3</sup> (One cubic meter)	