## TAMBARAM CITY MUNICIPAL CORPORATION BILL OF QUANTITIES

Issued to Contractor Thiru / Tmt.
Remitted in Challan No. /dt.

Tender Date: 28.07.2022 Upto Time: 3.00 P.M. Deposit: Rs.4700/-

Estimate Amount: Rs.4,70,000/-

## Assistant Executive Engineer Tambaram City municipal Corporation

Name of The Work :Providing pipe Distribution line in Ward no 62 Old GST road (Thilagavathi Nagar Junction to Santhosh vidiyala School ) in Tambaram City Municipal Corporation.

S.	QTY		DESCRIPTION OF WORK	Morth and	Rate			
No					In Figure	In words	Unit	Amount
1	29.50	C.um	Dismantaling the old fully damaged Using Erath excavater machine including removel of Debrise with transporation and all oter charges etc copmlete. TWAD Sor 2021-2022 P.no 278 2 b				1M <sup>3</sup> (One cubic meter)	
2	293.00 (	C.um	Earth work excavation for foundation in all sub soils and to full depth as may be directed except hard rock requiring blasting inclusive of shorting. Stutting and bailing out water wherever necessary and refilling the sides of foundation with excavated earth in layer of 15cm thick well rammed and consolidated earth deposting the surplus earth in layers with the compound in place shown by the departmental officers with the compound in place shown by the departmental officers with initial leads and lifts and clearing and leveling the site including refilling excavated earth etc, complete as per standard specification.  TWAD SOR 2021-22.P.no -261				1M <sup>3</sup> (One cubic meter)	

No. of Overwriting

Contractor Signature

In words	Unit	Amount
	Unit	Amount
	1 Rm (One	
	,	
	Meter)	
	1.00 No( One	
	Number)	
	1.00 No/ Opo	
	`	
	,	
	`	
	Number )	
	1.00 No( One	
	Number)	
		running Meter)  1 Rm ( One running Meter)  1.00 No( One Number )  1.00 No( One Number )  1.00 No( One Number )  1.00 No( One Number )

No. of Corrections No. of Overwriting

S. No	QTY		DESCRIPTION OF WORK	Morth and TNBPC	Rate			
					In Figure	In words	Unit	Amount
5			Lowering PVC rigid pipes and specials to trench and laying to proper grade and alignment, jointing with PVC couplers with cement paste.2021-22.P.no -261 - 11b(i)					
	650.00	Rm	140 mm PVC 6 Ksc				1 Rm ( One running Meter)	
	30.00	Rm	110 mm PVC 6 Ksc				1 Rm ( One running Meter)	
5	315.00	Cum	Refilling with excavated soil (other than sand) complying with the standard specification for filling in foundation and basement and pipe line works as per standard specification etccomplete.2021-22.P.no - 261-19 b				1M3(One cubic meter)	