

TAMBARAM CITY MUNICIPAL CORPORATION
BILL OF QUANTITIES

Issued to Contractor Thiru / Tmt.
Remitted in Challan No. /dt.

Tender Date: 28.07.2022
Upto Time: 3.00 P.M.
Deposit: Rs.5000/-
Estimate Amount: Rs.5,00,000/-

Assistant Executive Engineer
Tambaram City municipal Corporation

Name of The Work :Providing pipe Distribution line in Ward no 65 Ponniyaman Koil New Balaji nagar jn to New balaji NagarMadha koil Jn ,Ward No 45 Camp Road 100 feet road jn to Vasudava thirumana mandabam,Ward no 64 Venkatesan st jn to Krist king school St in Tambaram City Municipal Corporation.

S. No	QTY		DESCRIPTION OF WORK	Morth and TNBPC	Rate		Unit	Amount
					In Figure	In words		
1	50.00	C.um	Dismantaling the old fully damaged Using Erath excavater machine including removal of Debrise with transporation and all oter charges etc ... copmlete. TWAD Sor 2021-2022 P.no 278 2 b				1M ³ (One cubic meter)	
2	372.00	C.um	Earth work excavation for foundation in all sub soils and to full depth as may be directed except hard rock requiring blasting inclusive of shorting . Stutting and bailing out water wherever necessary and refilling the sides of foundation with excavated earth in layer of 15cm thick well rammed and consolidated earth deposing the surplus earth in layers with the compound in place shown by the departmental officers with the compound in place shown by the departmental officers with initial leads and lifts and clearing and leveling the site including refilling excavated earth etc., complete as per standard specification. TWAD SOR 2021-22.P.no -261				1M ³ (One cubic meter)	

No. of Corrections
No. of Overwriting

Contractor Signature

S No	QTY		DESCRIPTION OF WORK	Morth and TNBPC	Rate		Unit	Amount
					In Figure	In words		
3			Twards cost and supply of Varies size of 6 Kgs / Cm2 PVC O.D. Pipe including cost and conveyance of all materials and labour charges for loading and Unloading charges etc Complete....as per standard specification. I.S 4965/2000 2021-22. Page No 15				1M ³ (One cubic meter)	
	396.00	Rm	140 mm Pvc Pipe p No 21				1 Rm (Running Meter)	
	430.00	Rm	90 mm 6 KSc P.no 21				1 Rm (Running Meter)	
4	430.00	Rm	Twards cost and supply of Varies size of 6 Kgs / Cm2 PVC Specials including cost and conveyance of all materials and labour charges for loading and Unloading charges etc Complete....as per standard specification. I.S 4965/2000 2021-22. Page No 15				1M ³ (One cubic meter)	
	2.00	Nos	140 mm Bend Page no 27				1 No (One Number)	
	9.00	Nos	140 X 110 mm Reducer				2 No (One Number)	
	5.00	Nos	90 mm Tee				3 No (One Number)	
	5.00	Nos	90 mm Bend				4 No (One Number)	
	1.00	Nos	140 mm End Cap p no 27				5 No (One Number)	
	4.00	Nos	90 mm End Cap				6 No (One Number)	
	3.00	Nos	90 mm Valve P.no 45				7 No (One Number)	
	4.00	Nos	100 mm Valve p.no 45				8 No (One Number)	

No. of Corrections

No. of Overwriting

Contractor Signature

S No	QTY		DESCRIPTION OF WORK	Morth and TNBPC	Rate		Unit	Amount
					In Figure	In words		
5			Lowering PVC rigid pipes and specials to trench and laying to proper grade and alignment, jointing with PVC couplers with cement paste. 2021-22.P.no -261 - 11b(i)					
	396.00	Rm	140 mm PVC Pipe 6 Ksc Page no 248				1 Rm (Running Meter)	
	430.00		90 mm PVC 6 Ksc Pipe page no 248				1 Rm (Running Meter)	
6	372.00	Cum	Refilling with excavated soil (other than sand) complying with the standard specification for filling in foundation and basement and pipe line works as per standard specification etc...complete. 2021-22.P.no - 261-19 b				1M ³ (One cubic meter)	

No. of Corrections
No. of Overwriting

Contractor Signature