

TAMBARAM CITY MUNICIPAL CORPORATION

Zone V

BILL OF QUANTITIES

Issued to Contractor Thiru / Tmt.
Remitted in Challan No. /dt.

Tender Date: 28.07.2022
Upto Time: 3.00 P.M.
Deposit: Rs./-2000
Estimate Amount: Rs.2,00,000/-

**Assistant Executive Engineer
Tambaram City Municipal Corporation**

Name of Work: Development work of Eswari Nagar children Park at Zone No: V in ward No 46 in Tambaram City Municipal Corporation

S. No	QTY		DESCRIPTION OF WORK	Rate		Unit	Amount
				In Figure	In words		
1			Repair and Recondition of children playfield materials including cost and conveyance of all Materials etc complete				
	1.00	No	Double Swing			Each	
	1.00	No	Slide			Each	
	1.00	No	Jungle Jim			Each	
	1.00	No	Seesaw			Each	
	1.00	No	Meri go Round			Each	
2	6.00	Nos	Supply and fixing of 30W LED Street light fitting with LED on Out door fittings including cost and conveyance and			Each	
3	72.00	Mtr	Supply and fixing of 2.5 sqmm PVC unsheathed copper cable including cost and conveyance and fixing charges			One Meter	
4	90.00	Mtr	Supply and laying of 2 x 10 sq.mm PVC armoured LTUG cable in a trench to be excavated at a depth of 0.75			One Meter	
5	1.00	Nos	Supply and delivery of 25mm Pvc Hose in including cost and conveyance and fixing charges etc complete			Each	

No. of Corrections
No. of Overwriting

Contractor Signature

S. No	QTY		DESCRIPTION OF WORK	Rate		Unit	Amount
				In Figure	In words		
6	115.00	Kg	Repair and Reconditioning of Entrance Gate including cost and conveyance of all materials etc complete.			One kilogram	
7	6.00	Nos	Cutting the Falling Trees in Park including cost and conveyance of all materials etc complete.			Each	
8	2.00	Day	Hire charges of saw machine using petrol operation on 3' blade size including cost and conveyance and handling			One Day	
9	8.00	Nos	Cleaning the Park including cost and conveyance of all materials etc complete.			Each	
10	1.00	M2	Repair and Reconditioning of Submersible Motor including cost and conveyance of all materials etc			(One square Meter)	
11	12.00	M2	Supplying and fixing in position Cement based hydrualically pressed Anti-Skid tiles (pattern design) 20 mmthick in cement mortar 1:3 - 20mm thick & pointed with same colour of cement etc., complete as per standard specification			(One square Meter)	
12	2.00	Nos	Supply and Delivery of Stainless steel Dust bin inlcuding cost and conveyance of all materials and albour charges etc complete.			Each	
13	12.00	M3	Supply and filling of River sand for children play field area including cost and conveyance of all materials and labour charges etc complete.			(One Cubic Meter)	
14	40.00	M2	Painting new iron works such as steel doors, windows, ventilators, window bars, balustrades etc., with two coats			(One square Meter)	
15	150.00	M2	Painting two coats using Emulsion paint with including cost and conveyance of all materials and including all			(One square Meter)	

No. of Corrections
No. of Overwriting

Contractor Signature