

SCHEDULE – A

Repairs and Maintenance Of existing OHT at Ward No.14 Hospital Street in Sulur Town Panchayat

Est. No.:

Issued to : Thiru.

Estimate Amount: **12,96,000/-**

EMD.Amount : Rs. 25920/-

Tender Date & Time:

Executive officer
Sulur Town panchayat

Name of Work: Repairs and Maintenance Of existing OHT at Ward No.14 Hospital Street in Sulur Town Panchayat

- a) The quantities have given are those upon which the lump-sum tender cost at the work is caused but they are subject to alterations, omissions, deductions or additions as provided for in the conditions of the contract and do not necessarily show the actual quantities of the work to be done. The unit of rates noted below are those governing payment for extras or deductions for omission according to the conditions of the contract as set forth in the conditions and specification for the contract.
- b) It is to be expressly understood that the measured work it is to be taken out (Not withstanding any customarily practice to the contrary according to the actual quantities when the place and finished accordingly to the Drawings or as may be ordered time to time by the Special Village Panchayat Engineer and the cost calculated by works connected there with. The rate quoted is for the works in site and complete in every respect.
- c) The material required for the works must be supplied by the contractor and of the approved quality

TENDER SCHEDULE

Name of work : Repairs and Maitenance Of existing OHT at Ward No.14 Hospital Street in Sulur Town Panchayat

Estimate amount : 1296000/-

Sl. No.	Probable Quantity		Description of Work	TNDSS No.	Rate		Unit	Remark
					In Figures	In Words		
1			Providing two legged scaffolding using 15cm dia blue-gum posts of 4.0m overall length (3M HT + 0.5M projection + 0.5m into ground) the distance between two rows being 1.25m and the spacing of postsbeling 2.0m and the spacing of postsbeling 2.0m in both the rows with two horizontal posts with 0.5m overlap on either sideand braces at 2m c/cincluding longitudinal and transverse middle braces to step up and providing aplatform with country woodplanksof 40mm tk & 1.0m width in a complete form using colr and nalls - 1.0m run -- FOR REJUVENATION WORKS					
	70.00	m	0.00 -3.00 m					
	70.00	m	3.00 -5.50 m					
	70.00	m	5.50 -8.00 m					
	54.00	m	8.00 -10.50 m					
	70.00	m	10.50 -12.50 m					
2	56.00	m2	Applying Epoxy based zinc rich primer shall be done for existing rods for cathodic protection to steel rods. Applying of one coat of Heavy duty epoxy bonding agent over the parent concrete.including all materials and labour charges etc,complete.					
3	56.00	m2	Plastering with cement mortar 1:3 (One cement and three sand)10 mm thick including cost and conveyance of all materials to site including curing etc.,complete as per standard specification					
4	7678.00	Kg	Supplying and fixing of M.S grill of approved design for doors, windows and ventilators using necessary mild steel flats for inner and outer memebbers which should be fixed to window frames inclusive of priming coat of best approved quality red oxide primer etc., complete complying with standard specifications.					

5	60.00	M2	Drilling 20mm dia holes for 50mm depth in the leakage points from the external surface, Fixing 18mm dia PVC nozzles using Instant plugging mortar, Injecting cement slurry admixed with Grout Admix, Plasticised expanding grout admixture @ 225grams per bag of cement and Boscocem 475, Styrene Butadine Based mortar Modifying & Bonding Agent in the grouting points using 40psi hand operated grout pump, including all materials labour and hire charges etc, complete					
6	298.00	M2	Exterior Emulsion paint Two coats with good quality of approved Emulsion paint including cost of all materials to site and all labour charges for mixing applying and proper curing etc., Complete as per Standard Specifications					
7	55.00	m2	Painting Two Coats on new Iron works with best synthetic enamel paint of approved colour and quality including cost of all materials to site and all labour charges for mixing applying etc., Complete as per Standard Specifications					

CONDITION : Steel and Cement will not be supplied by department. Contractors should make his own arrangements.