

SCHEDULE – A

NAME OF WORK : Extension of pipe line from Kalaingar nagar to Green arch in Sulur Town Panchayat.

Est. No.:

Issued to : Thiru.

Estimate Amount: **10,00,000/-**

EMD.Amount : Rs. 20000/-

Tender Date & Time:

Executive officer
Sulur Town panchayat

Name of Work: Extension of pipe line from Kalaingar nagar to Green arch in Sulur Town Panchayat.

- a) The quantities have given are those upon which the lump-sum tender cost at the work is caused but they are subject to alterations, omissions, deductions or additions as provided for in the conditions of the contract and do not necessarily show the actual quantities of the work to be done. The unit of rates noted below are those governing payment for extras or deductions for omission according to the conditions of the contract as set forth in the conditions and specification for the contract.
- b) It is to be expressively understood that the measured work it is to be taken out (Not withstanding any customarily practice to the contrary according to the actual quantities when the place and finished accordingly to the Drawings or as may be ordered time to time by the Special Village Panchayat Engineer and the cost calculated by works connected there with. The rate quoted is for the works in site and complete in every respect.
- c) The material required for the works must be supplied by the contractor and of the approved quality

TENDER SCHEDULE

Name of work : Extension of pipe line from Kalaingar nagar to Green arch in Sulur Town Panchayat.

Estimate amount : 1000000/-

Sl. No.	Probable Quantity		Description of Work	TNDSS No.	Rate		Unit	Remark
					In Figures	In Words		
1	891.00	M3	Earth work excavating and depositing on bank with initial lead of 10 metre and initial lift of 2 metre in hard stiff clay, stiff block cotton, hard red earth, shales, murram, gravel, stoney earth and earth mixed with small size boulders as per standard specification					
2			Supply and delivery 75 mm PN6 HPDE PIPES PE 100 as per is 4984/2016including all cost and conveyance of all materials etc., complete					
	2200.00	M	90mm PN6 HPDE PIPES PE 100 as per is 4984/2016					
3			Conveying of 90 mm PN6 HPDE PIPES PE 100 as per is 4984/2016 to trench with in a lead of 200m lowering in to a trench carefully laying to proper grad and alignment to the requited pressure including conveyance of water upto 1.00km .					
	2200.00	M	90mm PN6 HPDE PIPES PE 100 as per is 4984/2016					
4	891.00	M3	Refilling with excavated earth other than sand complying with standard specification.					

CONDITION : Steel and Cement will not be supplied by department. Contractors should make his own arrangements.