

Item Rate BoQ

Tender Inviting Authority: BLOCK DEVELOPMENT OFFICER (BP)., THANJAVUR.

Name of Work: THANJAVUR DISTRICT - Special Scheme - AD Habitation - 2021-22. BT to New harijana colony road in K.Valundanpattu panchayat in Thanjavur Block.

AS .RC.No : 2100/2022/A7 Dt: 29.06.22

Name of the Bidder/ Bidding Firm / Company :						
<u>PRICE SCHEDULE</u>						
Sl. No.	Item Description	Quantity	Units	RATE exclusive of GST in figures To be entered by the Bidder Rs.    P	TOTAL AMOUNT	TOTAL AMOUNT In Words
1	2	4	5	13	54	55
	BT to New harijana colony road in K.Valundanpattu panchayat in Thanjavur Block.					
1	Earth work excavation and depositing on bank with initial lead of 10metres and lift of 2metres as per SS 20A including breaking clods,sectioning,ramming etc., complete as directed by the dept. officers for formation.(SI. No.61)	202.50	Cum			

2	Picking the Existing BT surface 50mm-100mm thick including cost conveyance and all labour charges for picking hand packing leveling and consolidation by power roller rolling including all labour charges and all other insidental charges etc.complete.	750.00	Sqm			
3	Providing and laying WBM 75 mm compacted thickness with Grade II metal using 1 cum of 75 - 22.4mm IRC HBG metal with 0.24 cum of gravel bindage per 10sqm including cost and conveyance of all materials and stacking to departmental gauge for spreading metal and gravel mix hand packing to camber including with all leads for water and compacting 80-100 KN power roller including hire charges and fuel	20.25	Cum			
4	Providing and laying WBM 75 mm compacted thickness with Grade III metal using 1 cum of 63 - 11.2mm IRC HBG metal with 0.24 cum of gravel bindage per 10sqm including cost and conveyance of all materials and stacking to departmental gauge for spreading metal and gravel mix hand packing to camber including with all leads for water and compacting 80-100 KN power roller including hire charges and fuel	168.75	Cum			
5	Providing and applying Tack coat 4 kg/10sqm over the WBM surface area including cost of Bituminous emulsion at at the site including labour charges for preparing applying the surface and applying the required quantity of emulsion Bitumen as tack coat including hire and fuel charges for bitumen sprayer etc., complete as per clause 503 of MoRD specifications.	2250.00	Sqm			

6	Providing and laying Pre-mix carpet 20mm thickness using 0.18cum of 13.20mm IRC machine crushed metal ,0.09cum of 11.2mm IRC machine crushed metal with 14.60kg of Bitumen for pre-mixing 10sqm of pre-mix carpet and laying Seal coat type"A" using 0.09cum of 6.70mm IRC HBG chips with 9.80kg bitumen including cost and conveyance of materials to the work site and stacking them to taking	2250.00	Sqm			
7	Providing and laying of Soling U.S.gravel from approved quarry including cost and conveyance to worksite to standard departmental gauge for taking pre-measurement and all other labour charges for spreading complete with standard specifications etc., complete	67.50	Cum			