

Item Rate BoQ

Tender Inviting Authority: BLOCK DEVELOPMENT OFFICER (BP)., THANJAVUR.

Name of Work: THANJAVUR DISTRICT - GF - 2020-21. Metalling to Kumbakonam Main Road to Manali Ramakrishna Polytechnic College Via Pancharam Road in Narasanayagapuram panchayat in Thanjavur Block.

AS .RC.No : 3272/2022/A2 Dt: 07.07.22

Name of the Bidder/ Bidding Firm / Company :						
<u>PRICE SCHEDULE</u>						
Sl. No.	Item Description	Quantity	Units	RATE exclusive of GST in figures To be entered by the Bidder Rs. P	TOTAL AMOUNT	TOTAL AMOUNT In Words
1	2	4	5	13	54	55
	Metalling to Kumbakonam Main Road to Manali Ramakrishna Polytechnic College Via Pancharam Road in Narasanayagapuram panchayat in Thanjavur Block.					
1	Providing and Laying Gravel to 100mm compacted thick including cost & conveyance of gravel from approved sources to work site including labour for spreading, watering and compacting by Power roller to achieve the required Proctor density at 100% compaction					

2	Km 0/0-1/0	146.16	Cum			
3	Km 1/0-2/0	29.19	Cum			
4	Km 2/0-2/6	11.13	Cum			

5	Construction of Granular Sub base by providing well graded material (25 mm to 4.75 mm IRC HBG metal @ 65 %,4.75 to 2.36mm IRC HBG metal @20%&2.36 mm below IRC HBG metal @15%)& (the material passing 425 microns sieve shall have liquid limit and plasticity index not more than 25 & 6% repectively) spreading in uniform layers with motor grader on prepared surface mixing by mix in place method with rotovator at OMC and compacting with three wheel 80-100 KN capacity and finished in accordance with the requirements of the specification and thickness as per approved plans or as directed by the Engineer (Mix -in - place method) .					
6	Km 0/0-1/0	375.00	Cum			
7	Km 1/0-2/0	375.00	Cum			

8	Km 2/0-2/6	225.00	Cum			
9	Providing and laying WBM 75 mm compacted thickness with Grade II metal using 1 cum of 75 - 22.4mm IRC HBG metal with 0.24 cum of gravel bindage per 10sqm including cost and conveyance of all materials and stacking to departmental gauge for spreading metal and gravel mix hand packing to camber including with all leads for water and compacting 80-100 KN power roller including hire charges and fuel charges for Power Roller, water sprinkler and all tools and plants employed,barricading etc., complete as per clauses 404 of MoRD specifications.					
10	Km 0/0-1/0	225.00	Cum			
11	Km 1/0-2/0	225.00	Cum			

12	Km 2/0-2/6	135.00	Cum			
----	------------	--------	-----	--	--	--